



Address: 5550 Glades Road Suite 500-1047 Boca Raton FL 33431

Call us: (689) 215-6253

E-mail: info@99estimators.com

Website: www.99estimators.com

LA QUINTA 91ST & MCDOWELL

OWNER

ARCHITECT

ADDENDA
Addendum Issued: NONE

Please review any Addendum issued after
Date 01/26/2022

99 ESTIMATORS

ID: 1616

BIDDER NAME: _____

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (PER UNIT)	EQUIPMENT (PER UNIT)	COMPOSITE RATE/UNIT	TOTAL COST
							Manhour / Unit	\$/HOUR	COST				
			010000	DIVISION 01 - GENERAL REQUIREMENTS									
1				MOBILIZATION	1	LS							
2				BOND & INSURANCE	1	LS							
3				SUPERVISION	1	LS							
4				SUBMITTALS & SAMPLES	1	LS							
5				TEMPORARY FACILITIES & CONTROLS	1	LS							
6				PROJECT SCHEDULE	1	LS							
7				CLOSEOUT PROCEDURES	1	LS							
8				PERMITS	1	LS							
				Subtotal									
			020000	DIVISION 02 - EXISTING CONDITIONS									
			022000	EARTHWORK									
9	S2.1			Footing excavation.	14155	CF							
10				Footing backfill.	2805	CF							
11				Export surplus material.	11350	CF							
				Subtotal									
			030000	DIVISION 03 - CONCRETE									
			033000	CAST IN PLACE CONCRETE									
				(2'Wx1'H) TYPE F-1, CONCRETE FOOTING									
12	S2.1			Compaction of sub-grade.	1260	SF							
13				Formwork.	1004	SF							
14				Rebar's (Grade 60)	1610	LB							
15				Concrete footing. (f'c = 3000 PSI)	1004	CF							
				(2'6"Wx1'H) TYPE F-2, CONCRETE FOOTING									
16	S2.1			Compaction of sub-grade.	45	SF							
17				Formwork.	27	SF							
18				Rebar's (Grade 60)	55	LB							
19				Concrete footing. (f'c = 3000 PSI)	34	CF							
				(3'Wx1'H) TYPE F-3, CONCRETE FOOTING									
20	S2.1			Compaction of sub-grade.	57	SF							
21				Formwork.	33	SF							
22				Rebar's (Grade 60)	80	LB							
23				Concrete footing. (f'c = 3000 PSI)	49	CF							
				(2'Wx1'H) TYPE F-4, CONCRETE FOOTING									
24	S2.1			Compaction of sub-grade.	435	SF							
25				Formwork.	345	SF							
26				Rebar's (Grade 60)	555	LB							
27				Concrete footing. (f'c = 3000 PSI)	345	CF							
				(2'6"Wx1'H) TYPE F-5, CONCRETE FOOTING									
28	S2.1			Compaction of sub-grade.	1340	SF							
29				Formwork.	892	SF							
30				Rebar's (Grade 60)	1784	LB							
31				Concrete footing. (f'c = 3000 PSI)	1115	CF							
				(3'Wx1'H) TYPE F-6, CONCRETE FOOTING									
32	S2.1			Compaction of sub-grade.	80	SF							
33				Formwork.	46	SF							
34				Rebar's (Grade 60)	110	LB							
35				Concrete footing. (f'c = 3000 PSI)	69	CF							
				(3'6"Wx1'H) TYPE F-7, CONCRETE FOOTING									
36	S2.1			Compaction of sub-grade.	92	SF							
37				Formwork.	46	SF							
38				Rebar's (Grade 60)	130	LB							
39				Concrete footing. (f'c = 3000 PSI)	81	CF							
				(3'6"SQ.x1'H) TYPE F-8, CONCRETE FOOTING PAD (7 EA)									
40	S2.1			Compaction of sub-grade.	112	SF							
41				Formwork.	98	SF							
42				Rebar's (Grade 60)	140	LB							
43				Concrete footing. (f'c = 3000 PSI)	86	CF							
				(4'SQ.x1'H) TYPE F-9, CONCRETE FOOTING PAD (4 EA)									
44	S2.1			Compaction of sub-grade.	81	SF							
45				Formwork.	64	SF							
46				Rebar's (Grade 60)	105	LB							
47				Concrete footing. (f'c = 3000 PSI)	64	CF							
				(6'SQ.x1'H) TYPE F-10, CONCRETE FOOTING PAD (2 EA)									
48	S2.1			Compaction of sub-grade.	85	SF							
49				Formwork.	48	SF							
50				Rebar's (Grade 60)	115	LB							
51				Concrete footing. (f'c = 3000 PSI)	72	CF							
				(6'6"SQ.x1'2"H) TYPE F-11, CONCRETE FOOTING PAD (2 EA)									
52	S2.1			Compaction of sub-grade.	98	SF							
53				Formwork.	61	SF							
54				Rebar's (Grade 60)	160	LB							
55				Concrete footing. (f'c = 3000 PSI)	99	CF							
				(7'SQ.x1'2"H) TYPE F-12, CONCRETE FOOTING PAD (1 EA)									
56	S2.1			Compaction of sub-grade.	57	SF							
57				Formwork.	33	SF							
58				Rebar's (Grade 60)	95	LB							
59				Concrete footing. (f'c = 3000 PSI)	58	CF							
				(3'SQ.x1'H) TYPE F-13, CONCRETE FOOTING PAD (1 EA)									
60	S2.1			Compaction of sub-grade.	13	SF							
61				Formwork.	12	SF							
62				Rebar's (Grade 60)	15	LB							
63				Concrete footing. (f'c = 3000 PSI)	9	CF							
				(3'6"SQ.x1'H) TYPE F-14, CONCRETE FOOTING PAD (11 EA)									
64	S2.1			Compaction of sub-grade.	176	SF							
65				Formwork.	154	SF							
66				Rebar's (Grade 60)	216	LB							
67				Concrete footing. (f'c = 3000 PSI)	135	CF							
				(4'SQ.x1'H) TYPE F-15, CONCRETE FOOTING PAD (12 EA)									
68	S2.1			Compaction of sub-grade.	243	SF							
69				Formwork.	192	SF							

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (PER UNIT)	EQUIPMENT (PER UNIT)	COMPOSITE RATE/UNIT	TOTAL COST
							Manhour / Unit	\$/HOUR	COST				
70				Rebar's (Grade 60)	310	LB							
71				Concrete footing. (f'c = 3000 PSI)	192	CF							
				(4'6"SQ.x1'H) TYPE F-16, CONCRETE FOOTING PAD (2 EA)									
72	S2.1			Compaction of sub-grade.	50	SF							
73				Formwork.	36	SF							
74				Rebar's (Grade 60)	66	LB							
75				Concrete footing. (f'c = 3000 PSI)	41	CF							
				(5'SQ.x1'H) TYPE F-17, CONCRETE FOOTING PAD (2 EA)									
76	S2.1			Compaction of sub-grade.	61	SF							
77				Formwork.	40	SF							
78				Rebar's (Grade 60)	80	LB							
79				Concrete footing. (f'c = 3000 PSI)	50	CF							
				(4'6"SQ.x1'H) TYPE F-18, CONCRETE FOOTING PAD (3 EA)									
80	S2.1			Compaction of sub-grade.	75	SF							
81				Formwork.	54	SF							
82				Rebar's (Grade 60)	100	LB							
83				Concrete footing. (f'c = 3000 PSI)	61	CF							
				(5'SQ.x1'H) TYPE F-19, CONCRETE FOOTING PAD (1 EA)									
84	S2.1			Compaction of sub-grade.	30	SF							
85				Formwork.	20	SF							
86				Rebar's (Grade 60)	40	LB							
87				Concrete footing. (f'c = 3000 PSI)	25	CF							
				(5'6"SQ.x1'H) TYPE F-20, CONCRETE FOOTING PAD (3 EA)									
88	S2.1			Compaction of sub-grade.	108	SF							
89				Formwork.	66	SF							
90				Rebar's (Grade 60)	146	LB							
91				Concrete footing. (f'c = 3000 PSI)	91	CF							
				(6'SQ.x1'H) TYPE F-21, CONCRETE FOOTING PAD (1 EA)									
92	S2.1			Compaction of sub-grade.	43	SF							
93				Formwork.	24	SF							
94				Rebar's (Grade 60)	60	LB							
95				Concrete footing. (f'c = 3000 PSI)	36	CF							
				(6'6"SQ.x1'2"H) TYPE F-22, CONCRETE FOOTING PAD (1 EA)									
96	S2.1			Compaction of sub-grade.	49	SF							
97				Formwork.	30	SF							
98				Rebar's (Grade 60)	80	LB							
99				Concrete footing. (f'c = 3000 PSI)	50	CF							
				(7'SQ.x1'2"H) TYPE F-23, CONCRETE FOOTING PAD (2 EA)									
100	S2.1			Compaction of sub-grade.	113	SF							
101				Formwork.	65	SF							
102				Rebar's (Grade 60)	184	LB							
103				Concrete footing. (f'c = 3000 PSI)	115	CF							
				(7'6"SQ.x1'2"H) TYPE F-24, CONCRETE FOOTING PAD (1 EA)									
104	S2.1			Compaction of sub-grade.	64	SF							
105				Formwork.	35	SF							
106				Rebar's (Grade 60)	106	LB							
107				Concrete footing. (f'c = 3000 PSI)	66	CF							
				(8'SQ.x1'4"H) TYPE F-25, CONCRETE FOOTING PAD (1 EA)									
108	S2.1			Compaction of sub-grade.	75	SF							
109				Formwork.	43	SF							
110				Rebar's (Grade 60)	140	LB							
111				Concrete footing. (f'c = 3000 PSI)	85	CF							
				(9'SQ.x1'6"H) TYPE F-26, CONCRETE FOOTING PAD (1 EA)									
112	S2.1			Compaction of sub-grade.	90	SF							
113				Formwork.	54	SF							
114				Rebar's (Grade 60)	215	LB							
115				Concrete footing. (f'c = 3000 PSI)	122	CF							
				(8'SQ.x1'4"H) TYPE F-27, CONCRETE FOOTING PAD (1 EA)									
116	S2.1			Compaction of sub-grade.	75	SF							
117				Formwork.	43	SF							
118				Rebar's (Grade 60)	140	LB							
119				Concrete footing. (f'c = 3000 PSI)	85	CF							
				(9'Wx14'Lx1'6"H) TYPE F-28, CONCRETE FOOTING PAD (1 EA)									
120	S2.1			Compaction of sub-grade.	138	SF							
121				Formwork.	69	SF							
122				Rebar's (Grade 60)	330	LB							
123				Concrete footing. (f'c = 3000 PSI)	189	CF							
				(3'SQ.x1'H) TYPE F-29, CONCRETE FOOTING PAD (1 EA)									
124	S2.1			Compaction of sub-grade.	13	SF							
125				Formwork.	12	SF							
126				Rebar's (Grade 60)	15	LB							
127				Concrete footing. (f'c = 3000 PSI)	9	CF							
				(3'SQ.x1'H) TYPE F-30, CONCRETE FOOTING PAD (1 EA)									
128	S2.1			Compaction of sub-grade.	13	SF							
129				Formwork.	12	SF							
130				Rebar's (Grade 60)	15	LB							
131				Concrete footing. (f'c = 3000 PSI)	9	CF							
				(4'SQ.x1'H) TYPE F-31, CONCRETE FOOTING PAD (1 EA)									
132	S2.1			Compaction of sub-grade.	21	SF							
133				Formwork.	16	SF							
134				Rebar's (Grade 60)	25	LB							
135				Concrete footing. (f'c = 3000 PSI)	16	CF							
				(5'SQ.x1'H) TYPE F-32, CONCRETE FOOTING PAD (1 EA)									
136	S2.1			Compaction of sub-grade.	30	SF							
137				Formwork.	20	SF							
138				Rebar's (Grade 60)	40	LB							
139				Concrete footing. (f'c = 3000 PSI)	25	CF							
				(8'SQ.x1'4"H) TYPE F-33, CONCRETE FOOTING PAD (1 EA)									
140	S2.1			Compaction of sub-grade.	75	SF							

#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (PER UNIT)	EQUIPMENT (PER UNIT)	COMPOSITE RATE/UNIT	TOTAL COST
							Manhour / Unit	\$/HOUR	COST				
141	S2.1			Formwork.	43	SF							
142				Rebar's (Grade 60)	140	LB							
143				Concrete footing. (f'c = 3000 PSI)	85	CF							
				(8'SQ.x1'4"H) TYPE F-34, CONCRETE FOOTING PAD (1 EA)									
144				Compaction of sub-grade.	75	SF							
145				Formwork.	43	SF							
146				Rebar's (Grade 60)	140	LB							
147				Concrete footing. (f'c = 3000 PSI)	85	CF							
	S2.1			(9'SQ.x1'6"H) TYPE F-35, CONCRETE FOOTING PAD (1 EA)									
148				Compaction of sub-grade.	90	SF							
149				Formwork.	54	SF							
150				Rebar's (Grade 60)	215	LB							
151				Concrete footing. (f'c = 3000 PSI)	122	CF							
	S2.1			(9'6"SQ.x1'6"H) TYPE F-36, CONCRETE FOOTING PAD (1 EA)									
152				Compaction of sub-grade.	100	SF							
153				Formwork.	57	SF							
154				Rebar's (Grade 60)	240	LB							
155				Concrete footing. (f'c = 3000 PSI)	136	CF							
	S2.1			(10'6"SQ.x1'8"H) TYPE F-37, CONCRETE FOOTING PAD (1 EA)									
156				Compaction of sub-grade.	121	SF							
157				Formwork.	70	SF							
158				Rebar's (Grade 60)	322	LB							
159				Concrete footing. (f'c = 3000 PSI)	184	CF							
	S2.1			(12" THK) ELEVATOR CONCRETE FOOTING PAD									
160				Compaction of sub-grade.	230	SF							
161				Formwork.	32	SF							
162				Rebar's (Grade 60)	520	LB							
163				Concrete footing. (f'c = 3000 PSI)	230	CF							
	A2.8			(10" SQ.x2'H) CONCRETE FOOTING PAD (24 EA)									
164				Compaction of sub-grade.	45	SF							
165				Rebar's (Grade 60)	60	LB							
166				Concrete footing. (f'c = 3000 PSI)	35	CF							
	S2.1			CONCRETE WALL									
167				Formwork.	440	SF							
168				Rebar's (Grade 60)	330	LB							
169				(8" THK) Concrete wall. (f'c = 3000 PSI)	147	CF							
	S2.2			SLAB ON GRADE									
170				Compaction of sub-grade.	13790	SF							
171				(4" THK) Drainage gravel fill.	13790	SF							
172				(10 MIL) Vapor barrier.	13790	SF							
173				Rebar's (Grade 60)	16550	LB							
174				(4" THK) Slab on grade. (f'c = 3000 PSI)	13790	SF							
	S2.2			SLAB ON GRADE									
175				Compaction of sub-grade.	50	SF							
176				(4" THK) Drainage gravel fill.	50	SF							
177				(10 MIL) Vapor barrier.	50	SF							
178				Rebar's (Grade 60)	75	LB							
179				(12" THK) Slab on grade. (f'c = 3000 PSI)	50	SF							
	A2.6			HOUSKEEPING CONCRETE PAD									
180				Rebar's (Grade 60)	80	LB							
181				(4" THK) Houskeeping concrete pad. (f'c = 3000 PSI)	55	SF							
	A2.8			(6'Wx10'Lx1'6"H) FIREPIT CONCRETE FOOTING PAD (1 EA) NOTE: PAD DETAIL NOT GIVEN ON DRAWINGS SO, WE HAVE ASSUMED THESE ITEMS)									
182				Compaction of sub-grade.	70	SF							
183				Formwork.	48	SF							
184				Rebar's (Grade 60)	205	LB							
185				Concrete footing. (f'c = 3000 PSI)	90	CF							
	A2.8			POOL WALL NOTE: WALL DETAIL NOT GIVEN ON DRAWINGS SO, WE HAVE ASSUMED THESE ITEMS)									
186				Waterproofing membrane.	630	SF							
187				Rebar's (Grade 60)	1370	LB							
188				(10" THK) Concrete wall. (f'c = 3000 PSI)	96	CF							
189				(12" THK) Concrete wall. (f'c = 3000 PSI)	512	CF							
	A2.8			POOL DECK SLAB NOTE: SLAB DETAIL NOT GIVEN ON DRAWINGS SO, WE HAVE ASSUMED THESE ITEMS)									
190				Compaction of sub-grade.	2445	SF							
191				(4" THK) Drainage gravel fill.	2445	SF							
192				(10 MIL) Vapor barrier.	2445	SF							
193				Rebar's (Grade 60)	3670	LB							
194				(4" THK) Concrete slab. (f'c = 3000 PSI)	2445	SF							
	A2.8			POOL SLAB NOTE: SLAB DETAIL NOT GIVEN ON DRAWINGS SO, WE HAVE ASSUMED THESE ITEMS)									
195				Compaction of sub-grade.	1060	SF							
196				(6" THK) Drainage gravel fill.	1060	SF							
197				(10 MIL) Vapor barrier.	1060	SF							
198				Rebar's (Grade 60)	2380	LB							
199				(6" THK) Concrete slab. (f'c = 3000 PSI)	1060	SF							
	A2.8			POOL STAIR SLAB & STEPS NOTE: SLAB DETAIL NOT GIVEN ON DRAWINGS SO, WE HAVE ASSUMED THESE ITEMS)									
200				Rebar's (Grade 60)	85	LB							
201				(6" THK) Stair slab & steps. (f'c = 3000 PSI)	40	CF							
202	A2.8			(10"W) Pool Precast coping.	30	LF							
203				(12"W) Pool Precast coping.	130	LF							
				Subtotal									

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (PER UNIT)	EQUIPMENT (PER UNIT)	COMPOSITE RATE/UNIT	TOTAL COST
							Manhour / Unit	\$/HOUR	COST				
			050000	DIVISION 05 - METAL									
			051200	STRUCTURAL STEEL									
205	S3.1 to S3.9			(10x10x3/4) Base plate. (6 EA)	128	LB							
206				(11x11x3/4) Base plate. (52 EA)	1335	LB							
207				(12x12x7/8) Base plate. (2 EA)	72	LB							
208				HSS4x4x3/16 (6 EA)	792	LB							
209				HSS5x5x3/16 (47 EA)	6488	LB							
210				HSS5x5x1/4 (5 EA)	1094	LB							
211				HSS6x6x1/4 (2 EA)	533	LB							
212				W18x40 (8 EA)	4480	LB							
213				W24x76 (1 EA)	1102	LB							
214				HSS4x4x1/4	2012	LB							
215				HSS4x4x1/4 Truss	4961	LB							
216				HSS5x5x3/16	396	LB							
217				W6x20	459	LB							
218				W8x28	509	LB							
219				W12x30	310	LB							
220				W16x31	1558	LB							
221				W18x35	708	LB							
222				W18x40	2935	LB							
223				W21x44	1150	LB							
224				W21x50	2725	LB							
225				W24x55	4589	LB							
226				W24x62	3610	LB							
227				W24x68	8959	LB							
228				W24x76	3410	LB							
229				W24x84	7659	LB							
230				W27x84	2973	LB							
231				L3x3x1/4	689	LB							
232				L4x4x1/4	538	LB							
233				L4x4x3/4	888	LB							
234				RC-1 Type 1/2" Resilient Channel @24" O.C.	19050	LF							
235	A2.1 to A7.3			(1HR)TYPE 01 GWB INTERIOR WALL (4565LF)									
236	A2.1 to A7.3			(7/8") Hat Channel W/RSIC-1 @16" O.C.	33964	LF							
237				(7/8") Hat Channel W/RSIC-1 @48" O.C.	15850	LF							
				(2HR)TYPE 02 GWB INTERIOR WALL (517LF)									
				(1/2") Resilient Channel @48" O.C.	1863	LF							
				STEEL BEAM FRAMING (30LF)									
238	A2.1 to A7.3			(3 5/8") Metal Studs @16" O.C. (Actual Length; 178) Note: Standard length; 2 ft (190LF)	95	EA							
239	A2.1 to A7.3			(3 5/8") Metal Top and Bottom Track (Actual Length; 240) Note: Standard length; 10 ft (240LF)	24	EA							
				STEEL BEAM FRAMING (407LF)									
240				(8") Metal Track (Actual Length; 407) Note: Standard length; 10 ft (410LF)	41	EA							
241				(1 1/2 x 1 1/2 x 1/4) Angle	814	LF							
			053000	METAL DECK									
242	S3.1 to S3.9			(1-1/2") 20 GA. Painted steel roof.	1345	SF							
			055000	METAL FABRICATIONS									
243	A2.1 to A7.3			Access Ladder	45	LF							
244				Pre-Fabricated Awning	200	SF							
245				Steel Plate Housing for Nightlatch	2	EA							
246				MISC. Item.	1	LS							
			057000	ORNAMENTAL METAL									
247	A2.1 to A7.3			HSS Guardrail w/ (HSS 2"x2"x3/16") Top & Bottom rail and Vertical Supports and (HSS 1"x1"x1/8") Balusters @4" O.C. (3'-6"H)	165	LF							
248				(1-1/2") NOM. DIA Standard Weight Steel Pipe Handrail	330	LF							
				Subtotal									
			060000	DIVISION 06 - WOOD, PLASTIC AND COMPOSITES									
			061053	WOOD FRAMING									
				WOOD POSTS - DOUGLAS FIR-LARCH STUD									
249	S3.1 to S3.9			(2x6) P.T KING STUD POST (Actual length; 3458 LF) Note: Standard length; 14 ft (3458 LF)	247	EA							
250				(2x6) KING STUD POST (Actual length; 8470 LF) Note: Standard length; 10 ft (9240 LF)	924	EA							
251				(1-1/2"x5-1/2") P.T 1.6E LSL POST (Actual length; 182 LF) Note: Standard length; 10 ft (182 LF)	13	EA							
				WOOD BEAMS - #2 DOUGLAS FIR-LARCH									
252				(2x4) BLOCKING (Actual length; 39 LF) Note: Standard length; 10 ft (40 LF)	4	EA							
253				(2x6) BLOCKING (Actual length; 562 LF) Note: Standard length; 10 ft (570 LF)	57	EA							
254				(2x8) LEDGER (Actual length; 1107 LF) Note: Standard length; 10 ft (1110 LF)	111	EA							
255				(2x6) HEADER BEAM (Actual length; 20 LF) Note: Standard length; 6 ft (24 LF)	4	EA							
256				(2x8) HEADER BEAM (Actual length; 322 LF) Note: Standard length; 4 ft (416 LF)	104	EA							
257				(2x8) HEADER BEAM (Actual length; 670 LF) Note: Standard length; 6 ft (888 LF)	148	EA							
258				(2x8) HEADER BEAM (Actual length; 84 LF) Note: Standard length; 8 ft (96 LF)	12	EA							
259				(2x8) HEADER BEAM (Actual length; 56 LF) Note: Standard length; 10 ft (60 LF)	6	EA							
260				(2x10) HEADER BEAM (Actual length; 17 LF) Note: Standard length; 4 ft (20 LF)	5	EA							
261				(2x10) HEADER BEAM (Actual length; 11 LF) Note: Standard length; 6 ft (12 LF)	2	EA							
262				(2x10) HEADER BEAM (Actual length; 346 LF) Note: Standard length; 8 ft (392 LF)	49	EA							
263				(2x10) HEADER BEAM (Actual length; 109 LF) Note: Standard length; 10 ft (110 LF)	11	EA							
264				(1-3/4"x9-1/2") LVL BEAM (Actual length; 36 LF) Note: Standard length; 4 ft (40 LF)	10	EA							
265				(1-3/4"x9-1/2") LVL BEAM (Actual length; 12 LF) Note: Standard length; 6 ft (12 LF)	2	EA							
266				(1-3/4"x9-1/2") LVL BEAM (Actual length; 28 LF) Note: Standard length; 8 ft (32 LF)	4	EA							

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (PER UNIT)	EQUIPMENT (PER UNIT)	COMPOSITE RATE/UNIT	TOTAL COST
							Manhour / Unit	\$/HOUR	COST				
267	S3.1 to S3.9			(1-3/4"x9-1/2") LVL BEAM (Actual length; 231 LF) Note: Standard length; 10 ft (240 LF)	24	EA							
268				(1-3/4"x11-7/8") LVL BEAM (Actual length; 7 LF) Note: Standard length; 4 ft (12 LF)	3	EA							
269				(1-3/4"x11-7/8") LVL BEAM (Actual length; 141 LF) Note: Standard length; 6 ft (162 LF)	27	EA							
270				(1-3/4"x11-7/8") LVL BEAM (Actual length; 83 LF) Note: Standard length; 8 ft (96 LF)	12	EA							
271				(1-3/4"x11-7/8") LVL BEAM (Actual length; 869 LF) Note: Standard length; 10 ft (920 LF)	92	EA							
272				(1-3/4"x11-7/8") LVL BEAM (Actual length; 173 LF) Note: Standard length; 12 ft (192 LF)	16	EA							
273				(1-3/4"x11-7/8") LVL BEAM (Actual length; 303 LF) Note: Standard length; 14 ft (336 LF)	24	EA							
274				(5-1/4"x11-7/8") LVL BEAM (Actual length; 7 LF) Note: Standard length; 8 ft (8 LF)	1	EA							
275				(5-1/4"x11-7/8") LVL BEAM (Actual length; 27 LF) Note: Standard length; 10 ft (30 LF)	3	EA							
276				(5-1/4"x11-7/8") LVL BEAM (Actual length; 26 LF) Note: Standard length; 14 ft (28 LF)	2	EA							
277				(7"x9-1/2") LVL BEAM (Actual length; 10 LF) Note: Standard length; 10 ft (10 LF)	1	EA							
278				(7"x11-7/8") LVL BEAM (Actual length; 8 LF) Note: Standard length; 8 ft (8 LF)	1	EA							
279				(7"x11-7/8") LVL BEAM (Actual length; 25 LF) Note: Standard length; 10 ft (30 LF)	3	EA							
280				(7"x11-7/8") LVL BEAM (Actual length; 38 LF) Note: Standard length; 14 ft (42 LF)	3	EA							
281				(7"x11-7/8") LVL BEAM (Actual length; 16 LF) Note: Standard length; 16 ft (16 LF)	1	EA							
282				(7"x14") LVL BEAM (Actual length; 75 LF) Note: Standard length; 14 ft (84 LF)	6	EA							
283				(7"x16") LVL BEAM (Actual length; 16 LF) Note: Standard length; 16 ft (16 LF)	1	EA							
284				(5-1/8"x15") GLB BEAM (Actual length; 16 LF) Note: Standard length; 16 ft (16 LF)	1	EA							
285	S3.1 to S3.9			FLOOR / ROOF JOISTS - #2 DOUGLAS FIR-LARCH 11-7/8" LPI 20 PLUS FLOOR JOISTS (Actual length; 153 LF) Note: Standard length; 6 ft (168 LF)	28	EA							
286				11-7/8" LPI 20 PLUS FLOOR JOISTS (Actual length; 229 LF) Note: Standard length; 8 ft (248 LF)	31	EA							
287				11-7/8" LPI 20 PLUS FLOOR JOISTS (Actual length; 385 LF) Note: Standard length; 10 ft (390 LF)	39	EA							
288				11-7/8" LPI 20 PLUS FLOOR JOISTS (Actual length; 81 LF) Note: Standard length; 12 ft (96 LF)	8	EA							
289				11-7/8" LPI 20 PLUS FLOOR JOISTS (Actual length; 20081 LF) Note: Standard length; 14 ft (21266 LF)	1519	EA							
290				11-7/8" LPI 20 PLUS FLOOR JOISTS (Actual length; 178 LF) Note: Standard length; 16 ft (192 LF)	12	EA							
291				11-7/8" LPI 20 PLUS FLOOR JOISTS (Actual length; 1390 LF) Note: Standard length; 18 ft (1530 LF)	85	EA							
292				11-7/8" LPI 32 PLUS FLOOR JOISTS (Actual length; 84 LF) Note: Standard length; 12 ft (84 LF)	7	EA							
293				11-7/8" LPI 32 PLUS FLOOR JOISTS (Actual length; 271 LF) Note: Standard length; 14 ft (308 LF)	22	EA							
294				11-7/8" LPI 52 PLUS FLOOR JOISTS (Actual length; 30 LF) Note: Standard length; 10 ft (30 LF)	3	EA							
295				(2x8) FLOOR JOISTS (Actual length; 251 LF) Note: Standard length; 6 ft (270 LF)	45	EA							
296				(2x8) FLOOR JOISTS (Actual length; 3525 LF) Note: Standard length; 8 ft (4320 LF)	540	EA							
297				(2x8) FLOOR JOISTS (Actual length; 97 LF) Note: Standard length; 10 ft (100 LF)	10	EA							
298				(2x8) FLOOR JOISTS (Actual length; 122 LF) Note: Standard length; 12 ft (132 LF)	11	EA							
299				(1-1/4") RIM JOISTS (Actual length; 1865 LF) Note: Standard length; 10 ft (1870 LF)	187	EA							
300				(2x8) ROOF RAFTERS (Actual length; 69 LF) Note: Standard length; 8 ft (80 LF)	10	EA							
301				(2x8) ROOF RAFTERS (Actual length; 814 LF) Note: Standard length; 10 ft (860 LF)	86	EA							
302				(2x10) ROOF RAFTERS (Actual length; 83 LF) Note: Standard length; 4 ft (112 LF)	28	EA							
303				(2x10) ROOF RAFTERS (Actual length; 107 LF) Note: Standard length; 6 ft (132 LF)	22	EA							
304				(2x10) ROOF RAFTERS (Actual length; 896 LF) Note: Standard length; 8 ft (1000 LF)	125	EA							
305				(2x12) STAIR STRINGER (Actual length; 101 LF) Note: Standard length; 10 ft (120 LF)	12	EA							
306				(2x12) STAIR STRINGER (Actual length; 257 LF) Note: Standard length; 12 ft (288 LF)	24	EA							
307				(2x12) STAIR STRINGER (Actual length; 148 LF) Note: Standard length; 14 ft (168 LF)	12	EA							
308	S3.8			ROOF TRUSSES PRE-Manufactured roof trusses	6185	LF							
309	S3.1 to S3.9			WALL BRACING - DOUGLAS FIR-LARCH STUD (2x4) BRACING (Actual length; 212 LF) Note: Standard length; 4 ft (212 LF)	53	EA							
310				(2x6) BRACING (Actual length; 60 LF) Note: Standard length; 6 ft (72 LF)	12	EA							
311				(2x6) BRACING (Actual length; 208 LF) Note: Standard length; 8 ft (208 LF)	26	EA							
312				(2x6) BRACING (Actual length; 1840 LF) Note: Standard length; 20 ft (1840 LF)	92	EA							
313	A2.1 to A7.3			(1HR)TYPE 01 GWB INTERIOR WALL - DOUGLAS FIR-LARCH STUD (4565LF) (2x6) Wood Studs @16" O.C. (Actual Length; 8549) Note: Standard length; 14 ft (9450LF)	675	EA							
314				(2x6) Wood Studs @16" O.C. (Actual Length; 50) Note: Standard length; 4 ft (76LF)	19	EA							
315				(2x6) Wood Studs @16" O.C. (Actual Length; 25366) Note: Standard length; 10 ft (27430LF)	2743	EA							
316				(2x6) P.T. Wood Bottom Track (Actual Length; 896) Note: Standard length; 10 ft (900LF)	90	EA							

#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (PER UNIT)	EQUIPMENT (PER UNIT)	COMPOSITE RATE/UNIT	TOTAL COST
							Manhour / Unit	\$/HOUR	COST				
360	A2.1 to A7.3			(2x4) Wood Studs @16" O.C. (Actual Length; 131) Note: Standard length; 2 ft (262LF)	131	EA							
361				(2x4) Top and Bottom Tracks (Actual Length; 344) Note: Standard length; 10 ft (350LF)	35	EA							
				PARAPET WALLS - DOUGLAS FIR-LARCH STUD									
362				(2x4) PARAPET WALL (Actual length; 177 LF) Note: Standard length; 4 ft (228 LF)	57	EA							
363				(2x4) PARAPET WALL (Actual length; 1156 LF) Note: Standard length; 6 ft (1176 LF)	196	EA							
364				(2x4) PARAPET WALL (Actual length; 325 LF) Note: Standard length; 8 ft (400 LF)	50	EA							
365				(2x4) PARAPET WALL (Actual length; 1210 LF) Note: Standard length; 16 ft (1312 LF)	82	EA							
366	S3.1 to S3.9			(2x6) PARAPET WALL (Actual length; 84 LF) Note: Standard length; 4 ft (84 LF)	21	EA							
367				(2x6) PARAPET WALL (Actual length; 546 LF) Note: Standard length; 8 ft (672 LF)	84	EA							
368				(2x4) PARAPET WALL (Actual length; 2272 LF) Note: Standard length; 16 ft (2464 LF)	154	EA							
369				(2x4) TOP & BOTTOM TRACK Note: Standard length; 10 ft (2280 LF)	228	EA							
370				(2x6) TOP & BOTTOM TRACK Note: Standard length; 10 ft (1540 LF)	154	EA							
371				SIMPSON A35	990	EA							
372				SIMPSON LU210	1125	EA							
373				USP FWH25118 Fire wall hanger.	547	EA							
374				SIMPSON ITS2.56/11.88	414	EA							
375				SIMPSON MIT3511.88	88	EA							
376				SIMPSON BA3.56/11.88	2	EA							
377				SIMPSON H1 Tie	446	EA							
378				SIMPSON JB28	38	EA							
379				SIMPSON T59	255	EA							
380				CS16x48	59	EA							
381				DTT2Z-SDS2.5	15	EA							
382				HDU2-SDS2.5	9	EA							
383				HDU8-SDS2.5	4	EA							
384				LSTHD8	2	EA							
061000				ROUGH CARPENTRY									
385	S3.1 to S3.9			(3/4") APA RATED STRUCT. II PLYWOOD FLOOR SHEATHING Note: Standard Size; 4x8 (40620 SF)	1270	EA							
386				(7/16") APA RATED PLYWOOD SHEARWALL SHEATHING Note: Standard Size; 4x8 (25460 SF)	796	EA							
387				(7/16") APA RATED PLYWOOD ROOF SHEATHING Note: Standard Size; 4x8 (15640 SF)	489	EA							
388				Plastic Laminate Plywood	105	SF							
389	A2.1 to A7.3			TYPE 04 GWB EXTERIOR WALL (2863LF) (7/16") APA Rated Sheathing	24244	SF							
390				(5/8", 1Layer) Glass Mat Sheathing	27794	SF							
391	A2.1 to A7.3			EXTERIOR BULKHEAD FRAMING (104LF) (7/16") APA Rated Sheathing	633	SF							
062000				FINISH CARPENTRY									
	A2.1 to A7.3			(4'-0"L x 11"W) Wood Tread		EA							
				(4'-0"L x 7"W) Wood Riser		EA							
064100				ARCHITECTURAL WOOD CASEWORK									
392	A2.1 to A7.3			(12"L x 20"W x 2'10"H) Base Cabinets (1EA)	34	SF							
393				(174"L x 20"W x 2'10"H) Base Cabinets (1EA)	50	SF							
394				(20"L x 20"W x 2'10"H) Base Cabinets (4EA)	23	SF							
395				(2'3"L x 20"W x 2'10"H) Base Cabinets (2EA)	13	SF							
396				(23'0"L x 20"W x 2'10"H) Base Cabinets (1EA)	65	SF							
397				(3'9"L x 20"W x 2'10"H) Base Cabinets (1EA)	11	SF							
398				(4'8"L x 20"W x 2'10"H) Base Cabinets (1EA)	14	SF							
399				(5'0"L x 2'6"W x 7'0"H) Cabinet Unit (1EA)	35	SF							
400				(6'0"L x 20"W x 2'10"H) Plastic Laminate Base Cabinet (2EA)	34	SF							
401				(6'10"L x 2'0"D x 2'6"H) Base Cabinets (1EA)	17	SF							
402				(6'2"L x 20"W x 2'10"H) Base Cabinets (1EA)	18	SF							
403				(7'0"L x 2'0"D x 2'10"H) Base Cabinets (1EA)	20	SF							
404				(8'0"L x 1'8"W x 3'3"H) Base Cabinets (1EA)	26	SF							
405				(9'3"L x 2'0"W x 2'10"H) Base Cabinets (1EA)	27	SF							
406				(7'0"L x 1'0"D x 2'6"H) Wall Cabinets (1EA)	18	SF							
407				Storage Shelves (2D)	73	LF							
408				Closet Shelf (1D)	247	LF							
409				Coat Closet Rod	295	LF							
410				(3'-2"W x 6'-0"H) Semi Recessed Display	1	EA							
411				(6'10"L x 2'0"D x 4'8"H) Shelving Unit	1	EA							
				Subtotal									
070000				DIVISION 07 - THERMAL AND MOISTURE PROTECTION									
412	A2.1 to A7.3			Vapor Barrier	9185	SF							
413				60-MIL Single Ply TPO Roof Membrane - White Color	10305	SF							
414				Grey 60-MIL Single Ply TPO Roof Membrane	2520	SF							
415				Roof Rigid Insulation	17830	SF							
416				Walkway Pad	650	SF							
417				TPO Roofing Membrane	260	SF							
418				Aluminum Drip Edge Flashing	15	LF							
419				Metal Flashing	330	LF							
420				ICE and Water Shield (2'-6"W)	335	LF							
421				(8") Unfaced Glass Fiber Insulation	40620	SF							
422				(3/4") Gypcrete	40620	SF							
423				(1/4") Soundmat	8850	SF							
424				Aluminum Coping	420	LF							
425				Aluminum Drip Edge Flashing	30	LF							
426	A2.1 to A7.3			(1HR)TYPE 01 GWB INTERIOR WALL (4565LF) R-21 Batt Insulation	45139	SF							
427	A2.1 to A7.3			(2HR)TYPE 02 GWB INTERIOR WALL (517LF) R-21 Batt Insulation	5466	LF							
428	A2.1 to A7.3			TYPE 03A GWB INTERIOR WALL (189LF) R-15 Batt Insulation	2018	SF							
429	A2.1 to A7.3			TYPE 04 GWB EXTERIOR WALL (2863LF) R-21 Batt Insulation	27794	SF							
430				(1 1/2") Rigid Foam	16785	SF							
	A2.1 to			STEEL BEAM FRAMING (30LF)									

[illegible]

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (PER UNIT)	EQUIPMENT (PER UNIT)	COMPOSITE RATE/UNIT	TOTAL COST
							Manhour / Unit	\$/HOUR	COST				
100000					DIVISION 10 - SPECIALTIES								
558	A2.1 to			Shower Glass Wall	2625	SF							
559	A7.3			Toilet Compartment Wall	190	SF							
102813					TOILET AND BATH ACCESSORIES								
560	A2.1 to A7.3			Door Mounted Shower Door Roller	45	EA							
561				Grab Bar (18")	96	EA							
562				Grab Bar (24")	18	EA							
563				Grab Bar (36")	98	EA							
564				Grab Bar (42")	98	EA							
565				Grab Bar (48")	2	EA							
566				Sanitary Wipe Dispenser	1	EA							
567				Soap Dispenser by Laundry Supplier	1	EA							
568				Robe Hook	95	EA							
569				Robe Hook Door	98	EA							
570				Robe Hook Wall	95	EA							
571				Toilet Paper Holder	95	EA							
572				Towel Bar	95	EA							
573				Toilet Paper Holder	3	EA							
574				Eye Wash	1	EA							
575				Diaper Changing Station	2	EA							
576				Diaper Changing Station	1	EA							
577				Dirty Towel Bin	1	EA							
578				(4'-6"W x 3'-0"H) Vanity Mirror w/ Backlighting	95	EA							
579				(2'-0" x 5'-0") Mirror	95	EA							
580				(3' x 3') Mirror	2	EA							
581				(2' x 3') Mirror	1	EA							
582				Shower Curtain and Rod	245	LF							
Subtotal													
110000					DIVISION 11 - EQUIPMENT								
583	A2.1 to A7.3			Elevator (4 Stops, 498"H)	1	EA							
584				Dresser w/ Microwave and Refrigerator	61	EA							
585				Dresser without Microwave and Refrigerator	21	EA							
586				Dry Bar - Coffee Maker, Microwave and Refrigerator	90	EA							
587				Flat Screen TV W/ Mounts	114	EA							
588				Floor Lamp	76	EA							
589				Hair Dryer	90	EA							
590				Iron	95	EA							
591				Clock Radio	67	EA							
592				Desk Lamp	95	EA							
593				Dresser Lamp	143	EA							
594				Bedside Telephone	95	EA							
595				PTAC & Deflector	95	EA							
596				Coin Operated Washer Machine - WHIRLPOOL	2	EA							
597				Commercial Grade Freezer - Owner Supplied	1	EA							
598				Commercial Grade Refrigerator - Owner Supplied	1	EA							
599				Dryer	2	EA							
600				Electric Fire Place	1	EA							
601				Electric Water Cooler	1	EA							
602				Ellipticals	2	EA							
603				Exercise Treadmills	2	EA							
604				Hand Dryer	3	EA							
605				Pool Equipment	1	EA							
606			Refrigerator	1	EA								
607			TACC-II UNIT - OWNER FURNISHED	2	EA								
608			Top Load Washer	1	EA								
609			Washer	2	EA								
610			Water Fountain	1	EA								
611			Weight Machine	1	EA								
612			Ice Machine	1	EA								
613			Microwave	1	EA								
Subtotal													
120000					DIVISION 12 - FURNISHING								
614	A2.1 to A7.3			(5'-0"L x 1'-10"W) Desk	95	EA							
615				King Bed	138	EA							
616				Queen Bed	4	EA							
617				TV Table	19	EA							
618				Coffee Table	19	EA							
619				(5'-0" x 1'-6") Table	1	EA							
620				(5'-0" x 2'-6") Table	1	EA							
621				Lounge Chair	93	EA							
622				Luggage Rack	95	EA							
623				Ergonomic Chair	95	EA							
624				Ironing Board and Hook	95	EA							
625				Night Stand	115	EA							
626				Skirt Hanger Mini Hook	95	EA							
627				Suit Hanger Mini Hook	95	EA							
628				Weight Bench	1	EA							
629				Yoga Mats	2	EA							
630				Work Room Chairs	3	EA							
631				Chair	3	EA							
632				Cash Drawer - Owner Furnished	2	EA							
633				Bar Stool	8	EA							
634				Employee Locker	8	EA							
635				Free Weights	1	EA							
636				Towel Shelf Unit	1	EA							
637				Trash Can	2	EA							
638				Sectional Sofa	19	EA							
POOL													
639			Shade Sail (w/ 4 Poles)	175	SF								
640			ADA Pool Chair Lift	2	EA								
641			(1'-6" x 1'-6") Side Table	11	EA								
642			(3'-6"DIA.) Round Table	4	EA								
643			Chairs	16	EA								
644			Chaise Lounge	7	EA								
645			Lounge Chairs	10	EA								

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (PER UNIT)	EQUIPMENT (PER UNIT)	COMPOSITE RATE/UNIT	TOTAL COST
							Manhour / Unit	\$/HOUR	COST				
646				Panic Release Bar	2	EA							
647				Lock Box for Fire Department Card Key	1	EA							
123661				SOLID SURFACING COUNTERTOPS									
648	A2.1 to A7.3			Quartz Countertop (2CM)	15	SF							
649				Solid Surface Countertop	380	SF							
650				Worksurface countertop.	15	SF							
651				Vanity Countertop	30	SF							
652				Vanity Backsplash	15	LF							
				Subtotal									
150000				DIVISION 15 - HEATING, VENTILATING, AND AIR-CONDITIONING (HVAC)									
653				MS-4 & MSC-4 - MINI SPLIT HEAT PUMP - 1 TON MINI-SPLIT HEAT PUMP - CARRIER: 40MAQB12B-3 & 38MAQB12R-3	1	EA							
654				MS-2 & MSC-2 - MINI SPLIT HEAT PUMP - 3/4 TON MINI-SPLIT HEAT PUMP - CARRIER: 40MAQB09B-3 & 38MAQB09R-3	1	EA							
655				MS-3 & MSC-3 - MINI SPLIT HEAT PUMP - 1 TON MINI-SPLIT HEAT PUMP - CARRIER: 40MAQB12B-3 & 38MAQB12R-3	1	EA							
656				MS-1 & MSC-1 - MINI SPLIT HEAT PUMP - 3/4 TON MINI-SPLIT HEAT PUMP - CARRIER: 40MAQB09B-3 & 38MAQB09R-3	1	EA							
657				FAU-11 & CU-11 - CARRIER - MODEL: 24ABB560A050, COOLING COIL: CARRIER, MANUF: CNPVP6024ALA, AIR HNDLER - MANUF: CARRIER, MODEL: 59SC5A120S24-20 (5 TON SPLIT)	1	EA							
658				FAU-6 & CU-6 - CARRIER - MODEL: 24ABB324A030, COOLING COIL: CARRIER, MANUF: CNPVP2417ALA, AIR HNDLER - MANUF: CARRIER, MODEL: 59SC5A040S17-12 (2 TON SPLIT)	1	EA							
659				FAU-5 & CU-5 - CARRIER - MODEL: 24ABB324A030, COOLING COIL: CARRIER, MANUF: CNPVP2417ALA, AIR HNDLER - MANUF: CARRIER, MODEL: 59SC5A040S17-12 (2 TON SPLIT)	1	EA							
660				FAU-4 & CU-4 - CARRIER - MODEL: 24ABB324A030, COOLING COIL: CARRIER, MANUF: CNPVP2417ALA, AIR HNDLER - MANUF: CARRIER, MODEL: 59SC5A040S17-12 (2 TON SPLIT)	1	EA							
661				FAU-3 & CU-3 - CARRIER - MODEL: 24ABB324A030, COOLING COIL: CARRIER, MANUF: CNPVP2417ALA, AIR HNDLER - MANUF: CARRIER, MODEL: 59SC5A040S17-12 (2 TON SPLIT)	1	EA							
662				FAU-12 & CU-12 - CARRIER - MODEL: 24ABB560A050, COOLING COIL: CARRIER, MANUF: CNPVP6024ALA, AIR HNDLER - MANUF: CARRIER, MODEL: 59SC5A120S24-20 (5 TON SPLIT)	1	EA							
663				FAU-2 & CU-2 - CARRIER - MODEL: 24ABB318A030, COOLING COIL: CARRIER, MANUF: CNPVP1814ALA, AIR HNDLER - MANUF: CARRIER, MODEL: 59SC5A040S14-10 (1.5 TON SPLIT)	1	EA							
664				FAU-10 & CU-10 - CARRIER - MODEL: 24ABB548A050, COOLING COIL: CARRIER, MANUF: CNPVP4821ALA, AIR HNDLER - MANUF: CARRIER, MODEL: 59SC5A080S21-20 (4 TON SPLIT)	1	EA							
665				MS-5 & MSC-5 - MINI SPLIT HEAT PUMP - 1-1/2 TON MINI-SPLIT HEAT PUMP - CARRIER: 40MAQB18B-3 & 38MAQB18R-3	1	EA							
666				PTAC-1 - PACKAGED TERMINAL AIR CONDITIONER - AMANA: PTH073G25ERXX W/ SUB BASE KIT: PTB320E, DRAIN KIT: DK900D, OCCUPANCY SENSOR: DD01E, THERMOSTAT: DS01E, WALL SLEEVE: WS900GS	76	EA							
667				PTAC-2 - PACKAGED TERMINAL AIR CONDITIONER - AMANA: PTH093G25ERXX W/ SUB BASE KIT: PTB320E, DRAIN KIT: DK900D, OCCUPANCY SENSOR: DD01E, THERMOSTAT: DS01E, WALL SLEEVE: WS900GS	19	EA							
668				FAU-1 & CU-1 - CARRIER - MODEL: 24ABB318A030, COOLING COIL: CARRIER, MANUF: CNPVP1814ALA, AIR HNDLER - MANUF: CARRIER, MODEL: 59SC5A040S14-10 (1.5 TON SPLIT)	1	EA							
669				FIRE & SMOKE DAMPER	20	EA							
670				LINT LASSO LLA-10	2	EA							
671				EF-1 - EXHAUST FAN - PANASONIC: FV-05VQ5 (50 CFM)	102	EA							
672				EF-2 - EXHAUST FAN - PANASONIC: FV-11VQ5 (110 CFM)	3	EA							
673				EF-3 - EXHAUST FAN - PANASONIC: FV-15VQ5 (150 CFM)	1	EA							
674				EF-4 - EXHAUST FAN - PANASONIC: FV-30VQ3 (290 CFM)	2	EA							
675				(4"Dia) EXHAUST DUCT CAP	13	EA							
676				(2'X2') AIR DIFFUSER (75 CFM)	1	EA							
677				(2'X2') AIR INTAKE DEVISE (75 CFM)	1	EA							
678				(2'X2') AIR INTAKE DEVISE (375 CFM)	1	EA							
679				(2'X2') AIR INTAKE DEVISE (265 CFM)	3	EA							
680				(2'X2') AIR DIFFUSER (125 CFM)	8	EA							
681				(2'X2') AIR INTAKE DEVISE (400 CFM)	2	EA							
682				(1'X1') AIR DIFFUSER (50 CFM)	8	EA							
683				(2'X2') AIR INTAKE DEVISE (530 CFM)	3	EA							
684				(2'X2') AIR INTAKE DEVISE (420CFM)	1	EA							
685				(2'X2') AIR INTAKE DEVISE (535 CFM)	3	EA							
686				(2'X2') AIR INTAKE DEVISE (600 CFM)	1	EA							
687				(2'X2') AIR INTAKE DEVISE (500 CFM)	3	EA							
688				(1'X1') AIR DIFFUSER (75 CFM)	2	EA							
689				(2'X2') AIR INTAKE DEVISE	4	EA							
690				(2'X2') AIR INTAKE DEVISE (250 CFM)	10	EA							
691				(2'X2') AIR INTAKE DEVISE (125 CFM)	2	EA							
692				(2'X2') AIR DIFFUSER (130 CFM)	15	EA							
693				(2'X2') AIR DIFFUSER (150 CFM)	2	EA							
694				(1'X1') CEILING GRILLE	1	EA							
695				LINEAR SUPPLY DIFFUSER (140 CFM)	12	EA							
696				LINEAR SUPPLY DIFFUSER (160 CFM)	13	EA							
697				LINEAR SUPPLY DIFFUSER (135 CFM)	2	EA							
698				LINEAR SUPPLY DIFFUSER (125 CFM)	7	EA							
699				LINEAR SUPPLY DIFFUSER (75 CFM)	1	EA							
700				LINEAR SUPPLY DIFFUSER (100 CFM)	1	EA							
701				LINEAR SUPPLY DIFFUSER (110 CFM)	1	EA							

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (PER UNIT)	EQUIPMENT (PER UNIT)	COMPOSITE RATE/UNIT	TOTAL COST
							Manhour / Unit	\$/HOUR	COST				
702				LINEAR SUPPLY DIFFUSER (115 CFM)	7	EA							
703				LINEAR SUPPLY DIFFUSER (130 CFM)	5	EA							
704				LINEAR SUPPLY DIFFUSER (200 CFM)	3	EA							
705				SUPPLY GRILLE (200 CFM)	1	EA							
706				SUPPLY GRILLE (800 CFM)	1	EA							
707				SUPPLY GRILLE (155 CFM)	4	EA							
708				SUPPLY GRILLE (50 CFM)	1	EA							
709				VOLUME DAMPER	95	EA							
710				POWDER COATED LOUVER W/ BUG SCREEN	5	EA							
711				(6"Dia) EXHAUST DUCT CAP	2	EA							
712				(8"Dia) EXHAUST DUCT CAP	1	EA							
713				(4"Dia) ROUND DUCT (40"H)	1	EA							
714				(4"Dia) ROUND SUPPLY GRILLE (50 CFM)	8	EA							
715				FAU-7 & CU-7 - CARRIER - MODEL: 24ABB324A030, COOLING COIL: CARRIER, MANUF: CNPVP2417ALA, AIR HNDLER - MANUF: CARRIER, MODEL: 59SC5A040S17-12 (2 TON SPLIT)	1	EA							
716				FAU-8 & CU-8 - CARRIER - MODEL: 24ABB324A030, COOLING COIL: CARRIER, MANUF: CNPVP2417ALA, AIR HNDLER - MANUF: CARRIER, MODEL: 59SC5A040S17-12 (2 TON SPLIT)	1	EA							
717				FAU-9 & CU-9 - CARRIER - MODEL: 24ABB324A030, COOLING COIL: CARRIER, MANUF: CNPVP2417ALA, AIR HNDLER - MANUF: CARRIER, MODEL: 59SC5A040S17-12 (2 TON SPLIT)	1	EA							
718				LOCKABLE CABINET FOR FAN SOLID STATE SPEED CONTROLS	1	EA							
719				EF-5 - EXHAUST FAN - FANTECH: FR 125 (170 CFM)	9	EA							
720				EF-6 - EXHAUST FAN - FANTECH: FR 140 (225 CFM)	4	EA							
721				EV-1 - EXHAUST VENTILATOR - SOLER&PALAU: RCX11-06 W/ BACKDRAFT DAMPER	2	EA							
722				THERMOSTAT	97	EA							
723				ROUND DUCT TO RECTANGULAR TRANSITION	52	EA							
724				METAL DUCT TRANSITION	35	EA							
725				90 Deg ELBOW W/ TURNING VANES	19	EA							
726				TRAPEZE HANGER	124	EA							
727				(3") CLEAVIS HANGER	187	EA							
728				(3/4") THREADED ROD	622	EA							
729				FIG.165H-HEX NUTS	1244	EA							
730				FIG.103-WASHER--FLAT--ROUND	1244	EA							
				Galvanized sheet metal duct w/ Wrap equal to ownes coming fiberglass w/ FRK vapor barrier. Insulation shall be R-6 ecept on roof shall be R-8.									
731				(10"x10") METAL DUCT	352	SF							
732				(10"x8") METAL DUCT	675	SF							
733				(12"x10") METAL DUCT	20	SF							
734				(12"x12") METAL DUCT	35	SF							
735				(14"x10") METAL DUCT	865	SF							
736				(14"x12") METAL DUCT	25	SF							
737				(14"x14") METAL DUCT	96	SF							
738				(14"x8") METAL DUCT	15	SF							
739				(15"x10") METAL DUCT	30	SF							
740				(16"x10") METAL DUCT	65	SF							
741				(16"x12") METAL DUCT	495	SF							
742				(18"x10") METAL DUCT	325	SF							
743				(18"x16") METAL DUCT	55	SF							
744				(18"x18") METAL DUCT	30	SF							
745				(20"x12") METAL DUCT	185	SF							
746				(22"x16") METAL DUCT	35	SF							
747				(24"x10") METAL DUCT	315	SF							
748				(24"x12") METAL DUCT	95	SF							
749				(4"x10") METAL DUCT	25	SF							
750				(4"x8") METAL DUCT	45	SF							
751				(6"x10") METAL DUCT	275	SF							
752				(6"x12") METAL DUCT	25	SF							
753				(6"x8") METAL DUCT	695	SF							
754				(8"x12") METAL DUCT	310	SF							
755				(8"x8") METAL DUCT	365	SF							
				ROUND DUCT									
756				(8"Dia) ROUND DUCT	460	SF							
757				(4"Dia) ROUND DUCT	735	SF							
758				(6"Dia) ROUND DUCT	235	SF							
				FLEXIBLE ROUND DUCT									
759				(4"Dia) FLEXIBLE ROUND DUCT	35	LF							
760				(6"Dia) FLEXIBLE ROUND DUCT	170	LF							
761				(8"Dia) FLEXIBLE ROUND DUCT	340	LF							
762				(10"Dia) FLEXIBLE ROUND DUCT	50	LF							
763				(12"Dia) FLEXIBLE ROUND DUCT	20	LF							
764				(14"Dia) FLEXIBLE ROUND DUCT	70	LF							
				Subtotal									
			150000	DIVISION 15 - PLUMBING									
765				BT-1 - BRASS TONGUE DOWNSPOUT - ZURN: ZARB-Z199-3IP- PVC	19	EA							
766				DD-1 - DIRECT DRAW, SELF CONTAINED BAP (PERLICK: DDS60	1	EA							
767				FD-1 - FLOOR DRAIN - J.R SMITH 2005-A	10	EA							
768				FS-1 - SLOOR SINK - PROFLO PF906M	9	EA							
769				S-7 - 3-COMPARTMENT SINK - PERLICK: TS12BLW	1	EA							
770				S-6 - UNDERBAR SINK W/ 12" BENDER STATION (BAR) - PERLICK: TS12BLW	1	EA							
771				IC-1 - ICE CHEST (BAR) - PERLICK: TSD24IC	1	EA							
772				SG-1 - SODA GUN, POST MIX (BAR) - WUNDER-BAR: 12 BUTTON	1	EA							
773				BFR-1 - BIB FLAT RACK (BAR) - TAPRITE: 2-BFFJ (STACKED)	1	EA							
774				CO2-1 - 50LB CO2 TANK (BAR)	1	EA							
775				(6") CO - CLEANOUT	4	EA							
776				HB-1 - WALL HYDRANT - ZURN 1350-EZ	2	EA							
777				PRV - BACKFLOW PREVENTER	1	EA							
778				L-1 - LAVATORY - AMERICAN STANDARD 0614.000	98	EA							

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (PER UNIT)	EQUIPMENT (PER UNIT)	COMPOSITE RATE/UNIT	TOTAL COST
							Manhour / Unit	\$/HOUR	COST				
779				WC-2 - WATER CLOSET - TOTO CT708E	4	EA							
780				S-8 - BREAKDOWN SINK	1	EA							
781				DT-1 - DRAIN THROUGH - H-M COMPANY	1	EA							
782				ES-1 - EQUIPMENT STUB	3	EA							
783				EW-1 - EYE WASH STATION	1	EA							
784				S-1 - HAND SINK - ADVANCE/TABCO: 7-PS-80	1	EA							
785				S-2 - 3-COMP SINK - JUST MANUFACTURING: T-ADA-1949-A-GR	1	EA							
786				S-3 - MOP SINK - STERN-WILLIAMS: SB-902 & T-35 - W/ CHICAGO FAUCET: 897-CP	1	EA							
787				DF-1 - DRINKING FOUNTAIN - HAWS 1119.14	1	EA							
788				TS-1 - TUB/SHOWER COMBINATION - AMERICAN STANDARD 2391.202/TC & 2090.202/TC	45	EA							
789				WC-1 - WATER CLOSET - TOTO CST744SL#01-DRAKE TOILET	95	EA							
790				SH-1 - SHOWER PAN W/ HEAD	45	EA							
791				SH-2 - ROLL-IN SHOWER PAN W/ HEAD(ACCESS)	1	EA							
792				IM-2 - ICEMAKER (BAR)- ICE-O-MATIC: 1CEU150A	1	EA							
793				IM-1 - ICEMAKE - MANITOWOC: 0450 OR 0600 W/ QPA-310	4	EA							
794				U-1 - URINAL - TOTO UT104E	1	EA							
795				S-4 - LAUNDRY SINK - GRAINGER #5NFL8	1	EA							
796				S-5 - UTILITY SINK - GRIFFIN SERIES	1	EA							
797				WH-1 - WATER HEATER - AO SMITH: BTH-199 MXI, CYCLONE MXI MODULATING (100 GAL)	4	EA							
798				WS-1 - WATER SOFTNER - RHEEM	1	EA							
799				WF-1 - WATER FILTER - HOSHIZAKI AMERICA 9320-21 H	1	EA							
800				FS-2 - FLOOR SINK - JOSAM 49502	6	EA							
801				RD-1 - ROOF DRAIN -	22	EA							
802				TS-2 - TUB/SHOWER COMBINATION (ACCESSIBLE) - AMERICAN STANDARD 2391.202/TC & 2090.202/TC	4	EA							
803				2PSIG GAS METER	1	EA							
804				(2-1/2") CIRCULATOR PUMP	1	EA							
805				(1-1/4") BACKFLOW PREVENTER	1	EA							
806				(4") PRV VALVE	1	EA							
807				(4") MAIN SHUT OFF VALVE	1	EA							
808				(1-1/2") SHUT OFF VALVE	1	EA							
809				(3") SHUT OFF VALVE	2	EA							
810				(24"x24"x36") SUMP BOX	1	EA							
811				(2") BACKWASH DRAIN W/ PEA TRAP	2	EA							
812				(4") COLD WATER MAIN SHUTOFF VALVE	1	EA							
813				(3") SHUTOFF VALVE	2	EA							
814				(3/4") HOSE BIBB	2	EA							
815				SIAMESE FIRE DEP CONNECTION	1	EA							
816				FIRE RISER	1	EA							
817				WCO - WALL CLEANOUT - MANUF: ZURN, MODEL: 1443	21	EA							
818				BALL VALVE	20	EA							
819				GATE VALVE	12	EA							
820				SHUT OFF VALVE	319	EA							
				DOMESTIC WATER PIPING COPPER TYPE "L"									
821				(1") COLD WATER PIPE	310	LF							
822				(1") HOT WATER PIPE	155	LF							
823				(1/2") COLD WATER PIPE	3310	LF							
824				(1/2") HOT WATER PIPE	2200	LF							
825				(1-1/2") COLD WATER PIPE	125	LF							
826				(1-1/2") HOT WATER PIPE	75	LF							
827				(1-1/4") COLD WATER PIPE	165	LF							
828				(1-1/4") HOT WATER PIPE	110	LF							
829				(2") COLD WATER PIPE	55	LF							
830				(2") HOT WATER PIPE	85	LF							
831				(2-1/2") COLD WATER PIPE	115	LF							
832				(2-1/2") HOT WATER PIPE	225	LF							
833				(3") COLD WATER PIPE	145	LF							
834				(3/4") COLD WATER PIPE	1910	LF							
835				(3/4") HOT WATER PIPE	1650	LF							
836				(4") COLD WATER PIPE	25	LF							
837				(8") FIRE WATER LINE	25	LF							
				FITTINGS									
838				3/4" 45 ELBOW CxC	19	EA							
839				1" 45 ELBOW CxC	4	EA							
840				1/2" 90 ELBOW CxC	110	EA							
841				3/4" 90 ELBOW CxC	72	EA							
842				1" 90 ELBOW CxC	10	EA							
843				1-1/4" 90 ELBOW CxC	5	EA							
844				1-1/2" 90 ELBOW CxC	6	EA							
845				2" 90 ELBOW CxC	12	EA							
846				2-1/2" 90 ELBOW CxC	7	EA							
847				3" 90 ELBOW CxC	2	EA							
848				3/4" UNION CxC	16	EA							
849				1-1/2" UNION CxC	8	EA							
850				1-1/2" x3/4" x1-1/2" REDUCED TEE - 3X	9	EA							
851				2-1/2" x2" x3/4" REDUCED TEE - 3X	2	EA							
852				2-1/2" x2" x1-1/2" REDUCED TEE - 3X	3	EA							
853				1/2" TEE	165	EA							
854				3/4" TEE	106	EA							
855				1" TEE	45	EA							
856				1-1/4" TEE	15	EA							
857				1-1/2" TEE	27	EA							
858				2" TEE	19	EA							
859				2-1/2" TEE	2	EA							
860				3/4" x1/2" CONCENTRIC REDUCER--CxC	320	EA							
861				1" x3/4" CONCENTRIC REDUCER--CxC	127	EA							
862				1-1/4" x3/4" CONCENTRIC REDUCER--CxC	5	EA							
863				1-1/4" x1" CONCENTRIC REDUCER--CxC	2	EA							
864				1-1/2" x1" CONCENTRIC REDUCER--CxC	8	EA							
865				1-1/2" x1-1/4" CONCENTRIC REDUCER--CxC	1	EA							
866				2" x3/4" CONCENTRIC REDUCER--CxC	16	EA							
867				2" x1-1/2" CONCENTRIC REDUCER--CxC	5	EA							
868				1/2" CAPS	147	EA							
869				3/4" CAPS	35	EA							
870				1" CAPS	5	EA							
871				1-1/2" P-TRAP-SUC.LINE	204	EA							
872				1/2" COUPLING	406	EA							
873				3/4" COUPLING	194	EA							
874				1" COUPLING	46	EA							

#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (PER UNIT)	EQUIPMENT (PER UNIT)	COMPOSITE RATE/UNIT	TOTAL COST
							Manhour / Unit	\$/HOUR	COST				
948				D-6 - PENDANT LIGHT (LARGE) CONFERENCE	6	EA							
949				L-25 - RECESSED EXTERIOR FIXTURE - GOTHAM: EVO 27/29 BAR WD 120	10	EA							
950				L-3 - RECESSED 6" LED WALL WASH - DMF LIGHTING:DLE16/ DME8835 QC / EL60WW	19	EA							
951				(4") DOWNLIGHT	38	EA							
952				RECESSED 6" LED WALL WASH - DMF LIGHTING: DLE16/DME8835 QC / EL60WW	211	EA							
953				L-10 - LINEAR COVE LIGHT FIXTURE, LED	384	LF							
				RECEPTACLES & SWITCHES									
954				DUPLEX RECEPTACLE	903	EA							
955				FLOOR DUPLEX RECEPTACLE	18	EA							
956				GFI DUPLEX RECEPTACLE	215	EA							
957				GFI DUPLEX RECEPTACLE WEATHERPROOF	38	EA							
958				GFI QUAD RECEPTACLE	1	EA							
959				JUNCTION BOX	143	EA							
960				QUAD FLOOR RECEPTACLE	8	EA							
961				QUAD RECEPTACLE	6	EA							
962				SPECIAL PURPOSE RECEPTACLE	97	EA							
963				TELE/DATA FLOOR RECEPTACLE	18	EA							
964				TELE/DATA OUTLET	103	EA							
965				TELEPHONE OUTLET	101	EA							
966				TV OUTLET	126	EA							
967				208V RECEPTACLE FOR PTAC	97	EA							
968				DATA DUPLEX HOUSING	119	EA							
969				DUPLEX RECEPTACLE W/ USB	286	EA							
				DISCONNECT SWITCH									
970				DISCONNECT SWITCH	18	EA							
				LIGHTING CONTROLS									
971				TOGGLE MOTOR STARTER SWITCH W/ OVERLOAD PROTECTION	25	EA							
972				GG - OCCUPANCY SENSOR	23	EA							
973				SINGLE POLE SWITCH	100	EA							
974				MOTOR RATED SWITCH	97	EA							
975				SINGLE POLE SWITCH W/ OCCUPANCT SENSOR	56	EA							
976				THREE POLE SWITCH W/ OCCUPANCT SEBSOR	185	EA							
				LOW VOLTAGE & OTHER ELECTRICAL DEVICES									
977				EVCS - ELECTRIC DUAL VEHCLE CHARGING STATION	4	EA							
978				EV PANEL	1	EA							
979				TESA CARD READER	2	EA							
980				CARD READER	4	EA							
981				HOUSE PHONE PANEL OUTLET	5	EA							
982				DOOR RELEASE	2	EA							
983				INTERCOM	1	EA							
984				WIFI POINT	16	EA							
985				COM. & TV EQUIPED BOARDS (2)-8'HX4'WX3/4"PLYWOOD W/ #6 GRND	3	EA							
986				HH - SPEAKER SYSTEM	20	EA							
987				WIRELESS ACCESS POINT	1	EA							
988				CCTV CAMERA	27	EA							
				FIRE ALARM									
989				MINI HORN W/ STROBE, COMBINATION AUDIO & VISUAL ALARM	26	EA							
990				SMOKE DETECTOR	4	EA							
991				CARBONMONOXIDE DETECTOR	2	EA							
992				SMOKE DETECTOR/STROBE & FIRE SPRINKLER	194	EA							
				GEARS									
993				ELECTRICAL PANEL, 225A, 3PH, 4W, 120/208	8	EA							
994				ELECTRICAL PANEL, 400A, 3PH, 4W, 120/208	5	EA							
995				ELECTRICAL PANEL, 100A, 3PH, 4W, 120/208	8	EA							
996				ELECTRICAL PANEL, 200A, 3PH, 4W, 120/208	1	EA							
997				MAIN DISTRIBUTION PANEL	1	EA							
998				LOAD CENTER, 125A	95	EA							
999				ELECTRICAL POLE 3P, 20A	95	EA							
1000				ELECTRICAL POLE 2P, 20A	104	EA							
1001				ELECTRICAL POLE 1P, 20A	198	EA							
1002				ELECTRICAL POLE 2P, 30A	4	EA							
1003				ELECTRICAL POLE 3P, 15A	4	EA							
1004				ELECTRICAL POLE 2P, 15A	6	EA							
1005				ELECTRICAL POLE 2P, 40A	8	EA							
1006				ELECTRICAL POLE 1P, 15A	9	EA							
1007				ELECTRICAL POLE 1P, 20A	2	EA							
1008				ELECTRICAL POLE 3P, 25A	8	EA							
1009				ELECTRICAL POLE 3P, 30A	4	EA							
				OTHERS									
1010				GROUNDING	1	LS							
1011				CAT 5E	1	LS							
1012				WIRING & CONDUIT	1	LS							
				Subtotal									
270000				COMMUNICATIONS									
1013	A2.8			PROVIDE WIFI IN POOL AREA	1	LS							
1014				CABLE TV	245	LF							
1015				CABLE TV SERVICE	1	EA							
1016				TELEPHONE SERVICE CONNECTION	1	EA							
1017				TELE/DATA CONDUIT	250	LF							
				Subtotal									
310000				DIVISION 31 - EARTHWORK									
				TOPSOIL:									
1018				6" TOPSOIL STRIPPING	1813	CY							
1019				6" TOPSOIL RE-SPREADING	460	CY							
1020				EXPORT SURPLUS TOPSOIL	1353	CY							
				GRADING:									
1021				CUT	471	CY							
1022				FILL	6579	CY							
1023				IMPORT FILL MATERIAL	6108	CY							
				Subtotal									
320000				DIVISION 32 - EXTERIOR IMPROVEMENT									
	C2.1			ASPHALT PAVEMENT PARKING									
1024				2½" ASPHALT CONCRETE	15490	SF							
1025				6" TYPE II ROADBASE	15490	SF							
	C2.1			ASPHALT PAVEMENT DRIVEWAY									

EXCAVATION & BEDDING

DESCRIPTION	Length	Unit	Dia of pipe	Trench width	EXC DEPTH	EXCAVATION QTY	BEDDING DEPTH	BEDDING QTY	Pipe volume	NET BEDDING	BACK FILLING
WATER UTILITIES											
4",C900 PVC WATER LINE	196	LF	0.42	2.42	4.75	2254.44	1.25	594.32	27.14	567.18	1660.12
6",C900 PVC WATER LINE	384	LF	0.58	2.58	4.92	4876.04	1.42	1404.49	102.46	1302.03	3471.55
8",C900 PVC WATER LINE	178	LF	0.75	2.75	5.08	2488.13	1.58	774.88	78.60	696.28	1713.25
4", COPPER TYPE L WATER LINE	24	LF	0.42	2.42	4.75	276.05	1.25	72.77	3.32	69.45	203.28
8", COPPER TYPE L WATER LINE	40	LF	0.75	2.75	5.08	559.13	1.58	174.13	17.66	156.47	385.00
Total (CY)						387.18		111.87	8.49	103.39	275.30
SAN SEWRAGE											
6" PVC SAN-SEW PIPE	178	LF	0.58	2.58	4.92	2260.25	1.42	651.04	47.49	603.55	1609.21
Total (CY)						83.71		24.11	1.76	22.35	59.60
DRAINAGE											
15" DIA. CLASS 2 CONCRETE PIPE	402	LF	1.63	3.63	5.96	8682.30	2.46	3581.92	833.30	2748.62	5100.38
18" SD POLY PIPE	25	LF	1.67	3.67	6.00	550.78	2.50	229.65	54.73	174.92	321.13
Total (CY)						341.97		141.17	32.89	108.28	200.80



99 ESTIMATORS