



Address: 5550 Glades Road Suite 500-1047 Boca Raton FL 33431

Call us: (689) 215-6253

E-mail: info@99estimators.com

Website: www.99estimators.com

EXCHANGE II

2925 BUFORD DRIVE, BUFORD, GA 30519

OWNER

ARCHITECT

ADDENDA

Addendum Issued: NONE

Please review any Addendum issued after Date
03/13/2025

ID: -1067

BIDDER NAME: _____

99 ESTIMATORS

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHrs/ Unit	\$/Hour	(\$Per Unit)				
			010000	DIVISION 01 - GENERAL REQUIREMENTS									
1				MOBILIZATION	1	LS							
2				BOND & INSURANCE	1	LS							
3				SUPERVISION	1	LS							
4				SUBMITTALS & SAMPLES	1	LS							
5				TEMPORARY FACILITIES & CONTROLS	1	LS							
6				PROJECT SCHEDULE	1	LS							
7				CLOSEOUT PROCEDURES	1	LS							
8				PERMITS	1	LS							
				Subtotal									
			024000	DEMOLITION									
9				REMOVE EXISTING STORM STRUCTURE	4	EA							
10				REMOVE STORM PIPE	102	LF							
11				REMOVE CURB & GUTTER	485	LF							
12				PROTECT EXISTING UTILITIES	28	EA							
13				REMOVE EXISTING WATER CAP AND CONNECT PROPOSED WATER LINE	4	EA							
14				PROTECT EXISTING WALL & FENCE	487	LF							
15				REMOVE EXISTING SANITARY SEWER MANHOLE	1	EA							
16				REMOVE EXISTING SAN SEWER PIPE	7	LF							
17				REMOVE CLEANOUT & CONVERT INTO SANITARY SEWER MANHOLE	2	EA							
18				REMOVE EXISTING FENCE	30	LF							
19				CONVERT EXISTING STORM STRUCTURES INTO JUNCTION BOX	3	EA							
20				SAW/CUT ASPHALT	490	LF							
21				REMOVE ASPHALT PAVEMENT	126	SF							
				Subtotal									
			310000	EARTHWORK									
22				6" TOP SOIL STRIPPING	4424	CY							
23				6" TOP SOIL RE-SPREADING	1811	CY							
24				EXPORT SURPLUS TOP SOIL	2613	CY							
25				ROUGH GRDING PAVEMENT AREA									
26				CUT	56068	CY							
27				FILL	19401	CY							
				EXPORT SURPLUS CUT MATERIAL	36667	CY							
				Subtotal									
			312500	ERROSION CONTROL									
28				SD2-P: INLET SEDIMENTATION TRAP-CURB INLET PROTECTION	23	EA							
29				CO: CONSTRUCTION EXIT, FUEL STORAGE, TIRE WASHDOWN AREA & RIPRAP	5697	SF							
30				SD1-S: SILT FENCE-TYPE S	7673	LF							
31				DU: DUST CONTROL	360994	SF							
32				DS2: DISTURBED AREA STABILIZATION WITH TEMPORARY SEEDING	360994	SF							
33				DS1: DISTURBED AREA STABILIZATION WITH MULCHING ONLY	360994	SF							
34				DI: DIVERSION BERM	17269	SF							
35				FI-CO: FLOCCULANT COAGULANTS	24	EA							
36				SD4-C#1: TEMPORARY SEDIMENTATION BASIN (VREQ=71CY, VPROV=73CY)	1	EA							
37				SD4-C#2: TEMPORARY SEDIMENTATION BASIN (VREQ=172CY, VPROV=183 CY)	1	EA							
38				SD4-C#3: TEMPORARY SEDIMENTATION BASIN (VREQ=127CY, VPROV=134 CY)	1	EA							
39				SP: SAMPLING POINT	5	EA							
40				SD2-SS: INLET SEDIMENTATION TRAP-SILT SAVER	39	EA							
41				SD2-EX: INLET SEDIMENTATION TRAP-EXCAVATED INLET	10327	SF							
42				CD-HB: HAYBALE CHECK DAM	175	LF							
43				SD4-C#4: TEMPORARY SEDIMENTATION BASIN (VREQ=87CY, VPROV=94 CY)	1	EA							
44				SS: SOIL STABILIZATION	37428	SF							
				Subtotal									
			320000	SITE IMPROVEMENT, SIDEWALK & PAVEMENTS									
45				24" CONC CURB & GUTTER	1433	LF							
46				STANDARD DUTY CONCRETE SIDEWALK:									
47				4" CONC. REINF. W/ 6X6 W2.9XW2.9 W.W.F	15679	SF							
48				2"-3" COMACTED GAVEL OR CRUSHED STONE	15679	SF							
49				HEAVY DUTY ASPHALT PAVEMENT:									
50				1.25" SURFACE-9.5MM SUPERPAVE-GP 2 ONLY	8747	SF							
51				1.75" BIDER-19MM SUPERPAVE- GP 1 OR 2	8747	SF							
52				8" GAB 98% MODIFIED PROCTOR	8747	SF							
53				12" COMPACTED SUBGRADE 98% STANDARD PROCTER DENSITY OF UPPER 12"	8747	SF							
54				5" CONCRETE SLAB REINF. W/#3@12" O.C. @ PARKING	98730	SF							
55				SLAB ON GRADE @ BUILDING PAD:									
56				4" POST TENTIONED SLAB	102704	SF							
57				VAPOR BARRIER	102704	SF							
58				2" SAND CUSHION	102704	SF							
59				HEAVY DUTY CONCRETE PAVEMENT:									
60				6" CONC. 4000PSI, REINF. W/6"X6" WWF	1333	SF							
61				6" GAB 98% MODIFIED PROCTOR	1333	SF							
62				24" COMPACTED SUBGRADE 98% STANDARD PROCTER DENSITY OF UPPER 24"	1333	SF							
63				STANDARD DUTY ASPHALT PAVEMENT:									
64				1.25" SURFACE-9.5MM SUPERPAVE-GP 2 ONLY	6107	SF							
65				4" BIDER-19MM SUPERPAVE- GP 2 ONLY	6107	SF							
66				10" GAB 98% MODIFIED PROCTOR	6107	SF							
67				24" COMPACTED SUBGRADE 98% STANDARD PROCTER DENSITY OF UPPER 24"	6107	SF							
68				5" CONCRETE SLAB REINF. W/#3@12" O.C. @ PARKING	6107	SF							
69				TILE FLOORING:									
70				AUTEUR DIAGONALS ASH 9"X9"X0.43" PORCELAIN TILE	1614	SF							
71				1/4" EPOXY SETTING BE	1614	SF							
72				4" PIP REINFORCED CONCRETE SLAB	1614	SF							
73				4" AGGREGATE BASE	1614	SF							
74				CONCRETE 'B' SALT ROCK FINISH:									
75				4" CONC. REINF. W/ 6X6 W2.9XW2.9 W.W.F	4515	SF							
				2"-3" COMACTED GAVEL OR CRUSHED STONE	4515	SF							
				CONCRETE PAVER ON FLEXIBLE BASE:									
				CONCRETE PAVERS	1549	SF							
				GEOTEXTILE FABRIC	1549	SF							
				4" MIN. COMPACTED GRANITE FINES (CRUSHED RUN)	1549	SF							
				SYNTHETIC TURF:									
				SYNTHETIC TURF	1956	SF							
				1"-2" DEEP LEVELING/FINISHING COURSE STONE DUST OR FINE MATERIAL	1956	SF							
				2"-4" DEEP SAND GRAVEL BASE COURSE CRUSHER RUN	1956	SF							

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHrs/ Unit	\$/Hour	(\$Per Unit)				
76				4" COMPACTED SUB-GRADE 98% STD PROCTOR	1956	SF							
77		17/L5.30		3" MEXICAN BEACH PEBBLES OVER FILTER FABRIC	3134	SF							
78		6/L5.3		CONCRETE 'A' STANDARD BROOM FINISH:									
79				4" CONC. REINF. W/ 6X6 W2.9XW2.9 W.W.F	8356	SF							
80				2"-3" COMACTED GAVEL OR CRUSHED STONE	8356	SF							
81				RETAINING WALL	592	LF							
82				NOTE: DETAIL/SECTION NOT GIVEN									
83				DETECTABLE WARNING SURFACE	228	SF							
84				22"x8" COMPACTOR	1	EA							
85				42" FALL PROTECTION HANDRAIL	592	LF							
86				CONCRETE WHEEL STOPS	298	EA							
87				8" CMU WALL @ COMPACTOR	498	SF							
88				PAINTED CEMENTIOUS COATING ON 8" CMU W/ JOINTS	498	SF							
				STRUCK FLUSH @ COMPACTOR									
				PIPE BOLLARDS @ COMPACTOR	3	EA							
				12'-0"x9'-3" WOOD SLATE GATE @ COMPACTOR AREA	1	EA							
				Subtotal									
			331000	WATER DISTRIBUTION									
89				1" TYPE K COPPER DOMESTIC WATER LINE	192	LF							
90				1.5" PVC IRRIGATION LINE	11	LF							
91				2" TYPE K COPPER DOMESTIC WATER LINE	665	LF							
92				6" DIP DOMESTIC WATER LINE	64	LF							
93				8" DIP FIRE WATER LINE	222	LF							
94				CONNECT TO EXISTING WATER SYSTEM	2	EA							
95				1.5" IRRIGATION METER IN UNDERGROUND VAULT	1	EA							
96				4" DCDA BACKFLOW PREVENTER IN UNDERGROUND	1	EA							
97				TRAFFIC RATED VAULT									
98				4" DOMESTIC WATER METER IN UNDERGROUND VAULT	1	EA							
99				4" DOMESTIC WATER METER IN UNDERGROUND VAULT	1	EA							
100				HOSE BIB FOR DUMPSTER	1	EA							
101				8"x90 DEG BEND WITH THRUST BLOCKING	12	EA							
102				DOMESTIC WATER CONNECTION TO BUILDING	3	EA							
103				2"x2"x1" TEE WITH THRUST BLOCKING	1	EA							
104				2"x45 DEG BEND WITH THRUST BLOCKING	4	EA							
105				8"x8"x8" TEE WITH THRUST BLOCKING	2	EA							
106				CONNECT TO EXISTING WATER SYSTEM WITH TEE	2	EA							
107				8" DCDA FIRE BACKFLOW PREVENTER IN UNDERGROUND	2	EA							
108				VAULT									
109				FIRE WATER CONNECTION TO BUILDING	2	EA							
110				6"x2"x6" TEE WITH THRUST BLOCKING	1	EA							
111				FDC WALL MOUNTED	2	EA							
112				EXCAVATION	0	CY							
113				STONE BEDDING	0	CY							
				TRENCH SPOIL EXPORT	0	CY							
				BACKFILLING	0	CY							
				Subtotal									
			333000	SANITARY SEWER									
114				8" PVC SANITARY SEWER LINE	500	LF							
115				SANITARY SEWER CONNECTION FROM BUILDING	4	EA							
116				SANITARY SEWER MANHOLE	6	EA							
117				CONNECT TO EXISTING SEWER SYSTEM	3	EA							
118				SANITARY SEWER CLEANOUT	4	EA							
119				EXCAVATION	0	CY							
120				STONE BEDDING	0	CY							
121				SELECT OR GRANULAR FILL	0	CY							
122				TRENCH SPOIL EXPORT	0	CY							
123				BACKFILLING	0	CY							
				Subtotal									
			334000	STORM DRAINAGE SYSTEMS									
124				18" RCP SD	1449	LF							
125				24" RCP SD	440	LF							
126				8" HDPE SD	23	LF							
127				12" HDPE SD	86	LF							
128				18" HDPE SD	524	LF							
129				24" HDPE SD	439	LF							
130				PVC ROOF DRAIN	415	LF							
131				PROPOSED GDOT 1019E HOODED GRATE CURB INLET	10	EA							
132				PROPOSED GWINNETT COUNTY STANDARD GRATE INLET	3	EA							
133				STANDARD JUNCTION BOX	8	EA							
134				CONNECT TO EXISTING PIPE WITH COLLAR	3	EA							
135				DOWNSPOUT CLEANOUT CONNECTION	30	EA							
136				CONNECT TO EXISTING STORM WATER SYSTEM	3	EA							
137				NYLOPLAST STRUCTURE WITH 12" STANDARD GRATE	20	EA							
138				CONVERT YARD INLET IN TO JUNCTION BOX	2	EA							
139				NYLOPLAST STRUCTURE WITH SOLID TOP	5	EA							
140				STANDARD SINGLE WING CATCH BASIN	1	EA							
141				INSERT A TEE DEVICE TO CONNECT DOWNSPOUT TO	21	EA							
142				STORM PIPE									
143				48" PADESTAL INLET	2	EA							
144				EXCAVATION	0	CY							
145				STONE BEDDING	0	CY							
146				TRENCH SPOIL EXPORT	0	CY							
				BACKFILLING	0	CY							
				Subtotal									
			337000	ELECTRICAL UTILITIES									
147				TRANSFORMER	5	EA							
148				4" ELECTRICAL CONDUIT	1128	LF							
				Subtotal									
			100610	SIGNAGE									
149				STOP SIGN (MUTCD R1-1)	2	EA							
150				NPDES INFORMATION SIGN (C5.80)	2	EA							
151				4'X3' TYRE WASH AREA SIGN	1	EA							
				Subtotal									
			321723	PAVEMENT MARKING									
152				8' WIDE PEDESESTRIAN CROSSWALK	9	EA							
153				4" YELLOW STRIPPING	1088	LF							
154				24" WHITE STOP BAR WITH "STOP"	8	EA							
155				SOLID 4" WHITE THERMOPLASTIC PARKING STRIPES	11103	LF							
				Subtotal									
			320000	LANDSCAPE									
156				12"W. POOL COPING WITH BULLNOSE EDGE,	268	SF							
157				MANUF:HARTSTONE									
158				4" MULCH @ LANDSCAPE AREA	97811	SF							
159				12"WX7'-6"H, REINF.D. CIP CHEEK WALL	390	CF							
160				12"WX7'-0"H, REINF.D. CIP CHEEK WALL	679	CF							
161				12"WX4'-6"H, REINF.D. CIP CHEEK WALL	63	CF							
162				12"WX4'-0"H, REINF.D. CIP CHEEK WALL	664	CF							
163				12"WX3'-6"H, REINF.D. CIP CHEEK WALL	39	CF							
164				12"WX2'-6"H, REINF.D. CIP CHEEK WALL	48	CF							
165				5'-0"x12"x6", REINF.D. CONC STEPS	193	CF							
166				5'-6"x12"x6", REINF.D. CONC STEPS	33	CF							
167				6'-0"x12"x6", REINF.D. CONC STEPS	42	CF							
168				7'-0"x12"x6", REINF.D. CONC STEPS	18	CF							
				10'-0"x12"x6", REINF.D. CONC STEPS	20	CF							

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHrs/ Unit	\$/Hour	(\$Per Unit)				
169				4" REINF. CONC WAIST SLAB	244	CF							
170				5'-0"X9'WX10'H, REINF.D CONC FOUNDATION	81	CF							
171				5'-6"X9'WX10'H, REINF.D CONC FOUNDATION	7	CF							
172				6'-0"X9'WX10'H, REINF.D CONC FOUNDATION	15	CF							
173				7'-0"X9'WX10'H, REINF.D CONC FOUNDATION	9	CF							
174				10'-0"X9'WX10'H, REINF.D CONC FOUNDATION	12	CF							
175				36"H RECTANGULAR TUBE STEEL HANDRAIL (POWDER COATED)	340	LF							
176		18/L5.30		PET WASTE RECEPTACLE	4	EA							
177		2/L5.80		15'-2"X8'-4", 4-PANEL VERADK PARILLA PRIVACY SCREEN	2023	SF							
178		4/L5.91		120"LX50"W, OUTDOOR CURTAIN @ CABANA, MODEL: PATIO34, MANUF: SUNBRELLA GROMMET TOP	209	EA							
179	L1.10	1/L5.80		VERTICAL WOOD SLAT WALL WITH APPARTMENT SIGNAGE IN PASS THRU CORTYARD	228	SF							
180	L1.10	9/L5.80		EXTENSION OF ARCH WALL	144	SF							
181	9/L5.80	16/L7.00		65" OUTDOOR WALL MOUNTED TV	1	EA							
182	L1.10	ID DWGS		6'X3' CUSTOM BOOTHS MILLWORK	3	EA							
183	L1.10	6/L5.91		1X6 CEDAR SLAT FAUX GREEN WALL "B"	240	SF							
184	L1.10	2/L5.93		FAUX GREEN WALL "A", NAME: UV-IFR PANEL, MANUF: VISTAFOLIA	324	SF							
185	L1.10	6/L5.91		1'-3"WX3'-0"H CIP CONCRETE PARTITION WALL	26	CF							
186	L1.10	1/L5.50		48"H GLASS FENCING AND GATE INTO THE POOL COURTYARD	32	LF							
187	L1.10	5/L5.80		8'X8'X16" CMU FULLY GROUTED BLOCK WALL (2'-4"H)	231	SF							
188	L1.10	5/L5.80		4'X8'X16" CMU FULLY GROUTED BLOCK WALL (8'H)	133	SF							
189				4" BRICK VENEER (1'-8"H)	331	SF							
190	L1.10	3/L0.11		20'WX2'H PRECAST CONCRETE CAP	99	LF							
191	L1.10	5/L5.80		REINF.D. CONCRETE FOUNDATION @ CMU WALL (2'-7"WX10"H)	213	CF							
192	L1.10	5/L5.80		4X4 LIGHT POST	11	EA							
193	L1.10	1/L5.92		POOL ARBOR	335	SF							
194	L1.10	1&2/L5.90		POOL CABANA	542	SF							
195	L1.10	1/L5.11		POOL GRILL STATION (9'-0"X2'-6"H)	1	EA							
196	L1.10	12/L5.21		TANNING LEDGE WITH BUBBLERS AND SEATING	1	EA							
197	L1.10	2/L5.12		KITCHEN STATION (11'-2"X2'-9"H)	1	EA							
198	L1.10	ARCH DWGS		2X2" ARCHITECTURAL COLUMNS	8	EA							
199	L1.10	1/L5.93		HORIZONTAL WOOD SLAT WALL WITH TV (7'-3"H)	13	LF							
200	L1.20			BRICK WALL WITH PRECAST CONCRETE CAP (DET. NOT GIVEN) (7'H ASSUMED)	118	LF							
201	L1.20	3/L5.50		5'H STEEL PICKET FENCE	88	LF							
202	L1.20	4/L5.50		3'X5' STEEL PICKET ACCESS CONTROLLED GATE	4	EA							
203	L1.10	ID DWGS		8'X10' RUGS	2	EA							
204	L1.10			ARCHITECTURAL BAR LEDGE WITH BAR STOOLS	1	EA							
205	L1.10	3/L5.80		31'-10"X8'-2", VERADEK PANEL SCREEN PASS THROUGH CEILING	1	EA							
206	L1.10-1.40			ORNAMENTAL UNDER STORY TREE	83	EA							
207	L1.10-1.40			OVERSTORY TREE	56	EA							
208	L1.20	3/L11.01		TURNESOL TWIG BENCH ON SYNTHETIC TURF FLEX LAWN W/ STRING LIGHT CANOPY ABOVE (93-3/4"X75-5/8"X17-1/2"H)	6	EA							
209	L1.20	6/L5.10		PGST-SERIES NATURAL GAS GRILL WITH TIMER MODEL: S27TNG, MANUF: BBQGUYS	1	EA							
210	L1.20			FLEXIBLE SEATING GROUPS ON SYNTHETIC TURF FLEX LAWN	1	EA							
211	L1.20			4X4 HSS POST FOR STRING LIGHTS	82	EA							
212	L1.20			STRING LIGHT	908	LF							
213	L1.20	3/L5.50		42" HIGH STEEL PICKET FENCE	438	LF							
214	L1.30	5/L5.10		NATURAL GAS GRILL STATION	1	EA							
215	L1.10	L0.11		CT 1510 UNGLAZED BLUE (SKID RESISTANT) TILE @ POOL STEP & POOL BENCH	495	SF							
216	L1.10	L0.11		REFLECTION SERIES MARINER BLUE @ POOL SHEEL FLOOR AREA	1295	SF							
217	L1.10	L0.11		REFLECTION SERIES MARINER BLUE @ POOL SHEEL WALL AREA	710	SF							
218	L1.10	L0.11		THAMES SERIES 2X2 CT TH 882 WATERLINE POOL TILE	110	SF							
219	L1.10	L5.21		POOL STEP & STEP AREA CONCRETE STRUCTURE (DESIGNED BY OTHERS)	495	SF							
220	L1.10	L5.21		POOL SHELL AREA CONCRETE STRUCTURE (DESIGNED BY OTHERS)	1295	SF							
221	L5.21	1/L5.21		ROLLED STAIR RAIL @ POOL STEPS (34"X84"L)	1	EA							
222	L5.21	2/L5.21		POOL STANDARD PLUS LADDER MODEL#: LF30-MG MANUF: SR SMITH	1	EA							
223	L5.20	13/L5.20		HANICAP POOL STAINLESS STEEL CHAIR LIFT, MOTION TREK 350 DLX, PRODUCT # 153121-DLX MANUF: SPECTRUM AQUATICS.	1	EA							
224	L5.20	11&12/L5.20		HANDICAP POOL CHAIR REINF. CONC. FOUNDATION PAD (4'-0"X2'-6"X1'-0") (1EA)	10	CF							
				DRAINAGE									
225	L3.10- L3.40			4" STRIP DRAIN (15/L4.00)	69	LF							
226				12" AREA DRAIN (8/L4.00)	62	EA							
227				DECK DRAIN (13/L4.00)	1	EA							
228				6" DRAIN PIPE	565	LF							
				MEP									
229		5/L7.10		LED STRING LIGHTS	1143	LF							
230		11/L7.00		BOLLARD - PATH LIGHT, MODEL: TAURAS 1 BOLLARD, MANUF: LIGMAN LIGHTING USA	87	EA							
231		6/L7.00		GRILL LIGHT MODEL: SF-36-B-MR-331-BZP-10-B MANUF: B-K-LIGHTING	6	EA							
232		3/L7.00		HOSE BIBB	20	EA							
233		17/L7.00		STREETSCAPE LIGHT	55	EA							
234		1/L7.01		DECORATIVE LED FIXTURE, MODEL: COPENHAGEN LED OUTDOOR CHANDELIER PRODUCT ID: KU2P205797, MANUF: LUMENS	3	EA							
235		3/L7.01		WALL JET, MODEL: NATURAL WONDERS, WALL JETS CMP PART #: 25598-200-000, MANUF: CMP	3	EA							
236		2/L7.01		LED BUBBLER, MODEL: BRILLIANT WONDERS, 4" LED BUBBLER CMP PART #: 25503-460-000, MANUF: CMP	3	EA							
237		3/L5.20		EMERGENCY PHONE	2	EA							
238		4/L7.00		PROXIMITY READER	9	EA							
239		10/L7.00		LANDSCAPE UPLIGHT MODEL: HSL16-S-BR-60-BLPXD, MANUF: AUORALIGHT	172	EA							
240	L6.00-6.40	13/L7.00		SPEAKER: 8" TWO-WAY CO-AXIAL MUSHROOM LANDSCAPE SPEAKER, MODEL: CONTROL 88M, MANUF: JBL PROFESSIONAL BY HARMAN	2	EA							
241		9/L7.00		SURFACE-MOUNTED FLOOD LIGHT	2	EA							
242		5/L7.00		PUSH TO EXIT	7	EA							
243		8/L5.20		POOL SHOWER	2	EA							
244		2/L5.70		EMERGENCY SHUTOFF	6	EA							
245		7/L7.00		SUBMERSIBLE POOL LIGHT MANUF: HUNZA	6	EA							
246		15/L7.00		75" TELEVISION, MODEL: SB-WM-F-L-BL, MANUF: SUNBRITE TV, LLC	4	EA							
247		1/L7.00		GFI - RECESSED IN WALL	6	EA							
248		2/L7.00		GFI - MOUNTED IN LANDSCAPE	17	EA							

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHrs/ Unit	\$/Hour	(\$Per Unit)				
249		4/L7.01		CAN LIGHT	9	EA							
250		18/L7.00		FLOOR LAMP, MODEL#9777, MANUF:GLOSTER	9	EA							
251		14/L7.00		POOL COURTYARD POLE LIGHT	6	EA							
252		7/L5.12		ICE MAKER	1	EA							
253		9/L5.12		FAUCET + SINK	1	EA							
254		12/L7.00		STEP LIGHT, MODEL:SL632, MANUF:LUMUX	53	EA							
255		6/L5.20		DRINKING FOUNTAIN	1	EA							
256		13/L5.20		ADA CHAIR	1	EA							
				TREES:									
257				AB4:ACER BUERGERIANUM 'ABMTF' PP16,629,B & B,14'-15' HT,4" CAL	29	EA							
258				AA4:AMELANCHIER ARBOREA 'AUTUMN BRILLIANCE',B & B,12'-15' HT,4" CAL,MULTI-TRUNK	42	EA							
259				CC4:CARPINUS CAROLINIANA,B & B,14'-16' HT,4" CAL	21	EA							
260				CJ3:CRYPTOMERIA JAPONICA,B & B,14'-15' HT	11	EA							
261				DI3:DEVELOPER INSTALLED,B & B,15'-16' HT,3" CAL	18	EA							
262				LS4:LIQUIDAMBAR STYRACIFLUA 'SLENDER SILHOUETTE',B & B,15'-16' HT,4" CAL	15	EA							
263				MV4:MAGNOLIA VIRGINIANA 'GREEN SHADOW' SINGLE STRAIGHT TRUNK, DENSE, UNIFORM BRANCHING, MATCHED, LIMB UP 84",B & B,14'-16' HT,4" CAL,SINGLE TRUNK	19	EA							
264				PP10:PARROTIA PERSICA (MULTI-STEM),B & B,9'-10' HT	5	EA							
265				PT:PINUS TAEDA,15 GAL	29	EA							
266				QP4:QUERCUS PHELLOS SINGLE STRAIGHT TRUNK, DENSE, UNIFORM BRANCHING, MATCHED, LIMB UP 84",B & B,15'-16' HT,4" CAL	9	EA							
267				QN4:QUERCUS SHUMARDII SINGLE STRAIGHT TRUNK, DENSE, UNIFORM BRANCHING, MATCHED, LIMB UP 84",B & B,15'-16' HT,4" CAL	6	EA							
268				UA4:ULMUS AMERICANA 'PRINCETON' SINGLE STRAIGHT TRUNK, DENSE, UNIFORM BRANCHING, MATCHED, LIMB UP 84",B & B,15'-16' HT,4" CAL	16	EA							
269				VAC10:VITEX AGNUS-CASTUS,B & B,10'-12' HT,,3 TRUNK MIN.	14	EA							
				SHRUBS:		EA							
270				AR3:ABELIA X 'ROSE CREEK',3 GAL	119	EA							
271				AJ7:AUCUBA JAPONICA 'GOLD DUST',7 GAL	31	EA							
272				AE:AZALEA ENCORE TM,3 GAL	61	EA							
273				AM:AZALEA INDICA 'MRS. G.G. GERBING',3 GAL	103	EA							
274				BUW7:BUXUS MICROPHYLLA JAPONICA 'WINTER GEM',7 GAL,18"W X 18"H	1	EA							
275				BGM30:BUXUS X 'GREEN MOUNTAIN',B & B,30"W X 30"H	22	EA							
276				CP:CEPHALOTAXUS HARRINGTONIA PROSTRATA,3 GAL	421	EA							
277	19.00-90.1			CHD7:CEPHALOTAXUS HARRINGTONIA VAR. DRUPACEA,7 GAL	9	EA							
278				CJA3:CLEYERA JAPONICA,3 GAL	93	EA							
279				CS:CORNUS SERICEA,7 GAL,3'-5' HT	9	EA							
280				HN:HYDRANGEA MACROPHYLLA 'NIKKO BLUE',3 GAL	35	EA							
281				HPL7:HYDRANGEA PANICULATA 'LIMELIGHT' TM,7 GAL	58	EA							
282				HQU7:HYDRANGEA QUERCIFOLIA,7 GAL	8	EA							
283				IC3:ILEX CORNUTA 'DWARF BURFORD',3 GAL	196	EA							
284				ID:ILEX CORNUTA 'DWARF BURFORD',3 GAL	299	EA							
285				IS:ILEX CRENATA 'SKY PENCIL',7 GAL,4' HT	21	EA							
286				IP3:ILLICIAM PARVIFLORUM,3 GAL	258	EA							
287				LJV3:LIGUSTRUM JAPONICUM 'VERIEGATUM',3 GAL	30	EA							
288				LP:LOROPETALUM CHINENSE RUBRUM 'PURPLE PIXIE',3 GAL	299	EA							
289				LCC3:LOROPETALUM CHINENSE 'CRIMSON FIRE',3 GAL,30" O.C.	502	EA							
290				MSA3:MISCANTHUS SINENSIS 'ADAGIO',3 GAL	81	EA							
291				MC:MUHLENBERGIA CAPILLARIS,3 GAL	372	EA							
292				PVN3:PANICUM VIRGATUM 'NORTH WIND',3 GAL	144	EA							
293				PB2:PENNSETUM ALOPECUROIDES 'LITTLE BUNNY',3 GAL	182	EA							
294				PA:PEROVSKIA ATRIPLICIFOLIA,3 GAL	17	EA							
295				PB:PRUNUS CAROLINIANA 'BRIGHT 'N TIGHT' TM,15 GAL	3	EA							
296				PO3:PRUNUS LAUROCEASUS 'OTTO LUYKEN',3 GAL	59	EA							
297				RO3:ROSMARINUS OFFICINALIS,3 GAL	43	EA							
298				RFC3:RUDBECKIA FULGIDA,3 GAL	6	EA							
				GROUND COVERS:									
299				AGO1:ACORUS GRAMINEUS 'OGON',1 GAL	971	EA							
300				ARI1:AJUGA REPTANS,1 GAL	395	EA							
301				EC:ERAGROSTIS CURVULA,SEED	27052	SF							
302				FE:FESTUCA GLAUCA 'ELIJAH BLUE',1 GAL,12" O.C.	2538	EA							
303				LB118:LIRIOPE MUSCARI 'BIG BLUE',1 GAL,18" O.C.	3015	EA							
304				LME1:LIRIOPE MUSCARI 'EVERGREEN GIANT',1 GAL,18" O.C.	2570	EA							
305				OJA4:OPHIPOGON JAPONICUS,4" POT,15" O.C.	116	EA							
306				PTE4:PACHYSANDRA TERMINALIS,4" POT,12" O.C.	344	EA							
307				RO1:ROSMARINUS OFFICINALIS 'PROSTRATUS',1 GAL,18" O.C.	430	EA							
308				SCO4:SEASONAL COLOR,4" POT,12" O.C.	38	EA							
309				TAA1:TRACHELOSPERMUM ASIATICUM 'ASIATIC',1 GAL,18" O.C.	1267	EA							
310				ZJM:ZOYSIA JAPONICA 'MEYER',SOD,	7480	SF							
				FURNISHING									
311		1/L11.00		CHAISE LOUNGER, MODEL#7950, MANUF:GLOSTER	27	EA							
312		6/L11.01		HANGING POD CHAIR , MODEL#404669, CB2	4	EA							
313		3/L11.01		TWIG BENCH, 93-3/4"x75-5/8"x17-1/2", MODEL:G-01, MANUF:TOURNESOL SITEWORKS	6	EA							
314		13/L11.00		LOVESEAT (PASS THRU), DUNE 2-SEATER SOFA, MODEL#91001, 71"x36.5"x28.5", MANUF:GLOSTER	1	EA							
315		2/L11.00		MINI CHAISE LOUNGER	6	EA							
316		5/L11.01		WINMARK CHAIR	50	EA							
317		4/L11.01		HARPO 69" TABLE, 32.5"x32.50X69", MANUF: LANDSCAPE FORMS	4	EA							
318		14 1/L11.01		WASTE RECEPTACLE, MODEL# SD-42, MANUF:VICTOR STANLEY	14	EA							
319		2/L11.01		PET WASTE RECEPTACLE, MODEL#1206A-L, MANUF: DOGIPO	8	EA							
320		12/L11.00		LOUNGE CHAIR (PASS THRU), MODEL#91000, MANUF:GLOSTER	7	EA							
321		4 14/L11.00		COUCH(PASS THRU) , MODEL#91002, MANUF:GLOSTER	4	EA							
322		17/L11.00		RECTANGULAR PLANTER POT (96X18), MODEL WCR-961824, MANUF:CRESCENT GARDEN	4	EA							
323	L10.00- L10.40	11/L11.00		ENTRY COFFEE TABLE , MODEL#9781, MANUF:GLOSTER	1	EA							
324		10/L11.00		LOUNGE CHAIR, MODEL#91122, MANUF:GLOSTER	20	EA							
325		18/L11.00		SQUARE PLANTER POT ,MODEL:2414Z47:UCRT-2400, MANUF:TOURNESOL SITEWORK	4	EA							
326		15/L11.00		TREE TRUNK COFFEE TABLE , MODEL#329771561IND, MANUF:SIERRA LIVING CONCEPTS	2	EA							

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHrs/ Unit	\$/Hour	(\$Per Unit)				
327		7/L11.00		SECTIONAL COUCH, GRID LEFT/RIGHT END UNIT/7100M, MANUF: GLOSTER	2	EA							
328		9/L11.00		SIDE TABLE, MODEL#7176, MANUF:GLOSTER	1	EA							
329		8/L11.00		SQUARE COFFEE TABLE, MODEL#7116, MANUF:GLOSTER	1	EA							
330		8/L5.70		FIRE EXTINGUISHER	7	EA							
331		17/L11.00		RECTANGULAR PLANTER POT (60X24), MODEL:WCR-6024X24, MANUF:TOURNESOL SITEWORK	4	EA							
332		5/L11.00		TABLE TOP, MODEL:CL-R80 31.5" ROUND, MANUF:LEBELLO	3	EA							
333		16/L11.00		POT 20X20, MANUF:TOURNESOL SITEWORK	1	EA							
334		16/L11.00		POT 26X26, MANUF:TOURNESOL SITEWORK	1	EA							
335		16/L11.00		POT 34X34, MANUF:TOURNESOL SITEWORK	2	EA							
336		17/L11.00		RECTANGULAR PLANTER POT (48X24), MODEL:WCR-482424 , MANUF:TOURNESOL SITEWORK	1	EA							
337		10/L5.12		PULL WASTE RECEPTACLE	1	EA							
338	L5.20			HANICAP POOL STAINLESS STEEL CHAIR LIFT	1	EA							
339	L5.21			ROLLED STAIR RAIL @ POOL STEPS (34"HX84"L)	1	EA							
340	L5.21			POOL STANDARD PLUS LADDER MODEL#:LF30-MG MANUF: SR SMITH	1	EA							
341	L5.80			65" OUTDOOR WALL MOUNTED TV	1	EA							
342				SLEEVEING	1	EA							
343	L12.00			4" CLASS 200 PVC IRRIGATION SLEEVE	904	LF							
344	L12.00			6" CLASS 200 PVC IRRIGATION SLEEVE	224	LF							
Subtotal													
BUILDING 1000 A													
020000				DIVISION 02 - EXISTING CONDITIONS									
022000				EARTHWORK									
345	S1-11A	S0-01, S3-01 & S3-02		Footing excavation.	10610	CF							
346				Footing backfill.	2200	CF							
Subtotal													
030000				DIVISION 03 - CONCRETE									
033000				CAST IN PLACE CONCRETE									
347	S1-11A	S0-01, S3-01 & S3-02		(2'Wx18"H) CONCRETE FOOTING	4135	SF							
348				Compaction of sub-grade.	8815	LB							
349				Rebar's (Grade 60)	5510	CF							
350	S1-11A	S0-01, S3-01 & S3-02		(2'Wx22"H) CONCRETE FOOTING	1450	SF							
351				Compaction of sub-grade.	4015	LB							
352				Rebar's (Grade 60)	2510	CF							
353	S1-11A	S0-01, S3-01 & S3-02		(1'Wx8"H) CONCRETE FOOTING	340	SF							
354				Compaction of sub-grade.	240	LB							
355				Rebar's (Grade 60)	150	CF							
356	S1-11A	S0-01, S3-01 & S3-02		(5'SQ. x2'H) CONCRETE FOOTING PAD (6 EA)	185	SF							
357				Compaction of sub-grade.	480	LB							
358				Rebar's (Grade 60)	300	CF							
359	S1-11A	S0-01, S3-01 & S3-02		SLAB ON GRADE	13275	SF							
360				Compaction of sub-grade.	13275	SF							
361				(10 MIL) Vapor barrier.	13275	SF							
362	S1-11A	S0-01, S3-01 & S3-02		(4" Thick) Reinforced concrete slab w/ post tensioning. (fc = 3000 PSI)	750	SF							
363				Compaction of sub-grade.	750	SF							
364				(10 MIL) Vapor barrier.	750	SF							
365	S1-12A to S1-14A			(4" Thick) Concrete slab w/ C/P 6x6 - 10/10 WWM. (fc = 3000 PSI)	750	SF							
366				Metal pan concrete stair.	220	SF							
Subtotal													
040000				DIVISION 04 - MASONRY									
042000				UNIT MASONRY									
366	A1-11A TO ID-7.3			Exterior Type BR-1, Brick Veneer-Gray.	1651	SF							
Subtotal													
050000				DIVISION 05 - METAL									
051200				STRUCTURAL STEEL									
367	S1-12A			W14x22	35	LF							
368				W16x31	18	LF							
369				W18x50	100	LF							
370				W18x55	25	LF							
371				W18x65	25	LF							
372				W18x76	65	LF							
373				W24x88	40	LF							
374	S1-12A		053000	METAL DECK	180	SF							
375			055000	METAL FABRICATIONS	1	LS							
376	A1-11A TO ID-7.3		057000	MISC. Item.	1046	LF							
377				ORNAMENTAL METAL	220	LF							
Subtotal													
060000				DIVISION 06 - WOOD, PLASTIC AND COMPOSITES									
061053				WOOD FRAMING									
378	S1-12A to S1-15A			(2x8) Header beam.	1005	LF							
379				(2x10) Header beam.	760	LF							
380				5.5x11.25 GL	305	LF							
381				5.5x14 GL	55	LF							
382				5.5x18 GL	320	LF							
383				7x18 GL	175	LF							
384				5.25x11.25 PSL	260	LF							
385				Pre-Fabricated wood floor trusses	23835	LF							
386				Pre-Engineered Roof Trusses	7865	LF							
387				(2x12) Canopy SCAB	550	LF							
388				Joist hanger.	4287	EA							
389	S1-12A to S1-15A		061000	ROUGH CARPENTRY	47455	SF							
390				(3/4") T&G OSB or Plywood sheathing.	16005	SF							
391	A1-11A TO ID-7.3			(5/8") Exterior grade OSB or Plywood sheathing.	15300	SF							
392			064100	SHEARWALL	230	LF							
393				(5/8", 1-Layer) Plywood sheathing.	1370	LF							
394				ARCHITECTURAL WOOD CASEWORK	16	EA							
395				(12" W) Rod & Shelf.	1370	LF							
396				(2) Rod & (12" D) Shelf.	1370	LF							
397				(14"3"Lx16Dx26"H) Wall cabinet.	16	EA							

[illegible]

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST		
							MHrs/ Unit	\$/Hour	(\$Per Unit)						
477	A1-11A TO ID-7.3			(2x6) Wood studs at 16" O.C	1995	LF									
478				(4") Batt insulation	2630	SF									
479				(5/8", 1-Layer) Type X, GYP. BD. both side	2630	SF									
480				(1", 1-Layer) Type X, GYP. Liner panel both side	2630	SF									
481				(2x6) Top and bottom track.	880	LF									
482	A1-11A TO ID-7.3			(1 HR) EXTERIOR WALL (2250 LF)											
483				(2x6) Wood studs at 16" O.C	15235	LF									
484				(R-20) Batt insulation.	10365	SF									
485				(5/8", 1-Layer) Typ X, GYP. BD. One side.	12610	SF									
486				(5/8", 1-Layer) Type X, Exterior Plywood sheathing one side.	12610	SF									
487	A1-11A TO ID-7.3		093100	(2x6) Top and bottom track.	6750	LF									
488				CERAMIC / PORCELAIN TILING											
				Porcelain tile.	4697	SF									
				Kitchen backsplash wall tile.	887	SF									
			096000	FLOORING											
489	A1-11A TO ID-7.3			Carpet floor.	15373	SF									
490				Vinyl wood plank w/ sound mat floor.	27816	SF									
491				Corridor Carpet Floor.	4336	SF									
492				Wood base painted.	16400	LF									
			099100	PAINTING											
493	A1-11A TO ID-7.3			GWB ceiling paint.	52655	SF									
494				GWB wall paint.	191915	SF									
495				Door paint. (620 EA)	41921	SF									
				Subtotal											
			100000	DIVISION 10 - SPECIALTIES											
			101510	TOILET COMPARTMENTS											
496	A1-11A TO ID-7.3			Compartment wall. (6' H)	80	LF									
			102813	TOILET AND BATH ACCESSORIES											
497	A1-11A TO ID-7.3			Toilet paper holder.	94	EA									
498				Towel bar.	94	EA									
499				Mirror.	94	EA									
500				(36"x60") Tub	27	EA									
				Subtotal											
			110000	DIVISION 11 - EQUIPMENT											
501	A1-11A TO ID-7.3			Range & Micro wave.	66	EA									
502				Refrigerator.	66	EA									
503				Washer/Dryer Stacked.	66	EA									
504				Dishwasher.	66	EA									
505				Dryer	66	EA									
506				Washer	66	EA									
				Subtotal											
			120000	DIVISION 12 - FURNISHING											
			123660	QUARTZ SURFACING COUNTERTOPS											
507				QUARTZ COUNTER TOP - MSI SURFACES - MANHATTAN GRAY 3CM - POLISHED	2900	SF									
				Subtotal											
			150000	DIVISION 15 - HEATING, VENTILATING, AND AIR- CONDITIONING (HVAC)											
508	M1-11A TO MP1-21			EH 1-1-2 - ELECTRIC HEATER, MANUF: MARLEY, MODEL NO: AWH (100 CFM)	1	EA									
509				FC 1-1-1 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 1-1- 1, Manuf: CARRIER, FE4A/25HCE (800CFM)	1	EA									
510				FC 1-2-1 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 1-2- 1, Manuf: CARRIER, FE4A/25HCE (800CFM)	1	EA									
511				FC 1-3-1 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 1-3- 1, Manuf: CARRIER, FE4A/25HCE (800CFM)	1	EA									
512				FC 1-4-1 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 1-4- 1, Manuf: CARRIER, FE4A/25HCE (800CFM)	1	EA									
513				Fire damper	4	EA									
514				NON-FREEZE WALL HYDRANT, ROOF MOUNT PEDESTAL W/ MOUNTING FLANGE & SHROUD, MALE HOSE END OUTLET W/ DUAL CHECK BACKFLOW PREVENTER, (3/4") INLET W/ SELF DRAINING VENTURI - WOODFORD MODEL SRH-MS	6	EA									
515				NON-FREEZE WALL HYDRANT, ROOF MOUNT PEDESTAL W/ MOUNTING FLANGE & SHROUD, MALE HOSE END OUTLET W/ DUAL CHECK BACKFLOW PREVENTER, (3/4") INLET W/ SELF DRAINING VENTURI - WOODFORD MODEL SRH-MS	1	EA									
516				RG2 - (20"x18") Return grille - Manuf: Titus, Model: 355RS, Steel	4	EA									
517				SG16 - (14x8) Supply grille - Manuf: Titus, Model: 301RS, Steel (200 CFM) w/ Radiation damper	16	EA									
518				EF A - EXHAUST FAN - MANUF: BROAN, MODEL: 670, (50 CFM)	84	EA									
519				FC A1 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP A1, Manuf: CARRIER, FFMA/25HCE (600CFM)	16	EA									
520				FC A3 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP A3, Manuf: CARRIER, FFMA/25HCE (600CFM)	2	EA									
521				FC B1 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP B1, Manuf: CARRIER, FFMA/25HCE (600CFM)	13	EA									
522				FC B2 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP B2, Manuf: CARRIER, FFMA/25HCE (800CFM)	9	EA									
523				FC B2E - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP B2, Manuf: CARRIER, FFMA/25HCE (800CFM)	4	EA									
524				FC B2-HC - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP B2-HC, Manuf: CARRIER, FFMA/25HCE (800CFM)	1	EA									
525					8	EA									
526				Radiation damper	387	EA									
527				RG2 - (16"x10") Return grille - Manuf: Titus, Model: 355RS	16	EA									
528				RG2 - (36"x10") Return grille - Manuf: Titus, Model: 355RS	13	EA									
529				RG2 - (36"x12") Return grille - Manuf: Titus, Model: 355RS	22	EA									
530				RG3 - (16"x10") Return grille - Manuf: Titus, Model: 350RL	91	EA									
531				RG3 - (36"x10") Return grille - Manuf: Titus, Model: 350RL	18	EA									
532				SG16 - (14x8) Supply grille - Manuf: Titus, Model: 301RS, Steel (200 CFM)	194	EA									
533				SG16 - (8x6) Supply grille - Manuf: Titus, Model: 301RS, Steel	136	EA									
534							Galvanized sheet metal duct w/ Wrap equal to ownes coming								
535							(12x12) Metal duct	80	LF						
536							(12X10) Metal duct	15	LF						
537							(14X10) Metal duct	150	LF						
							(14X12) Metal duct	40	LF						
							ROUND DUCT								

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHrs/ Unit	\$/Hour	(\$Per Unit)				
538	M1-11A TO MP1-21			(8"Dia) Round duct	170	LF							
539				(4"Dia) Round duct	3120	LF							
				FLEXIBLE ROUND DUCT									
540				(10"Dia) Flexible round duct	760	LF							
541				(8"Dia) Flexible round duct	240	LF							
542				(4"Dia) Flexible Round duct	445	LF							
543				(5"Dia) Flexible Round duct	530	LF							
544				(7"Dia) Flexible Round duct	1460	LF							
545				(8"Dia) Flexible Round duct	2790	LF							
				Subtotal									
			150000	DIVISION 15 - PLUMBING									
546	P1-11A TO P3-08			FCO - FLOOR CLEANOUT - CAST IRON CLEANOUT W/ GSKET SEAL & THREADED PLUG, ADJUSTABLE CAST IRON ROUND TOP W/ SECURING SCREW - JAY R. SMITH FIGURE 4220	6	EA							
547				(2") HUB DRAIN W/ PRIMER CONNECTION	39	EA							
548				AAV - AIR ADMITTANCE VALVE - STUDOR MINI-VENT, INTERNAL SCREENING, PREVENTS THE RELEASE OF FOUL AIR WHITE ABS	39	EA							
549				IM-1 - ICE MAKER OUTLET BOX: ABS, LEAD FREE W/ QUARTER TURN BALL VALVE & WATER HAMMER ARRESTOR - SIOUX CHIEF 696-G1010	40	EA							
550				KS-1 - KITCHEN SINK - RESIDENTIAL	40	EA							
551				LAV-1 - LAVATORY - RESIDENTIAL	100	EA							
552				SH-1 - SHOWER - RESIDENTIAL W/ SHOWER HEAD	40	EA							
553				SHUTT-OFF VALVE	40	EA							
554				WATER SUBMETER	40	EA							
555				WC-1 - WATER CLOSET - RESIDENTIAL	62	EA							
556				WH-1 - WATER HEATER - MODEL: ENLB-40 - 38 GAL, W/ T&P RELIEF VALVE, VACCUM RELIEF VALVE & WATTS LFBRV COMBINATION BALL & THERMAL RELIEF VALVE, A O SMITH - PROLINE SERIES	18	EA							
557				WH-2 - WATER HEATER - MODEL: ENLB-50 - 48 GAL, W/ T&P RELIEF VALVE, VACCUM RELIEF VALVE & WATTS LFBRV COMBINATION BALL & THERMAL RELIEF VALVE, A O SMITH - PROLINE SERIES	22	EA							
558				WM-1 - WASHING MACHINE OUTLET BOX, ABS, LEAD FREE W/ QUARTER TURN BALL VALVE, WATER HAMMER ARRESSTOR - SIOUX CHIEF 696-G1010 SERIES	40	EA							
				Subtotal									
559	P1-11A TO P3-08			DOMESTIC WATER PIPING									
560				(1-1/2") COLD WATER PIPE	365	LF							
561				(2") COLD WATER PIPE	50	LF							
562				(2-1/2") COLD WATER PIPE	295	LF							
563				(3") COLD WATER PIPE	20	LF							
564				(1/2") COLD WATER PIPE	1985	LF							
565				(1/2") HOT WATER PIPE	1485	LF							
566				(1-1/4") COLD WATER PIPE	195	LF							
567				(3/4") COLD WATER PIPE	1700	LF							
568				(3/4") HOT WATER PIPE	1480	LF							
569				SANITARY PIPING									
570				(4") SANITARY PIPE	150	LF							
571				(6") SANITARY PIPE	470	LF							
572				(2") SANITARY PIPE	1620	LF							
573				(2") VENT PIPE	650	LF							
				(3") SANITARY PIPE	1780	LF							
				(3") VENT PIPE	630	LF							
				Subtotal									
			160000	DIVISION 16 - ELECTRICAL									
574	E1-11A TO EP1-32			LIGHT FIXTURE									
575				A1 - 6" SURFACE MOUNT LED DOWNLIGHT - MANUF: HALO, MODEL: SLD 1200 SERIES / SLD612835WH/80 CRI/3500K/WHITE	15	EA							
576				A1 - 6" SURFACE MOUNT LED DOWNLIGHT - MANUF: HALO, MODEL: SLD 1200 SERIES / SLD612835WH/80 CRI/3500K/WHITE	39	EA							
577				B1 - UNIT ENTRY SCONE - MANUF: SAVOY HOUSE, MODEL: 9-0901-1-89/GLENN 1-LIGHT WALL SCONE / 7"WX12"HX9"D/E26 8W 120V LED BULB (1 PER FIXTURE) / MATTE BLACK FINISH	12	EA							
578				B1 - UNIT ENTRY SCONE - MANUF: SAVOY HOUSE, MODEL: 9-0901-1-89/GLENN 1-LIGHT WALL SCONE / 7"WX12"HX9"D/E26 8W 120V LED BULB (1 PER FIXTURE) / MATTE BLACK FINISH	41	EA							
579				EM - EMERGENCY FIXTURE LIGHT - SEALED NICKEL CADMIUM BATTERY, CIRCULAR HEAD, DAMP LOCATION LISTED, W/ BATTERY CAPACITY TO POWER REMOTE HEAD, MANUF: SURE LITES SEL50 SERIES LITHONIA	8	EA							
580				EM - EMERGENCY FIXTURE LIGHT - SEALED NICKEL CADMIUM BATTERY, CIRCULAR HEAD, DAMP LOCATION LISTED, W/ BATTERY CAPACITY TO POWER REMOTE HEAD, MANUF: SURE LITES SEL50 SERIES LITHONIA	24	EA							
581				EMR1 - REMOTE HEAD, PAIRED W/ EMERGENCY FIXTURE OR EXIT SIGN, SINGLE HEAD, MANUF: SURE LITES SRP SERIES	4	EA							
582				S1 - 4' LED STRIP LIGHT - METALUX SNLED SERIES, LITHONIA	4	EA							
583				S1 - 4' LED STRIP LIGHT - METALUX SNLED SERIES, LITHONIA	18	EA							
584				S3 - 4' SURFACE/WALL MOUNTED LED FIXTURE, INTEGRAL OCCUPANCY SENSOR W/ 0-10V DIMMING, STEP DIMMING, HIGH LUMEN OUTPUT, INTEGRAL 14W BATTERY PACK, MANUF: METALUX SWLED SERIES LITHONIA	3	EA							
585				S3 - 4' SURFACE/WALL MOUNTED LED FIXTURE, INTEGRAL OCCUPANCY SENSOR W/ 0-10V DIMMING, STEP DIMMING, HIGH LUMEN OUTPUT, INTEGRAL 14W BATTERY PACK, MANUF: METALUX SWLED SERIES LITHONIA	9	EA							
586				X1 - EXIT SIGN, LED LAMP, POLYCARBONATE HOUSING, SELF CONTAINED BATTERY, MODEL: SURE LITES LPX SERIES LITHONIA	6	EA							
587				X1 - EXIT SIGN, LED LAMP, POLYCARBONATE HOUSING, SELF CONTAINED BATTERY, MODEL: SURE LITES LPX SERIES LITHONIA	9	EA							
588				D - 7" SURFACE MOUNTED LED FIXTURE - MANUF: SATCO - S29331 / 7" FLUSH MOUNT LED FIXTURE - ROUND /120V	434	EA							
				F - 50" CEILING FAN W/ LED LIGHT KIT - MANUF: CASK INDUSTRIES - CF104/4-BLADE/50"WX19.5"H	141	EA							

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHrs/ Unit	\$/Hour	(\$Per Unit)				
589				P - ISLAND PENDANT - MANUF: KUZCO LIGHTING - MODEL: VANDERBILT 493210-WH/GD/10"DIA X 12"H / 120" MAX CORD LENGTH	109	EA							
590				VA - VANITY SCONCE - MANUF: QUORUM INTERNATIONAL - MODEL: 507-3-6980/EPsy 3-LIGHT VANITY / 9.25"H X23.5"W X 7"D / 100W MAX WATTAGE	155	EA							
591				W - EXTERIOR SCONCE - MANUF: QUORUM INTERNATIONAL - MODEL: 730-69/TORREY SM LANTERN - NR/13.75"H X 7.5"W X 14.75"D / 100W MAX	37	EA							
				LIGHTING CONTROLS									
592				OCCUPANCY SENSOR SWITCH	3	EA							
593				OCCUPANCY SENSOR SWITCH	12	EA							
594				3-WAY SWITCH	226	EA							
595				SINGLE TOGGLE SWITCH	675	EA							
				RECEPTACLES & SWITCHES									
596				DUPLEX RECEPTACLE	805	EA							
597				DUPLEX RECEPTACLE	24	EA							
598				GFI DUPLEX RECEPTACLE	460	EA							
599				GFI RECEPTACLE WEATHER PROOF	41	EA							
600				QUAD RECEPTACLE	2	EA							
601				QUAD RECEPTACLE	6	EA							
602				240 VOLT RECEPTACLE	106	EA							
603				COMBINATION DATA/ TELE OUTLET	282	EA							
604				JUNCTION BOX	106	EA							
605				SPLIT DUPLEX RECEPTACLE	53	EA							
606				TELEVISION OUTLET	151	EA							
607				USB DUPLEX RECEPTACLE	164	EA							
608				USB GFI DUPLEX RECEPTACLE	36	EA							
				DISCONNECT SWITCHES									
609				SERVICE DISCONNECT "D1A3"	1	EA							
				LOW VOLTAGE & OTHER ELECTRICAL DEVICES									
610				METER STACK	8	EA							
611				METERCENTER ELBOW	4	EA							
612				METERCENTER MAIN	4	EA							
613				ELECTRIC WIRING	1	LS							
				ELECTRIC BREAKER									
614				ELECTRIC BREAKER - 1P 20A	753	EA							
615				ELECTRIC BREAKER - 2P 30A	104	EA							
616				ELECTRIC BREAKER - 2P 50A	52	EA							
				ELECTRIC PANEL									
617				LOAD CENTER - 125A MLO 1PHASE 3W	36	EA							
618				ELECTRIC PANEL "A1" - 400A MLO 3PHASE 4W	1	EA							
619				ELECTRIC PANEL "A3" - 400A MLO 3PHASE 4W	1	EA							
				FIRE ALARM									
620				FIRE ALARM DOOR HOLDER	6	EA							
621				FIRE ALARM MINI HORN (CANDELAS)	130	EA							
622				FIRE ALARM HORN W/STROBE (CANDELAS)	3	EA							
623				FIRE ALARM HORN W/STROBE (CANDELAS)	19	EA							
624				FIRE ALARM PULL STATION	3	EA							
625				FIRE ALARM PULL STATION	3	EA							
626				SMOKE ALARM	3	EA							
627				SMOKE DETECTOR	18	EA							
628				SPRINKLER FLOW SWITCH	1	EA							
629				SPRINKLER FLOW SWITCH	3	EA							
630				SPRINKLER VALVE TAMPER SWITCH	1	EA							
631				SPRINKLER VALVE TAMPER SWITCH	3	EA							
632				120V, SELF CONTAINED AUDIBLE CARBON MONOXIDE SMOKE ALARM	98	EA							
633				120V, SELF CONTAINED AUDIBLE SMOKE ALARM	88	EA							
				Subtotal									
				BUILDING 1000 B									
			020000	DIVISION 02 - EXISTING CONDITIONS									
			022000	EARTHWORK									
634	S1-11B	S0-01, S3-01 & S3-02		Footing excavation.	13660	CF							
635				Footing backfill.	3090	CF							
				Subtotal									
			030000	DIVISION 03 - CONCRETE									
			033000	CAST IN PLACE CONCRETE									
				(2'Wx1'8"H) CONCRETE FOOTING									
636	S1-11B	S0-01, S3-01 & S3-02		Compaction of sub-grade.	3690	SF							
637				Rebar's (Grade 60)	7860	LB							
638				Concrete footing. (fc = 3000 PSI)	4915	CF							
				(2'Wx2'2"H) CONCRETE FOOTING									
639	S1-11B	S0-01, S3-01 & S3-02		Compaction of sub-grade.	1375	SF							
640				Rebar's (Grade 60)	3805	LB							
641				Concrete footing. (fc = 3000 PSI)	2380	CF							
				(1'Wx8"H) CONCRETE FOOTING									
642	S1-11B	S0-01, S3-01 & S3-02		Compaction of sub-grade.	185	SF							
643				Rebar's (Grade 60)	130	LB							
644				Concrete footing. (fc = 3000 PSI)	80	CF							
				(5'SQ. x2'H) CONCRETE FOOTING PAD (56 EA)									
645	S1-11B	S0-01, S3-01 & S3-02		Compaction of sub-grade.	1700	SF							
646				Rebar's (Grade 60)	4480	LB							
647				Concrete footing. (fc = 3000 PSI)	2800	CF							
				(5'Wx7'6"Lx2'H) CONCRETE FOOTING PAD (1 EA)									
648	S1-11B	S0-01, S3-01 & S3-02		Compaction of sub-grade.	45	SF							
649				Rebar's (Grade 60)	120	LB							
650				Concrete footing. (fc = 3000 PSI)	75	CF							
				(5'Wx7'8"Lx2'H) CONCRETE FOOTING PAD (1 EA)									
651	S1-11B	S0-01, S3-01 & S3-02		Compaction of sub-grade.	45	SF							
652				Rebar's (Grade 60)	130	LB							
653				Concrete footing. (fc = 3000 PSI)	77	CF							
				(5'Wx8'Lx2'H) CONCRETE FOOTING PAD (1 EA)									
654	S1-11B	S0-01, S3-01 & S3-02		Compaction of sub-grade.	50	SF							
655				Rebar's (Grade 60)	130	LB							
656				Concrete footing. (fc = 3000 PSI)	80	CF							
				(5'Wx9'8"Lx2'H) CONCRETE FOOTING PAD (2 EA)									
657	S1-11B	S0-01, S3-01 & S3-02		Compaction of sub-grade.	50	SF							
658				Rebar's (Grade 60)	155	LB							
659				Concrete footing. (fc = 3000 PSI)	97	CF							
				ELEVATOR PIT CONCRETE FOOTING PAD									
660	S1-11B	S0-01, S3-01 & S3-02		Compaction of sub-grade.	95	SF							
661				Rebar's (Grade 60)	290	LB							
662				(12" THK) Concrete footing. (fc = 3000 PSI)	95	CF							
				CONCRETE WALL									
663	S1-11B	S0-01, S3-01 & S3-02		Rebar's (Grade 60)	285	LB							
664				(8" THK) Concrete wall. (fc = 5000 PSI)	125	CF							
				SLAB ON GRADE									
665	S1-11B	S0-01, S3-01 & S3-02		Compaction of sub-grade.	13180	SF							
666				(10 MIL) Vapor barrier.	13180	SF							

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHrs/ Unit	\$/Hour	(\$Per Unit)				
667				(4" Thick) Reinforced concrete slab w/ post tensioning. (f'c = 3000 PSI)	13180	SF							
668	S1-11B	S0-01, S3-01 & S3-02		SLAB ON GRADE									
669				Compaction of sub-grade.	550	SF							
670				(10 MIL) Vapor barrier.	550	SF							
671	S1-12B to S1-15B			(4" Thick) Concrete slab w/ CIP 6x6 - 10/10 WWM. (f'c = 3000 PSI)	550	SF							
				Subtotal									
			040000	DIVISION 04 - MASONRY									
			042000	UNIT MASONRY									
672	A1-11A TO ID-7.3			Exterior Type BR-1, Brick Veneer-Gray.	2310	SF							
				Subtotal									
			050000	DIVISION 05 - METAL									
			051200	STRUCTURAL STEEL									
673	S1-12B			W16x31	65	LF							
674				W18x35	40	LF							
675				W18x50	90	LF							
676				W18x76	205	LF							
			053000	METAL DECK									
677	S1-12B			Metal canopy.	215	SF							
			055000	METAL FABRICATIONS									
678				MISC. Item.	1	LS							
			057000	ORNAMENTAL METAL									
679	A1-11A TO ID-7.3			Type-MR-1, 42" Aluminum picket railing.	695	LF							
680				(42" H) Hand Rail.	110	LF							
				Subtotal									
			060000	DIVISION 06 - WOOD, PLASTIC AND COMPOSITES									
			061053	WOOD FRAMING									
681	S1-12A to S1-16B			(2x8) Header beam.	1110	LF							
682				(2x10) Header beam.	1070	LF							
683				(2x12) Header beam.	8	LF							
684				5.5x11.25 GL	410	LF							
685				5.5x14 GL	70	LF							
686				5.5x18 GL	265	LF							
687				7x18 GL	255	LF							
688				5.25x11.25 PSL	275	LF							
689				(2-1.75x9.25) LVL beam.	5	LF							
690				Pre-Fabricated wood floor trusses	28025	LF							
691				Pre-Engineered Roof Trusses	7885	LF							
692				(2x12) Canopy SCAB	1020	LF							
693				(2x12) Roof joist.	65	LF							
694				Joist hanger.	4821	EA							
			061000	ROUGH CARPENTRY									
695	S1-12A to S1-15A			(3/4") T&G OSB or Plywood sheathing.	55710	SF							
696				(5/8") Exterior grade OSB or Plywood sheathing.	16520	SF							
	A1-11A TO ID-7.3			SHEARWALL									
697				(5/8", 1-Layer) Plywood sheathing.	17640	SF							
			064100	ARCHITECTURAL WOOD CASEWORK									
698	A1-11A TO ID-7.3			(12" W) Road & Shelf	1315	LF							
723				(8'3"x1Dx3'6"H) Wall cabinet.	1	EA							
707				(12'Lx2'Dx2'10"H) Wall cabinet.	13	EA							
701				(13'Lx2'Dx2'10"H) Wall cabinet.	1	EA							
709				(11'3"Lx1Dx2'6"H) Wall cabinet.	14	EA							
713				(11'2"Lx1Dx2'6"H) Wall cabinet.	7	EA							
720				(15'x1Dx2'6"H) Wall cabinet.	1	EA							
716				(13'6"Lx1Dx2'6"H) Wall cabinet.	7	EA							
711				(14'Lx1D2'10"H) Wall cabinet.	1	EA							
707				(12'Lx2'Dx2'10"H) Base cabinet.	14	EA							
708				(6'Lx2'Dx2'10"H) Base cabinet.	70	EA							
709				(11'Lx2'Dx2'10"H) Base cabinet.	8	EA							
710				(6'Lx2Dx2'10"H) Base cabinet.	28	EA							
711				(8'8"Lx2Dx2'10"H) Base cabinet.	14	EA							
712				(12'Lx1Dx2'6"H) Base cabinet.	10	EA							
713				(9'8"Lx2Dx2'10"H) Base cabinet.	10	EA							
714				(4'Lx2Dx2'10"H) Base cabinet.	7	EA							
715				(8'8"Lx2Dx2'10"H) Base cabinet.	7	EA							
716				(8'Lx2Dx2'10"H) Base cabinet.	9	EA							
717				(10'x2Dx1'9"H) Base cabinet.	1	EA							
718				(11'3'x2Dx1'9"H) Base cabinet.	2	EA							
719				(12'4'x1Dx2'6"H) Base cabinet.	2	EA							
720				(13'x2Dx2'10"H) Base cabinet.	1	EA							
721				(3'x2Dx2'10"H) Base cabinet.	1	EA							
722				Cabinet.	110	EA							
723				16" Mud bench	53	EA							
				Subtotal									
			070000	DIVISION 07 - THERMAL AND MOISTURE PROTECTION									
				ROOFING									
724	A2-10			(R-39) Roof insulation.	16520	SF							
725	A1-11A TO ID-7.3			(60 MIL) TPO Roofing.	16520	SF							
726				Walking pad	925	SF							
727				Air/Moisture barrier.	8300	SF							
			076000	SHEET METAL FLASHING AND TRIM									
728	A1-11A TO ID-7.3			Downspout.	355	LF							
729				Gutter	530	LF							
				Subtotal									
			080000	DIVISION 08 - OPENING									
			080152	WOOD WINDOWS									
730	A1-11A TO ID-7.3			Type W 04, (6'-0" W x 6'-0" H) Single vinyl window.	180	EA							
731				Type W 03, (5'-0" W x 6'-0" H) Single vinyl window.	35	EA							
732				(19'-0" W x 5'-6"H) Glass window.	1	EA							
733				Type S01&S03- (9'-0" W x 9'-0" H) Storefront.	10	EA							
734				Type S02- (5'-11 1/2" w x 9'-0" H) Storefront.	2	EA							
735				Type S04- (6'-4" W x 9'-0" H) Storefront.	2	EA							
736				Type S05- (6'-4" W x 9'-0" H) Storefront.	2	EA							
737				Type S06- (10'-0" W x 9'-0" H) Storefront.	1	EA							
			081113	HOLLOW METAL DOORS, FRAMES AND HARDWARE									
738	A1-11A TO ID-7.3			(3'-0" W x 7'-0" H) HM door & frame.	1	EA							
739				(3'-0" W x 8'-0" H) HM door & frame.	1	EA							
			082100	WOOD DOORS									
740				(HR 90 MIN) (6'-0" W x 7'-0" H) Fiberglass door & frame.	4	EA							
741				(HR 90 MIN) (3'-0" W x 7'-0" H) HM door & frame.	4	EA							

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHFS/ Unit	\$/Hour	(\$Per Unit)				
742	A1-11A TO ID-7.3			(HR 45 MIN) (3'-0" W x 7'-0" H) HM door & frame.	16	EA							
743				(9'-0" W x 8'-0" H) VinyI/ Glass door & frame.	4	EA							
744				(3'-0" W x 8'-0" H) Fiberglass door & frame.	53	EA							
745				(2'-10" W x 6'-8" H) Solid core wood door & frame.	341	EA							
746				(2'-6" W x 6'-8" H) Solid core wood door & frame.	13	EA							
747				(HR 20 MIN) (3'-0" W x 7'-0" H) Solid core wood door & frame.	53	EA							
748				(5'-0" W x 6'-8" H) Solid core wood door & frame.	15	EA							
749				(3'-0" W x 6'-8" H) Solid core wood door & frame.	3	EA							
750				(2'-0" W x 6'-8" H) Hollow core wood door & frame.	14	EA							
751				(3'-0" W x 6'-8" H) Solid core wood door.	28	EA							
087100				FINISH HARDWARE									
752	A1-11A TO ID-7.3			Door hardware. (548 EA)	1	LS							

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHrs/ Unit	\$/Hour	(\$Per Unit)				
827				Type RB-1 Rubber base.	125	LF							
828				Type WD-7, Wood wall trim.	15	LF							
829	A1-11A TO ID-7.3		099100	PAINTING									
				GWB ceiling paint.	57500	SF							
				GWB wall paint.	231275	SF							
831				Door paint. (548 EA)	51475	SF							
				Subtotal									
			100000	DIVISION 10 - SPECIALTIES									
			101510	TOILET COMPARTMENTS									
832	A1-11A TO ID-7.3			Compartment wall. (6' H)	215	LF							
			102813	TOILET AND BATH ACCESSORIES									
833				Toilet paper holder.	68	EA							
834	A1-11A TO ID-7.3			Tower bar.	68	EA							
835				Mirror.	70	EA							
836				(36"x60") Tub	21	EA							
				Subtotal									
			110000	DIVISION 11 - EQUIPMENT									
837	A1-11A TO ID-7.3			Dishwasher.	61	EA							
838				Range & Micro wave.	60	EA							
839				Refrigerator	61	EA							
840				Washer/Dryer stacked	60	EA							
841				Dryer	15	EA							
				Subtotal									
			120000	DIVISION 12 - FURNISHING									
			123660	QUARTZ SURFACING COUNTERTOPS									
842				QUARTZ COUNTER TOP - MSI SURFACES - MANHATTAN GRAY 3CM - POLISHED	2525	SF							
				Subtotal									
			150000	DIVISION 15 - HEATING, VENTILATING, AND AIR- CONDITIONING (HVAC)									
843	M1-11A TO MP1-21			- (20"x14") Return grille - Manuf: Titus, Model: 355RS, Steel	1	EA							
844				DS 1-1-1 - Ductless split system w/ Heat pump Outdoor unit DSHP 1-1-1, Manuf: MITSUBISHI ELECTRIC, MODEL: PKA/PUZ, (705 CFM)	1	EA							
845				EF 1-1-1 - Exhaust fan, Manuf: Broan, Model: L300, 300 CFM	1	EA							
846				EF 1-1-2 - Exhaust fan, Manuf: Broan, Model: L200, 200 CFM	1	EA							
847				EF 1-1-3 - Exhaust fan, Manuf: Broan, Model: L250, 250 CFM	1	EA							
848				EF 1-1-6 - Exhaust fan, Manuf: Broan, Model: AE80, 80 CFM	1	EA							
849				EH 1-1-1 - ELECTRIC HEATER, MANUF: MARLEY, MODEL NO. AWH (100 CFM)	1	EA							
850				EH 1-1-3 - ELECTRIC HEATER, MANUF: MARLEY, MODEL NO. AWH (100 CFM)	1	EA							
851				ELECTRIC DUCT COIL	1	EA							
852				ESP-1 - PUMP - MODEL: STANCO OIL MINDER SYSTEM W/ ALARM & REMOTE MONITORING CIRCUIT	1	EA							
853				FC 1-1-2 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 1-1- 2, Manuf: CARRIER, FE4A/25HCE (1600CFM)	1	EA							
854				FC 1-1-3 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 1-1- 3, Manuf: CARRIER, FE4A/25HCE (1600CFM)	1	EA							
855				FC 1-1-4 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 1-1- 4, Manuf: CARRIER, FE4A/25HCE (1600CFM)	1	EA							
856				FC 1-1-5 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 1-1- 5, Manuf: CARRIER, FE4A/25HCE (1600CFM)	1	EA							
857				FC 1-1-6 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 1-1- 6, Manuf: CARRIER, FE4A/25HCE (1600CFM)	1	EA							
858				FC 1-1-7 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 1-1- 7, Manuf: CARRIER, FE4A/25HCE (1600CFM)	1	EA							
859				FC 1-2-2 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 1-2- 2, Manuf: CARRIER, FE4A/25HCE (800CFM)	1	EA							
860				FC 1-3-2 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 1-3- 2, Manuf: CARRIER, FE4A/25HCE (800CFM)	1	EA							
861				FC 1-4-2 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 1-4- 2, Manuf: CARRIER, FE4A/25HCE (800CFM)	1	EA							
862				Fire damper	4	EA							
863				HWR-1 - HOT WATER RETURN PUMP - MODEL: TACO 006, INLINE	1	EA							
864				L1 - LOUVER - MANUF: GREENHECK, MODEL: ESD-435	1	EA							
865				L2 - LOUVER - MANUF: GREENHECK, MODEL: ESD-435	1	EA							
866				NFWH - NON-FREEZE EXTERIOR WALL HYDRANT, (3/4") CAST BRONZE HYDRANT, RECESSED W/ STAINLESS STEEL BOX, VACUUM BREAKER, NICKEL BRONZE - JAY R. SMITH FIGURE 5509-QT	4	EA							
867				NON-FREEZE WALL HYDRANT, ROOF MOUNT PEDESTAL W/ MOUNTING FLANGE & SHROUD, MALE HOSE END OUTLET W/ DUAL CHECK BACKFLOW PREVENTER, (3/4") INLET W/ SELF DRAINING VENTURI - WOODFORD MODEL SRH-MS	1	EA							
868				RG2 - (20"x18") Return grille - Manuf: Titus, Model: 355RS, Steel	6	EA							
869				SF 1-1-1 - SUPPLY FAN - MANUF: GREENHECK, MODEL: SQ 90- 95, TYPE: INLINE (250 CFM)	1	EA							
870				SG16 - (14x8) Supply grille - Manuf: Titus, Model: 301RS, Steel (200 CFM) w/ Radiation damper	15	EA							
871				EF A - EXHAUST FAN - MANUF: BROAN, MODEL: 670, (50 CFM)	67	EA							
872				FC A2 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP A2, Manuf: CARRIER, FFMA/25HCE (600CFM)	13	EA							
873				FC A3 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP A3, Manuf: CARRIER, FFMA/25HCE (600CFM)	1	EA							
874				FC A4 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP A4, Manuf: CARRIER, FFMA/25HCE (600CFM)	14	EA							
875				FC A4-HC - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP A4-HC, Manuf: CARRIER, FFMA/25HCE (600CFM)	1	EA							
876				FC A5 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP A5, Manuf: CARRIER, FFMA/25HCE (600CFM)	10	EA							
877				FC B1 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP B1, Manuf: CARRIER, FFMA/25HCE (600CFM)	7	EA							
878				FC B2 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP B2, Manuf: CARRIER, FFMA/25HCE (800CFM)	7	EA							

[illegible]

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHrs/ Unit	\$/Hour	(\$Per Unit)				
948	E1-11A TO EP1-32			B1 - UNIT ENTRY SCONE - MANUF: SAVOY HOUSE, MODEL: 9-0901-1-89/GLENN 1-LIGHT WALL SCONE / 7"WX12"HX9"D/E26 8W 120V LED BULB (1 PER FIXTURE) / MATTE BLACK FINISH	53	EA							
949				EM - EMERGENCY FIXTURE LIGHT - SEALED NICKEL CADMIUM BATTERY, CIRCULAR HEAD, DAMP LOCATION LISTED, W/ BATTERY CAPACITY TO POWER REMOTE HEAD, MANUF: SURE LITES SEL50 SERIES LITHONIA	40	EA							
950				EMR1 - REMOTE HEAD, PAIRED W/ EMERGENCY FIXTURE OR EXIT SIGN, SINGLE HEAD, MANUF: SURE LITES SRP SERIES	2	EA							
951				S1 - 4' LED STRIP LIGHT - METALUX SNLED SERIES, LITHONIA	28	EA							
952				S2E - 4' LED VAPORTIGHT STRIP, IMPACT RESISTANT POLYCARBONATE HOUSING, IMPACT RESISTANT FROASTED POLYCARBONATE LENS, LED LAMP, WIDE DISTRIBUTION, MANUF: LITHONIA VAP LED SERIES, PHILIPS W/ 1600 LUMEN BATTERY	2	EA							
953				S2E - 4' LED VAPORTIGHT STRIP, IMPACT RESISTANT POLYCARBONATE HOUSING, IMPACT RESISTANT FROASTED POLYCARBONATE LENS, LED LAMP, WIDE DISTRIBUTION, MANUF: LITHONIA VAP LED SERIES, PHILIPS W/ 1600 LUMEN BATTERY	2	EA							
954				S3 - 4' SURFACE/WALL MOUNTED LED FIXTURE, INTEGRAL OCCUPANCY SENSOR W/ 0-10V DIMMING, STEP DIMMING, HIGH LUMEN OUTPUT, INTEGRAL 14W BATTERY PACK, MANUF: METALUX SWLED SERIES LITHONIA	15	EA							
955				X1 - EXIT SIGN, LED LAMP, POLYCARBONATE HOUSING, SELF CONTAINED BATTERY, MODEL: SURE LITES LPX SERIES LITHONIA	27	EA							
956				X1 - EXIT SIGN, LED LAMP, POLYCARBONATE HOUSING, SELF CONTAINED BATTERY, MODEL: SURE LITES LPX SERIES LITHONIA	4	EA							
957				D - 7" SURFACE MOUNTED LED FIXTURE - MANUF: SATCO - S29331 / 7" FLUSH MOUNT LED FIXTURE - ROUND /120V	357	EA							
958				F - 50" CEILING FAN W/ LED LIGHT KIT - MANUF: CASK INDUSTRIES - CF104/4-BLADE/50"WX19.5"H	120	EA							
959				P - ISLAND PENDANT - MANUF: KUZCO LIGHTING - MODEL: VANDERBILT 493210-WH/GD/10"DIA X 12"H / 120" MAX CORD LENGTH	120	EA							
960				VA - VANITY SCONCE - MANUF: QUORUM INTERNATIONAL - MODEL: 507-3-6980/EP5Y 3-LIGHT VANITY / 9.25"H X23.5"W X 7"D / 100W MAX WATTAGE	114	EA							
961				W - EXTERIOR SCONE - MANUF: QUORUM INTERNATIONAL - MODEL: 730-69/TORREY SM LANTERN - NR/13.75"H X 7.5"W X 14.75"D / 100W MAX	53	EA							
962				L-17 - SEMI-FLUSH CEILING FIXTURE	11	EA							
963				L-1 - (4") SQUARE RECESSED DOWNLIGHT	196	EA							
964				L-10 PICTURE LIGHT	6	EA							
965				L-11 - MINI PENDANT	4	EA							
966				L-12 - PENDANT	8	EA							
967				L-13 - SEMI FLUSH CEILING FIXTURE	8	EA							
968				L-15 - HARDWARE TABLE LAMP	2	EA							
969				L-16 - PENDANT	4	EA							
970				L-18 - CHANDLIER	1	EA							
971				L-19 - MINI PENDANT	5	EA							
972				L-2 - 6" GLIMPSE SURFACE MOUNT	17	EA							
973				L-20 - WALL SCONE	6	EA							
974				L-22 - MINI PENDANT	6	EA							
975				L-23 - LINEAR SURFACE MOUNT LED	9	EA							
976				L-24 - SEMI FLUSH CEILING FIXTURE	3	EA							
977				L-25 - TRACK LIGHTING FIXTURE	6	EA							
978				L-26 - RECESSED CEILING FIXTURE	12	EA							
979				L-27 - CEILING FAN	5	EA							
980				L-28 - WALL SCONE	2	EA							
981				L-4 - 40" CHANDLIER	1	EA							
982				L-5 - 48" CHANDLIER	2	EA							
983				L-6 - WALL SCONE	2	EA							
984				L-7 - MINI-PENDANT	3	EA							
985				L-8 - PENDANT	6	EA							
986				L-9 - SEMI FLUSH DRUM	2	EA							
987				L21 - PENDANT - MANUF: SATCO NUVO - MODEL: BIZET 1 LIGHT MINI PENDANT / NUVO 60-7242 / VINTAGE BRASS/60W MAX E26 MEDIUM BASE G40	4	EA							
988				L3 - 24" CHANDLIER	2	EA							
989				LIGHTING CONTROLS									
990				3-WAY SWITCH	255	EA							
991				OCCUPANCY SENSOR	8	EA							
992				OCCUPANCY SENSOR SWITCH	4	EA							
993				SINGLE POLE SWITCH	660	EA							
994				RECEPTACLES & SWITCHES									
995				DUPLEX RECEPTACLE	694	EA							
996				DUPLEX RECEPTACLE	41	EA							
997				GFI DUPLEX RECEPTACLE	526	EA							
998				GFI DUPLEX RECEPTACLE WEATHER PROOF	59	EA							
999				TWO WAY COMMUNICATION CALL BOX	5	EA							
1000				240 VOLT RECEPTACLE	104	EA							
1001				COMBINATION DATA/ TELE OUTLET	251	EA							
1002				JUNCTION BOX	106	EA							
1003				SPLIT DUPLEX RECEPTACLE	53	EA							
1004				TELEVISION OUTLET	132	EA							
1005				USB DUPLEX RECEPTACLE	180	EA							
1006				USB GFI DUPLEX RECEPTACLE	40	EA							
1007				USB OUTLET FLOOR BOX	6	EA							
1008				FLOOR BOX DUPLEX RECEPTACLE	15	EA							
1009				DISCONNECT SWITCHES									
1010				DISCONNECT SWITCH	2	EA							
1011				LOW VOLTAGE & OTHER ELECTRICAL DEVICES									
1012				METER/CENTER MAIN	2	EA							
1013				ELECTRIC WIRING	1	LS							
1014	E1-11A TO			ELECTRIC BREAKER									
1015				ELECTRIC BREAKER - 1P 20A	797	EA							
1016				ELECTRIC BREAKER - 2P 30A	104	EA							
1017				ELECTRIC BREAKER - 2P 50A	52	EA							
1018				ELECTRIC PANEL									
1019				LOAD CENTER - 125A MLO 1PHASE 3W	65	EA							
1020				ELECTRIC PANEL "B2" - 400A MLO 3PHASE 4W	1	EA							
1021				ELECTRIC PANEL "B4" - 200A MLO 3PHASE 4W	1	EA							
1022													
1023				FIRE ALARM									
1024				FIRE ALARM ANNUNCIATOR	1	EA							
1025				FIRE ALARM DOOR HOLDER	3	EA							
1026				FIRE ALARM DOOR HOLDER	13	EA							
1027				FIRE ALARM HORN W/STROBE (CANDELAS)	7	EA							

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST	
							MHrs/ UNIT	S/HOUR	(\$*er Unit)					
1020	EP1-32			FIRE ALARM HORN W/STROBE (CANDELAS)	19	EA								
1021				FIRE ALARM PULL STATION	3	EA								
1022				FIRE ALARM PULL STATION	4	EA								
1023				FIRE ALARM STROBE (CANDELAS)	1	EA								
1024				HEAT DETECTOR	1	EA								
1025				HEAT DETECTOR	1	EA								
1026				SMOKE DETECTOR	6	EA								
1027				SMOKE DETECTOR	28	EA								
1028				SPRINKLER FLOW SWITCH	4	EA								
1029				SPRINKLER VALVE TAMPER SWITCH	4	EA								
1030				120V, SELF CONTAINED AUDIBLE CARBON MONOXIDE SMOKE ALARM	74	EA								
1031				120V, SELF CONTAINED AUDIBLE SMOKE ALARM	67	EA								
1032				FIRE ALARM MINI HORN (CANDELAS)	118	EA								
1033				FIRE ALARM MINI HORN W/ STROBE (CANDELAS)	3	EA								
					Subtotal									
			020000	BUILDING 1000 C										
			022000	DIVISION 02 - EXISTING CONDITIONS										
				<u>EARTHWORK</u>										
1034	S1-11C to S1-12C	S0-01, S3-01 & S3-02		Footing excavation.	16370	CF								
1035				Footing backfill.	9410	CF								
				Subtotal										
			030000	DIVISION 03 - CONCRETE										
			033000	<u>CAST IN PLACE CONCRETE</u>										
1036	S1-11C to S1-12C	S0-01, S3-01 & S3-02		(2'Wx1'8"H) CONCRETE FOOTING										
1037				Compaction of sub-grade.	2380	SF								
1038				Rebar's (Grade 60)	5070	LB								
				Concrete footing. (f'c = 3000 PSI)	3170	CF								
1039	S1-11C to S1-12C	S0-01, S3-01 & S3-02		(2'Wx2'2"H) CONCRETE FOOTING										
1040				Compaction of sub-grade.	1050	SF								
1041				Rebar's (Grade 60)	2905	LB								
				Concrete footing. (f'c = 3000 PSI)	1820	CF								
1042	S1-11C to S1-12C	S0-01, S3-01 & S3-02		(1'Wx8"H) CONCRETE FOOTING										
1043				Compaction of sub-grade.	225	SF								
1044				Rebar's (Grade 60)	160	LB								
				Concrete footing. (f'c = 3000 PSI)	100	CF								
1045	S1-11C to S1-12C	S0-01, S3-01 & S3-02		(5'SQ. x2'H) CONCRETE FOOTING PAD (22 EA)										
1046				Compaction of sub-grade.	670	SF								
1047				Rebar's (Grade 60)	1760	LB								
				Concrete footing. (f'c = 3000 PSI)	1100	CF								
1048	S1-11C to S1-12C	S0-01, S3-01 & S3-02		(5'Wx5'6"Lx2'H) CONCRETE FOOTING PAD (1 EA)										
1049				Compaction of sub-grade.	33	SF								
1050				Rebar's (Grade 60)	88	LB								
				Concrete footing. (f'c = 3000 PSI)	55	CF								
1051	S1-11C to S1-12C	S0-01, S3-01 & S3-02		(5'Wx6'Lx2'H) CONCRETE FOOTING PAD (1 EA)										
1052				Compaction of sub-grade.	36	SF								
1053				Rebar's (Grade 60)	100	LB								
				Concrete footing. (f'c = 3000 PSI)	60	CF								
1054	S1-11C to S1-12C	S0-01, S3-01 & S3-02		(5'Wx6'11"Lx2'H) CONCRETE FOOTING PAD (1 EA)										
1055				Compaction of sub-grade.	45	SF								
1056				Rebar's (Grade 60)	115	LB								
				Concrete footing. (f'c = 3000 PSI)	70	CF								
1057	S1-11C to S1-12C	S0-01, S3-01 & S3-02		(5'Wx8'Lx2'H) CONCRETE FOOTING PAD (1 EA)										
1058				Compaction of sub-grade.	50	SF								
1059				Rebar's (Grade 60)	128	LB								
				Concrete footing. (f'c = 3000 PSI)	80	CF								
1060	S1-11C to S1-12C	S0-01, S3-01 & S3-02		(5'Wx1'2"H) RETAINING WALL CONCRETE FOOTING										
1061				Compaction of sub-grade.	690	SF								
1062				Rebar's (Grade 60)	1170	LB								
				Concrete footing. (f'c = 3000 PSI)	730	CF								
1063	S1-11C to S1-12C	S0-01, S3-01 & S3-02		<u>RETAINING WALL</u>										
1064				Rebar's (Grade 60)	2200	LB								
				(12" THK) Concrete wall. (f'c = 5000 PSI)	1375	CF								
1065	S1-11C to S1-12C	S0-01, S3-01 & S3-02		<u>SLAB ON GRADE</u>										
1066				Compaction of sub-grade.	10130	SF								
1067				(10 MIL) Vapor barrier.	10130	SF								
				(4" Thick) Reinforced concrete slab w/ post tensioning. (f'c = 3000 PSI)	10130	SF								
1068	S1-11C to S1-12C	S0-01, S3-01 & S3-02		<u>SLAB ON GRADE</u>										
1069				Compaction of sub-grade.	625	SF								
1070				(10 MIL) Vapor barrier.	625	SF								
				(4" Thick) Concrete slab w/ CIP 6x6 - 10/10 WWM. (f'c = 3000 PSI)	625	SF								
1071	S1-12C to S1-15C			Metal pan concrete stair.	320	SF								
				Subtotal										
			040000	DIVISION 04 - MASONRY										
			042000	<u>UNIT MASONRY</u>										
1072	A1-11A TO ID-7.3			Exterior Type BR-1, Brick Veneer-Gray.	1815	SF								
				Subtotal										
			050000	DIVISION 05 - METAL										
			053000	<u>METAL DECK</u>										
1073	S1-12B			Metal canopy.	130	SF								
			055000	<u>METAL FABRICATIONS</u>										
1074				MISC. Item.	1	LS								
			057000	<u>ORNAMENTAL METAL</u>										
1075	A1-11A TO ID-7.3			(42" H) Hand railing.	160	LF								
1076				Type-MR-1, 42" Aluminum picket railing.	730	LF								
				Subtotal										
			060000	DIVISION 06 - WOOD, PLASTIC AND COMPOSITES										
			061053	<u>WOOD FRAMING</u>										
1077	S1-12A to S1-16C			(2x8) Header beam.	810	LF								
1078				(2x10) Header beam.	975	LF								
1079				5.5x11.25 GL	415	LF								
1080				5.5x14 GL	70	LF								
1081				5.5x18 GL	155	LF								
1082				7x18 GL	135	LF								
1083				5.25x11.25 PSL	120	LF								
1084				Pre-Fabricated wood floor trusses	19285	LF								
1085				Pre-Engineered Roof Trusses	4940	LF								
1086				(2x12) Canopy SCAB	610	LF								
1087				Joist hanger.	3227	EA								

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHrs/ Unit	\$/Hour	(\$Per Unit)				
			061000	ROUGH CARPENTRY									
1088	S1-12A to S1-16C			(3/4") T&G OSB or Plywood sheathing.	38140	SF							
1089				(5/8") Exterior grade OSB or Plywood sheathing.	10380	SF							
	A1-11A TO ID-7.3			SHEARWALL									
1090				(5/8", 1-Layer) Plywood sheathing.	23580	SF							
			064100	ARCHITECTURAL WOOD CASEWORK									
1091				(12" W) Road & Shelf	110	LF							
1092				(12"Lx2'Dx2'10"H) Wall cabinet.	13	EA							
1093				(11'3"Lx1Dx2'6"H) Wall cabinet.	8	EA							
1094				(12'Lx1Dx2'6"H) Wall cabinet.	4	EA							
1095				(13'6"Lx1Dx2'6"H) Wall cabinet.	14	EA							
1096				Unit B3- (11'Lx1Dx2'6"H) Wall cabinet.	4	EA							
1097				(12'Lx2'Dx2'10"H) Base cabinet.	9	EA							
1098				(6'Lx2Dx2'10"H) Base cabinet.	78	EA							
1099				(3'6"Lx2Dx2'10"H) Base cabinet.	4	EA							
1100				(8'8"Lx2Dx2'10"H) Base cabinet.	8	EA							
1101				(12'Lx1Dx2'6"H) Base cabinet.	5	EA							
1102				(9'8"Lx2Dx2'10"H) Base cabinet.	5	EA							
1103				(11'9"Lx2Dx2'10"H) Base cabinet.	4	EA							
1104				(11'Lx2Dx2'10"H) Base cabinet.	14	EA							
1105				(6'8"Lx2Dx2'10"H) Base cabinet.	4	EA							
1106				(9'4"Lx2Dx2'10"H) Base cabinet.	4	EA							
1107				16" Mud bench	13	EA							
1108				Cabinet.	80	EA							
				Subtotal									
			070000	DIVISION 07 - THERMAL AND MOISTURE PROTECTION									
				ROOFING									
1109	A2-10			(R-38) Roof insulation.	10380	SF							
1110				(60 MIL) TPO Roofing.	10380	SF							
1111	A1-11A TO ID-7.3			Walking pad	480	SF							
1112				Air/Moisture barrier.	9490	SF							
			076000	SHEET METAL FLASHING AND TRIM									
1113	A1-11A TO ID-7.3			Downspout	355	LF							
1114				Gutter	425	LF							
				Subtotal									
			080000	DIVISION 08 - OPENING									
			080152	WOOD WINDOWS									
1115				Type W 01, (2'-6" W x 6'-0" H) Single vinyl window.	8	EA							
1116				W 02, (3'-0" W x 6'-0" H) Single vinyl window.	4	EA							
1117				Type W 04, (6'-0" W x 6'-0" H) Single vinyl window.	75	EA							
1118				Type W 03, (5'-0" W x 6'-0" H) Single vinyl window.	17	EA							
1119				Type S01&S03- (9'-0" W x 9'-0" H) Storefront.	5	EA							
1120				Type S05- (6'-4" W x 9'-0" H) Storefront.	2	EA							
1121				Type S07- (10'-0" W x 9'-0" H) Storefront.	1	EA							
1122				Type S08- (8'-6 1/2" W x 6'-0" H) Storefront.	1	EA							
1123				Type S09- (7'-0" W x 9'-0" H) Storefront.	1	EA							
			081113	HOLLOW METAL DOORS, FRAMES AND HARDWARE									
1124				(HR 45 MIN)(3'-0" W x 7'-0" H) HM door & frame.	12	EA							
1125	A1-11A TO ID-7.3			(HR 90 MIN) (3'-0" W x 7'-0" H) HM door & frame.	4	EA							
1126				(3'-0" W x 8'-0" H) Fiberglass door & frame.	36	EA							
1127				(HR 90 MIN) (6'-0" W x 7'-0" H) Fiberglass door & frame.	8	EA							
			082100	WOOD DOORS									
1128				(2'-10" W x 6'-8" H) Solid core wood door & frame.	192	EA							
1129				(2'-6" W x 6'-8" H) Solid core wood door & frame.	13	EA							
1130	A1-11A TO ID-7.3			(HR 20 MIN) (3'-0" W x 7'-0" H) Solid core wood door & frame.	37	EA							
1131				(5'-0" W x 6'-8" H) Solid core wood door & frame.	12	EA							
1132				(3'0" W x 6'8" H) Solid core wood door.	55	EA							
1133				Unit B3, (1'-6" W x 6'-8" H) Hollow core wood door & frame.	4	EA							
			087100	FINISH HARDWARE									
1134	A1-11A TO ID-7.3			Door hardware. (313 EA)	1	LS							
				Subtotal									
			090000	DIVISION 09 - FINISHES									
1135	A1-11A TO ID-7.3			Fitness WP-1, T1-11 Painted Ceiling.	325	SF							
1136				Type MOS-1, Faux Moss Wall.	145	SF							
			092600	GYPSUM BOARD ASSEMBLIES									
1137				GWb ceiling.	35210	SF							
1138				Type WP-2, Wood plank, stained Ceiling.	610	SF							
1139				Type WC-4, Wall covering.	215	SF							
1140				Exterior Type CP-1, Fiber cement panel (4"x10") W/ Battens-White Allura.	2640	SF							
1141	A1-11A TO ID-7.3			Exterior Type CP-2, Fiber cement panel (4"x10") W/ Battens-Dark gray.	6010	SF							
1142				Exterior Type CP-3, Fiber cement panel (4"x10") W/ Metal Reveals White.	615	SF							
1143				Exterior Type WP-1, Wall panel.	1455	SF							
1144				Exterior Type CT-1, (12" H)	520	LF							
1145				Exterior Type CT-1, (2'3" H)	80	LF							
				INTERIOR WALLS									
1146	A1-11A TO ID-7.3			(1 HR) TYPE 1WB4, GWB UNIT WALL (3280 LF)									
1147				(2x4) Wood studs at 16" O.C	22210	LF							
1148				(5/8", 1-Layer) Type X, GYP. BD. both side	59040	SF							
				(2x4) Top and bottom track.	9840	LF							
1149	A1-11A TO ID-7.3			(1 HR) TYPE 1WB6, GWB UNIT WALL (780 LF)									
1150				(2x6) Wood studs at 16" O.C	5290	LF							
1151				(5/8", 1-Layer) Type X, GYP. BD. both side	14040	SF							
				(2x6) Top and bottom track.	2340	LF							
1152				(1 HR) TYPE 1WC4, GWB WALL (230 LF)									
1153				(2x4) Wood studs at 16" O.C	1565	LF							
1154	A1-11A TO ID-7.3			(1/2") Resilient channel	1565	LF							
1155				(4") Batt insulation	2070	SF							
1156				(5/8", 1-Layer) Type X, GYP. BD. One side	2070	SF							
1157				(5/8", 1-Layer) Type X, Exterior grade GYP. BD. One side	2070	SF							
1158				(2x4) Top and bottom track.	690	LF							
				(1/2") Top and bottom track.	460	LF							
1159				(1 HR) TYPE 1WC6, GWB WALL (2390 LF)									
1160				(2x6) Wood studs at 16" O.C	16180	LF							
1161	A1-11A TO ID-7.3			(1/2") Resilient channel	16180	LF							
1162				(6") Batt insulation	21510	SF							
1163				(5/8", 1-Layer) Type X, GYP. BD. One side	21510	SF							
1164				(5/8", 1-Layer) Type X, Exterior grade GYP. BD. One side	21510	SF							
1165				(2x6) Top and bottom track.	7170	LF							
				(1/2") Top and bottom track.	4780	LF							
1166				(1 HR) TYPE 1WD4, GWB UNIT SEP. WALL (1265 LF)									
1167	A1-11A TO ID-7.3			(2x4) Wood studs at 16" O.C	8570	LF							
1168				(4") Batt insulation	22770	SF							
				(5/8", 1-Layer) Type X, GYP. BD. both side	22770	SF							

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHrs/ Unit	\$/Hour	(\$Per Unit)				
1169	A1-11A TO ID-7.3			(2x4) Top and bottom track.	3795	LF							
				(1 HR) TYPE 1WD6, GWB UNIT SEP. WALL (460 LF)									
1170				(2x6) Wood studs at 16" O.C	3125	LF							
1171				(6") Batt insulation	8280	SF							
1172				(5/8", 1-Layer) Type X, GYP. BD. both side	8280	SF							
1173	A1-11A TO ID-7.3			(2x6) Top and bottom track.	1380	LF							
				(2 HR) TYPE 2WK4, GWB SHAFT WALL (630 LF)									
1174				(2x4) Wood studs at 16" O.C	8545	LF							
1175				(4") Batt insulation	11340	SF							
1176				(5/8", 1-Layer) Type X, GYP. BD. both side	11340	SF							
1177	A1-11A TO ID-7.3			(1", 1-Layer) Type X, GYP. Liner panel both side	11340	SF							
1178				(2x4) Top and bottom track.	3780	LF							
				(2 HR) TYPE 2WK6, GWB SHAFT WALL (90 LF)									
1179				(2x6) Wood studs at 16" O.C	1236	LF							
1180				(4") Batt insulation	1620	SF							
1181	A1-11A TO ID-7.3			(5/8", 1-Layer) Type X, GYP. BD. both side	1620	SF							
1182				(1" 1-Layer) Type X, GYP. Liner panel both side	1620	SF							
1183				(2x6) Top and bottom track.	540	LF							
				(1 HR) EXTERIOR WALL (1485 LF)									
1184				(2x6) Wood studs at 16" O.C	11180	LF							
1185	A1-11A TO ID-7.3			(R-20) Batt insulation.	9490	SF							
1186				(5/8", 1-Layer) Typ X, GYP. BD. One side.	9490	SF							
1187				(5/8", 1-Layer) Type X, Exterior Plywood sheathing one side.	9490	SF							
1188				(2x6) Top and bottom track.	4455	LF							
093100				CERAMIC / PORCELAIN TILING									
1189	A1-11A TO ID-7.3			porcelain wall tile.	1825	SF							
1190				Type WT-20, Wall tile.	525	SF							
1191				Kitchen backsplash wall tile.	660	SF							
096000				FLOORING									
1192	A1-11A TO ID-7.3			Carpet floor.	10850	SF							
1193				Vinyl wood plank w/ sound mat floor.	20235	SF							
1194				Type LVT3, Luxury vinyl.	585	SF							
1195				Type SC-1, Sealed concrete floor.	50	SF							
1196				Floor tile.	735	SF							
1197				WV-1, Woven vinyl floor.	615	SF							
1198				Wood base painted.	10690	LF							
1199				(1"x10") Type WB-1 Wood base painted PT-2.	495	LF							
1200				(8" H) Type TB-3, Tile base.	60	LF							
1201				Type RB-1, Rubber base.	35	LF							
1202				Type WD-17, 2x2 Wood wall trim, Stained.	1230	LF							
1203				Type WD-19, 2x6 Wood wall trim, Stained.	110	LF							
099100				PAINTING									
1204	A1-11A TO ID-7.3			6" Wood plank .P-1, T1-11 Painted Ceiling.	325	SF							
1205				Type WP-2, Wood plank, stained Ceiling.	610	SF							
1206				GWB ceiling paint.	35210	SF							
1207				GWB wall paint.	112535	SF							
1208				Door paint. (313 EA)	17535	SF							
				Subtotal									
100000				DIVISION 10 - SPECIALTIES									
101510				TOILET COMPARTMENTS									
1209	A1-11A TO ID-7.3			Compartment wall. (6' H)	145	LF							
102813				TOILET AND BATH ACCESSORIES									
1210	A1-11A TO ID-7.3			Mirror.	51	EA							
1211				Toilet paper holder.	51	EA							
1212				Tower bar.	51	EA							
1213				(36"x60") Tub	40	EA							
				Subtotal									
110000				DIVISION 11 - EQUIPMENT									
1214	A1-11A TO ID-7.3			Dishwasher.	49	EA							
1215				Range & Microwave.	49	EA							
1216				Refrigerator	49	EA							
1217				Dryer	49	EA							
1218				Washer	49	EA							
				Subtotal									
120000				DIVISION 12 - FURNISHING									
123660				QUARTZ SURFACING COUNTERTOPS									
1219				QUARTZ COUNTER TOP - MSI SURFACES - MANHATTAN GRAY 3CM - POLISHED	2449	SF							
				Subtotal									
150000				DIVISION 15 - HEATING, VENTILATING, AND AIR- CONDITIONING (HVAC)									
1220				- FC 1-5-3 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 1- 5-3, Manuf: CARRIER, FE4A/25HCE (800CFM)	1	EA							
1221				EF 1-1-4 - Exhaust fan, Manuf: Broan, Model: AE80, 80 CFM	1	EA							
1222				EF 1-1-5 - Exhaust fan, Manuf: Broan, Model: AE80, 80 CFM	1	EA							
1223				EH 1-1-4 - ELECTRIC HEATER, MANUF: MARLEY, MODEL NO: AWH (100 CFM)	1	EA							
1224				EW C-1 - ELECTRIC WATER COOLER	1	EA							
1225				FC 1-1-10 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 1- 1-10, Manuf: CARRIER, FE4A/25HCE (1600CFM)	1	EA							
1226				FC 1-1-11 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 1- 1-11, Manuf: CARRIER, FE4A/25HCE (600CFM)	1	EA							
1227				FC 1-1-8 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 1-1- 8, Manuf: CARRIER, FE4A/25HCE (1600CFM)	1	EA							
1228				FC 1-1-9 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 1-1- 9, Manuf: CARRIER, FE4A/25HCE (1600CFM)	1	EA							
1229				FC 1-2-3 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 1-2- 3, Manuf: CARRIER, FE4A/25HCE (800CFM)	1	EA							
1230				FC 1-3-3 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 1-3- 3, Manuf: CARRIER, FE4A/25HCE (800CFM)	1	EA							
1231				FC 1-4-3 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 1-4- 3, Manuf: CARRIER, FE4A/25HCE (800CFM)	1	EA							
1232				Fire damper	5	EA							
1233				NFWH - NON-FREEZE EXTERIOR WALL HYDRANT, (3/4") CAST BRONZE HYDRANT, RECESSED W/ STAINLESS STEEL BOX, VACCUUM BREAKER, NICKEL BRONZE - JAY R. SMITH FIGURE 5509-QT	1	EA							
1234				NFWH - NON-FREEZE EXTERIOR WALL HYDRANT, (3/4") CAST BRONZE HYDRANT, RECESSED W/ STAINLESS STEEL BOX, VACCUUM BREAKER, NICKEL BRONZE - JAY R. SMITH FIGURE 5509-QT	1	EA							
1235	M1-11A TO MP1-21			NON-FREEZE WALL HYDRANT, ROOF MOUNT PEDESTAL W/ MOUNTING FLANGE & SHROUD, MALE HOSE END OUTLET W/ DUAL CHECK BACKFLOW PREVENTER, (3/4") INLET W/ SELF DRAINING VENTURI - WOODFORD MODEL SRH-MS	1	EA							

[illegible]

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHrs/ Unit	\$/Hour	(\$Per Unit)				
1304				(3") VENT PIPE	489	LF							
				Subtotal									
			160000	DIVISION 16 - ELECTRICAL									
				LIGHT FIXTURE									
1305				A1 - 6" SURFACE MOUNT LED DOWNLIGHT - MANUF: HALO, MODEL: SLD 1200 SERIES / SLD612835WH/80 CRI/3500K/WHITE	55	EA							
1306				B1 - UNIT ENTRY SCONE - MANUF: SAVOY HOUSE, MODEL: 9-0901-1-89/GLENN 1-LIGHT WALL SCONE / 7"WX12"HX9"D/E26 8W 120V LED BULB (1 PER FIXTURE) / MATTE BLACK FINISH	38	EA							
1307				EM - EMERGENCY FIXTURE LIGHT - SEALED NICKEL CADMIUM BATTERY, CIRCULAR HEAD, DAMP LOCATION LISTED, W/ BATTERY CAPACITY TO POWER REMOTE HEAD, MANUF: SURE LITES SEL50 SERIES LITHONIA	28	EA							
1308				EMR1 - REMOTE HEAD, PAIRED W/ EMERGENCY FIXTURE OR EXIT SIGN, SINGLE HEAD, MANUF: SURE LITES SRP SERIES	1	EA							
1309				S1 - 4' LED STRIP LIGHT - METALUX SNLED SERIES, LITHONIA	25	EA							
1310				S3 - 4' SURFACE/WALL MOUNTED LED FIXTURE, INTEGRAL OCCUPANCY SENSOR W/ 0-10V DIMMING, STEP DIMMING, HIGH LUMEN OUTPUT, INTEGRAL 14W BATTERY PACK, MANUF: METALUX SWLED SERIES LITHONIA	15	EA							
1311				X1 - EXIT SIGN, LED LAMP, POLYCARBONATE HOUSING, SELF CONTAINED BATTERY, MODEL: SURE LITES LPX SERIES LITHONIA	24	EA							
1312				D - 7" SURFACE MOUNTED LED FIXTURE - MANUF: SATCO - S29331 / 7" FLUSH MOUNT LED FIXTURE - ROUND /120V	281	EA							
1313				F - 50" CEILING FAN W/ LED LIGHT KIT - MANUF: CASK INDUSTRIES - CF104/4-BLADE/50"WX19.5"H	88	EA							
1314	E1-11A TO EP1-32			P - ISLAND PENDANT - MANUF: KUZCO LIGHTING - MODEL: VANDERBILT 493210-WH/GD/10"DIA X 12"H / 120" MAX CORD LENGTH	88	EA							
1315				VA - VANITY SCOSCE - MANUF: QUORUM INTERNATIONAL - MODEL: 507-3-6980/EP5Y 3-LIGHT VANITY / 9.25"H X23.5"W X 7"D / 100W MAX WATTAGE	87	EA							
1316				W - EXTERIOR SCONE - MANUF: QUORUM INTERNATIONAL - MODEL: 730-69/TORREY SM LANTERN - NR/13.75"H X 7.5"W X 14.75"D / 100W MAX	38	EA							
				LIGHTING CONTROLS									
1317				OCCUPANCY SENSOR SWITCH	6	EA							
1318				3-WAY SWITCH	168	EA							
1319				SINGLE TOGGLE SWITCH	490	EA							
				RECEPTACLES & SWITCHES									
1320				DUPLEX RECEPTACLE	542	EA							
1321				DUPLEX RECEPTACLE	20	EA							
1322				GFI DUPLEX RECEPTACLE	387	EA							
1323				GFI RECEPTACLE WEATHER PROOF	42	EA							
1324				TWO WAY COMMUNICATION BASE STATION	1	EA							
1325				240 VOLT RECEPTACLE	76	EA							
1326				COMBINATION DATA/ TELE OUTLET	176	EA							
1327				JUNCTION BOX	76	EA							
1328				SPLIT DUPLEX RECEPTACLE	38	EA							
1329				TELEVISION OUTLET	88	EA							
1330				USB DUPLEX RECEPTACLE	106	EA							
1331				USB GFI DUPLEX RECEPTACLE	29	EA							
				DISCONNECT SWITCHES									
1332				SERVICE DISCONNECT "DC"	1	EA							
				LOW VOLTAGE & OTHER ELECTRICAL DEVICES									
1333				CT ENCLOSURE & KWH METER	1	EA							
1334				METERCENTER MAIN	2	EA							
1335				ELECTRIC WIRING	1	LS							
				ELECTRIC BREAKER									
1336				ELECTRIC BREAKER - 1P 20A	534	EA							
1337				ELECTRIC BREAKER - 2P 30A	74	EA							
1338				ELECTRIC BREAKER - 2P 50A	30	EA							
				ELECTRIC PANEL									
1339				LOAD CENTER - 125A MLO 1PHASE 3W	46	EA							
1340				SWITCHBOARD "MS11" - 4000.0A MCB 3PHASE 4W	1	EA							
1341				DISTRIBUTION PANEL "DC" - 1200.0A MLO 3PHASE 4W	1	EA							
1342				ELECTRIC PANEL "C2" - 400A MLO 3PHASE 4W	1	EA							
				ELECTRIC PANEL "C4" - 200A MLO 3PHASE 4W		EA							
				FIRE ALARM									
1343				FIRE ALARM STROBE (CANDELAS)	4	EA							
1344				FIRE ALARM CONTROL PANEL	1	EA							
1345				FIRE ALARM DOOR HOLDER	2	EA							
1346				FIRE ALARM DOOR HOLDER	9	EA							
1347				FIRE ALARM HORN W/STROBE (CANDELAS)	4	EA							
1348				FIRE ALARM HORN W/STROBE (CANDELAS)	13	EA							
1349				FIRE ALARM PULL STATION	2	EA							
1350				FIRE ALARM PULL STATION	4	EA							
1351				SMOKE DETECTOR	2	EA							
1352				SMOKE DETECTOR	13	EA							
1353				SPRINKLER FLOW SWITCH	4	EA							
1354				SPRINKLER VALVE TAMPER SWITCH	4	EA							
1355				120V, SELF CONTAINED AUDIBLE CARBON MONOXIDE SMOKE ALARM	58	EA							
1356				120V, SELF CONTAINED AUDIBLE SMOKE ALARM	50	EA							
1357				FIRE ALARM MINI HORN (CANDELAS)	81	EA							
1358				FIRE ALARM MINI HORN W/ STROBE (CANDELAS)	4	EA							
				Subtotal									
				BUILDING 1000 D									
			020000	DIVISION 02 - EXISTING CONDITIONS									
			022000	EARTHWORK									
1359	S1-11D to S1-12D	S0-01, S3-01 & S3-02		Footing excavation.	25515	CF							
1360				Footing backfill.	15760	CF							
				Subtotal									
			030000	DIVISION 03 - CONCRETE									
			033000	CAST IN PLACE CONCRETE									
				(2'Wx1'8"H) CONCRETE FOOTING									
1361	S1-11D to S1-12D	S0-01, S3-01 & S3-02		Compaction of sub-grade.	3155	SF							
1362				Rebar's (Grade 60)	6730	LB							
1363				Concrete footing. (F'c = 3000 PSI)	4205	CF							
				(2'Wx2'2"H) CONCRETE FOOTING									
1364	S1-11D to S1-12D	S0-01, S3-01 & S3-02		Compaction of sub-grade.	1110	SF							
1365				Rebar's (Grade 60)	3070	LB							

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHrs/ Unit	\$/Hour	(\$Per Unit)				
1366				Concrete footing. (fc = 3000 PSI) (1'Wx8"H) CONCRETE FOOTING	1920	CF							
1367	S1-11D to S1-12D	S0-01, S3-01 & S3-02		Compaction of sub-grade.	320	SF							
1368				Rebar's (Grade 60)	235	LB							
1369				Concrete footing. (fc = 3000 PSI)	145	CF							
1370	S1-11D to S1-12D	S0-01, S3-01 & S3-02		ELEVATOR PIT CONCRETE FOOTING PAD									
1371				Compaction of sub-grade.	90	SF							
1372				Rebar's (Grade 60)	280	LB							
				(12" THK) Concrete footing. (fc = 3000 PSI)	90	CF							
1373	S1-11D to S1-12D	S0-01, S3-01 & S3-02		(5'Wx12"H) RETAINING WALL CONCRETE FOOTING									
1374				Compaction of sub-grade.	1410	SF							
1375				Rebar's (Grade 60)	2400	LB							
				Concrete footing. (fc = 3000 PSI)	1500	CF							
1376	S1-11D to S1-12D	S0-01, S3-01 & S3-02		RETAINING WALL									
1377				Rebar's (Grade 60)	4505	LB							
				(12" THK) Concrete wall. (fc = 5000 PSI)	2815	CF							
1378	S1-11D to S1-12D	S0-01, S3-01 & S3-02		CONCRETE WALL									
1379				Rebar's (Grade 60)	285	LB							
				(8" THK) Concrete wall. (fc = 5000 PSI)	125	CF							
1380	S1-11D to S1-12D	S0-01, S3-01 & S3-02		SLAB ON GRADE									
1381				Compaction of sub-grade.	12000	SF							
1382				(10 MIL) Vapor barrier.	12000	SF							
				(4" Thick) Reinforced concrete slab w/ post tensioning. (fc = 3000 PSI)	12000	SF							
1383	S1-11D to S1-12D	S0-01, S3-01 & S3-02		SLAB ON GRADE									
1384				Compaction of sub-grade.	865	SF							
1385				(10 MIL) Vapor barrier.	865	SF							
				(4" Thick) Concrete slab w/ CIP 6x6 - 10/10 WWM. (fc = 3000 PSI)	865	SF							
1386	S1-12D to S1-15D			Metal pan concrete stair.	300	SF							
				Subtotal									
			040000	DIVISION 04 - MASONRY									
			042000	UNIT MASONRY									
1387	A1-11A TO ID-7.3			Exterior Type BR-1, Brick Veneer-Gray.	1420	SF							
				Subtotal									
			050000	DIVISION 05 - METAL									
			057000	ORNAMENTAL METAL									
1388	A1-11A TO ID-7.3			Hand rail	180	LF							
1389				Type-MR-1, 42" Aluminum picket railing.	850	LF							
				Subtotal									
			060000	DIVISION 06 - WOOD, PLASTIC AND COMPOSITES									
			061053	WOOD FRAMING									
1390	S1-12A to S1-16D			(2x8) Header beam.	1045	LF							
1391				(2x10) Header beam.	1060	LF							
1392				5.5x11.25 GL	445	LF							
1393				5.5x14 GL	70	LF							
1394				5.5x18 GL	175	LF							
1395				7x18 GL	105	LF							
1396				5.25x11.25 PSL	100	LF							
1397				Pre-Fabricated wood floor trusses	22710	LF							
1398				Pre-Engineered Roof Trusses	6305	LF							
1399				(2x12) Canopy SCAB	850	LF							
1400				(2x12) Roof joist.	70	LF							
1401				Joist hanger.	4114	EA							
			061000	ROUGH CARPENTRY									
1402	S1-12A to S1-16D			(3/4") T&G OSB or Plywood sheathing.	45250	SF							
1403	A1-11A TO ID-7.3			(5/8") Exterior grade OSB or Plywood sheathing.	13235	SF							
1404				SHEARWALL									
				(5/8", 1-Layer) Plywood sheathing.	16335	SF							
			064100	ARCHITECTURAL WOOD CASEWORK									
1405	A1-11A TO ID-7.3			(12" W) Road & Shelf.	1430	LF							
1406				(11'3"Lx1Dx2'6"H) Wall cabinet.	5	EA							
1407				(12'Lx1Dx2'6"H) Wall cabinet.	4	EA							
1408				(11'2"Lx1Dx2'6"H) Wall cabinet.	5	EA							
1409				Unit B2- (13'6"Lx1Dx2'6"H) Wall cabinet.	8	EA							
1410				(12'Lx2'Dx2'10"H) Base cabinet.	20	EA							
1411				(6'Lx2'Dx2'10"H) Base cabinet.	86	EA							
1412				(8'8"Lx2Dx2'10"H) Base cabinet.	10	EA							
1413				(12'Lx1Dx2'6"H) Base cabinet.	13	EA							
1414				(9'8"Lx2Dx2'10"H) Base cabinet.	13	EA							
1415				(11'9"Lx2Dx2'10"H) Base cabinet.	4	EA							
1416				(4'Lx2Dx2'10"H) Base cabinet.	6	EA							
1417				(8'Lx2Dx2'10"H) Base cabinet.	5	EA							
1418				Unit B2- (11'Lx2Dx2'10"H) Base cabinet.	8	EA							
1419				(4'6"Lx2Dx2'10"H) Base cabinet.	3	EA							
1420				(6'6"Lx2Dx2'10"H) Base cabinet.	7	EA							
1421				(8'8"Lx1Dx2'6"H) Wall cabinet.	4	EA							
1422				(9'Lx2Dx2'10"H) Base cabinet.	4	EA							
1423				16" Mud bench	68	EA							
1424				Cabinet.	105	EA							
				Subtotal									
			070000	DIVISION 07 - THERMAL AND MOISTURE PROTECTION									
1425	A2-10			ROOFING									
1426	A1-11A TO ID-7.3			(R-38) Roof insulation.	13235	SF							
1427				(60 MIL) TPO Roofing.	13235	SF							
1428				Walking pad.	570	SF							
			076000	SHEET METAL FLASHING AND TRIM									
1429	A1-11A TO ID-7.3			Downspout	260	LF							
1430				Gutter	520	LF							
				Subtotal									
			080000	DIVISION 08 - OPENING									
			080152	WOOD WINDOWS									
1431	A1-11A TO ID-7.3			Type W 01, (2'-6" W x 6'-0" H) Single vinyl window.	8	EA							
1432				Type W 02, (3'-0" W x 6'-0" H) Single vinyl window.	3	EA							
1433				Type W 03, (5'-0" W x 6'-0" H) Single vinyl window.	20	EA							
1434				Type W 04, (6'-0" W x 6'-0" H) Single vinyl window.	308	EA							
			081113	HOLLOW METAL DOORS, FRAMES AND HARDWARE									
1435	A1-11A TO ID-7.3			(4)x (HR 45 MIN)(3'-0" W x 7'-0" H) HM door & frame.	16	EA							
1436				(4)x (HR 90 MIN)(3'-0" W x 7'-0" H) HM door & frame.	8	EA							
			082100	WOOD DOORS									
1437				(3'-0" W x 8'-0" H) Fiberglass door & frame.	44	EA							

#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHRS/ UNIT	\$/HOUR	(\$Per Unit)				
1438	A1-11A TO ID-7.3			(HR 90 MIN) (6'-0" W x 7'-0" H) Fiberglass door & frame.	4	EA							
1439				(2'-10" W x 6'-8" H) Solid core wood door & frame.	300	EA							
1440				(2'-6" W x 6'-8" H) Solid core wood door & frame.	11	EA							
1441				(HR 20 MIN) (3'-0" W x 7'-0" H) Solid core wood door & frame.	49	EA							
1442				(3'-0" W x 6'-8" H) Solid core wood door & frame.	14	EA							
1443				(2'-0" W x 6'-8" H) Hollow core wood door & frame.	10	EA							
1444				(5'-0" W x 6'-8" H) Hollow core wood door & frame.	17	EA							
1445				(1'-6" W x 6'-8" H) Hollow core wood door & frame.	4	EA							
1446				(2'-6" W x 6'-8" H) Hollow core wood door & frame.	3	EA							
1447	A1-11A TO ID-7.3			Door hardware. (480 EA)	1	LS							
				Subtotal									
			090000	DIVISION 09 - FINISHES									
1448	A1-11A TO ID-7.3			Exterior Type CP-1, Fiber cement panel (4"x10") W/ Batters-White Allura.	7350	SF							
1449				Exterior Type CP-2, Fiber cement panel (4"x10") W/ Batters-Dark gray.	5170	SF							
1450				Exterior Type CP-3,Fiber cement panel (4"x10") W/ Metal Reveals White.	495	SF							
1451				Exterior Type WP-1, Wall panel.	1835	SF							
1452				Exterior Type CT-1, (12" H)	820	LF							
1453				Exterior Type CT-1, (23" H)	80	LF							
1454				Exterior Type CT-1, (4" H)	280	LF							
			092600	GYPSUM BOARD ASSEMBLIES									
1455	A1-11A TO ID-7.3			5/8" GWB ceiling.	47510	SF							
				INTERIOR WALLS									
	A1-11A TO ID-7.3			(1 HR) TYPE 1WB4, GWB UNIT WALL (4555 LF)									
1456				(2x4) Wood studs at 16" O.C	30832	LF							
1457				(5/8", 1-Layer) Type X, GYP. BD. both side	81990	SF							
1458				(2x4) Top and bottom track.	13665	LF							
1459	A1-11A TO ID-7.3			(1 HR) TYPE 1WB6, GWB UNIT WALL (716 LF)									
1460				(2x6) Wood studs at 16" O.C	4854	LF							
1461				(5/8", 1-Layer) Type X, GYP. BD. both side	12888	SF							
				(2x6) Top and bottom track.	2148	LF							
1462	A1-11A TO ID-7.3			(1 HR) TYPE 1WC4, GWB WALL (100 LF)									
1463				(2x4) Wood studs at 16" O.C	686	LF							
1464				(1/2") Resilient channel	686	LF							
1465				(4") Batt insulation	900	SF							
1466				(5/8", 1-Layer) Type X, GYP. BD. One side	900	SF							
1467				(5/8", 1-Layer) Type X, Exterior grade GYP. BD. One side	900	SF							
1468				(2x4) Top and bottom track.	300	LF							
				(1/2") Top and bottom track.	200	LF							
1469	A1-11A TO ID-7.3			(1 HR) TYPE 1WC6, GWB WALL (1715 LF)									
1470				(2x6) Wood studs at 16" O.C	11614	LF							
1471				(1/2") Resilient channel	11614	LF							
1472				(6") Batt insulation	15435	SF							
1473				(5/8", 1-Layer) Type X, GYP. BD. One side	15435	SF							
1474				(5/8", 1-Layer) Type X, Exterior grade GYP. BD. One side	15435	SF							
1475				(2x6) Top and bottom track.	5145	LF							
				(1/2") Top and bottom track.	3430	LF							
1476	A1-11A TO ID-7.3			(1 HR) TYPE 1WD4, GWB UNIT SEP. WALL (2325 LF)									
1477				(2x4) Wood studs at 16" O.C	15745	LF							
1478				(4") Batt insulation	41850	SF							
1479				(5/8", 1-Layer) Type X, GYP. BD. both side	41850	SF							
				(2x4) Top and bottom track.	6975	LF							
1480	A1-11A TO ID-7.3			(1 HR) TYPE 1WD6, GWB UNIT SEP. WALL (570 LF)									
1481				(2x6) Wood studs at 16" O.C	3867	LF							
1482				(6") Batt insulation	10260	SF							
1483				(5/8", 1-Layer) Type X, GYP. BD. both side	10260	SF							
				(2x6) Top and bottom track.	1710	LF							
1484	A1-11A TO ID-7.3			(2 HR) TYPE 2WK4, GWB SHAFT WALL (495 LF)									
1485				(2x4) Wood studs at 16" O.C	6717	LF							
1486				(4") Batt insulation	8910	SF							
1487				(5/8", 1-Layer) Type X, GYP. BD. both side	8910	SF							
1488				(1", 1-Layer) Type X, GYP. Liner panel both side	8910	SF							
				(2x4) Top and bottom track.	2970	LF							
1489	A1-11A TO ID-7.3			(2 HR) TYPE 2WK6, GWB SHAFT WALL (155 LF)									
1490				(2x6) Wood studs at 16" O.C	2116	LF							
1491				(4") Batt insulation	2790	SF							
1492				(5/8", 1-Layer) Type X, GYP. BD. both side	2790	SF							
1493				(1", 1-Layer) Type X, GYP. Liner panel both side	2790	SF							
				(2x6) Top and bottom track.	930	LF							
1494	A1-11A TO ID-7.3			(1 HR) EXTERIOR WALL (1855 LF)									
1495				(2x6) Wood studs at 16" O.C	12562	LF							
1496				(R-20) Batt insulation.	5395	SF							
1497				(5/8", 1-Layer) Typ X, GYP. BD. One side.	5395	SF							
1498				(5/8", 1-Layer) Type X, Exterior Plywood sheathing one side.	5395	SF							
				(2x6) Top and bottom track.	5565	LF							
			093100	CERAMIC / PORCELAIN TILING									
1499	A1-11A TO ID-7.3			porcelain wall tile.	2725	SF							
1500				Kitchen backsplash wall tile.	880	SF							
			096000	FLOORING									
1501	A1-11A TO ID-7.3			Carpet floor.	11510	SF							
1502				Vinyl wood plank w/ sound mat floor.	26090	SF							
1503				Wood base painted.	14620	LF							
			099100	PAINTING									
1504	A1-11A TO ID-7.3			GWB ceiling paint.	47510	SF							
1505				GWB wall paint.	139400	SF							
1506				Door paint. (480 EA)	21710	SF							
				Subtotal									
			100000	DIVISION 10 - SPECIALTIES									
			101510	TOILET COMPARTMENTS									
1507	A1-11A TO ID-7.3			Compartment wall. (6' H)	265	LF							
				TOILET AND BATH ACCESSORIES									
1508	A1-11A TO ID-7.3			Mirror.	66	EA							
1509				Toilet paper holder.	66	EA							
1510				Tower bar.	66	EA							
1511				(36"x60") Tub	45	EA							
				Subtotal									
			110000	DIVISION 11 - EQUIPMENT									
1512	A1-11A TO			Dishwasher.	49	EA							
1513				Range & Microwave.	49	EA							

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHrs/ Unit	\$/Hour	(\$Per Unit)				
1514	ID-7.3			Refrigerator	49	EA							
1515				Dryer	49	EA							
1516				Washer	49	EA							
				Subtotal									
			120000	DIVISION 12 - FURNISHING									
			123660	QUARTZ SURFACING COUNTERTOPS									
1517				QUARTZ COUNTER TOP - MSI SURFACES - MANHATTAN GRAY 3CM - POLISHED	3085	SF							
				Subtotal									
			150000	DIVISION 15 - HEATING, VENTILATING, AND AIR-CONDITIONING (HVAC)									
1518	M1-11A TO MP1-21			- FC 1-5-4 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 1-5-4, Manuf: CARRIER, FE4A/25HCE (800CFM)	1	EA							
1519				ESP-1 - PUMP - MODEL: STANCO OIL MINDER SYSTEM W/ ALARM & REMOTE MONITORING CIRCUIT	1	EA							
1520				FC 1-1-12 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 1-1-12, Manuf: CARRIER, FE4A/25HCE (800CFM)	1	EA							
1521				FC 1-2-4 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 1-2-4, Manuf: CARRIER, FE4A/25HCE (800CFM)	1	EA							
1522				FC 1-3-4 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 1-3-4, Manuf: CARRIER, FE4A/25HCE (800CFM)	1	EA							
1523				FC 1-4-4 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 1-4-4, Manuf: CARRIER, FE4A/25HCE (800CFM)	1	EA							
1524				Fire damper	5	EA							
1525				NFWH - NON-FREEZE EXTERIOR WALL HYDRANT, (3/4") CAST BRONZE HYDRANT, RECESSED W/ STAINLESS STEEL BOX, VACCUUM BREAKER, NICKEL BRONZE - JAY R. SMITH FIGURE 5509-QT	1	EA							
1526				NON-FREEZE WALL HYDRANT, ROOF MOUNT PEDESTAL W/ MOUNTING FLANGE & SHROUD, MALE HOSE END OUTLET W/ DUAL CHECK BACKFLOW PREVENTER, (3/4") INLET W/ SELF DRAINING VENTURI - WOODFORD MODEL SRH-MS	2	EA							
1527				RG2 - (20"X18") Return grille - Manuf: Titus, Model: 355RS, Steel	5	EA							
1528				SG16 - (14x8) Supply grille - Manuf: Titus, Model: 301RS, Steel (200 CFM) w/ Radiation damper	20	EA							
1529				EF A - EXHAUST FAN - MANUF: BROAN, MODEL: 670, (50 CFM)	66	EA							
1530				FC A2 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP A2, Manuf: CARRIER, FFMA/25HCE (600CFM)	10	EA							
1531				FC A4 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP A4, Manuf: CARRIER, FFMA/25HCE (600CFM)	5	EA							
1532				FC A5 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP A5, Manuf: CARRIER, FFMA/25HCE (600CFM)	13	EA							
1533				FC A7 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP A7, Manuf: CARRIER, FFMA/25HCE (800CFM)	4	EA							
1534				FC B1 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP B1, Manuf: CARRIER, FFMA/25HCE (600CFM)	5	EA							
1535				FC B2 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP B2, Manuf: CARRIER, FFMA/25HCE (800CFM)	8	EA							
1536				FC C1 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP C1, Manuf: CARRIER, FFMA/25HCE (1200CFM)	3	EA							
1537				FC C1-HC - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP C1-HC, Manuf: CARRIER, FFMA/25HCE (1200CFM)	1	EA							
1538				Radiation damper	341	EA							
1539				RG2 - (16"X10") Return grille - Manuf: Titus, Model: 355RS	16	EA							
1540				RG2 - (36"X10") Return grille - Manuf: Titus, Model: 355RS	22	EA							
1541				RG2 - (36"X12") Return grille - Manuf: Titus, Model: 355RS	12	EA							
1542				RG3 - (16"X10") Return grille - Manuf: Titus, Model: 350RL	62	EA							
1543				RG3 - (36"X10") Return grille - Manuf: Titus, Model: 350RL	15	EA							
1544				SG16 - (14x8) Supply grille - Manuf: Titus, Model: 301RS, Steel	21	EA							
1545				SG16 - (8x6) Supply grille - Manuf: Titus, Model: 301RS, Steel	124	EA							
	M1-11A TO MP1-21			Galvanized sheet metal duct w/ Wrap equal to ownes corning fiberglass w/ FRK vapor barrier. Insulation shall be R-6 except on roof shall be R-8.									
1546				(12X12) Metal duct	43	LF							
1547				(12X10) Metal duct	209	LF							
1548				(14X10) Metal duct	72	LF							
1549				(14X12) Metal duct	22	LF							
				ROUND DUCT									
1550				(8"Dia) ROUND DUCT	10	LF							
1551				(8"Dia) Round duct	115	LF							
1552				(4"Dia) Round duct	2910	LF							
				FLEXIBLE ROUND DUCT									
1553				(8"Dia) Flexible round duct	910	LF							
1554				(4"Dia) Flexible Round duct	386	LF							
1555				(5"Dia) Flexible Round duct	536	LF							
1556				(7"Dia) Flexible Round duct	1114	LF							
1557				(8"Dia) Flexible Round duct	2601	LF							
				Subtotal									
			150000	DIVISION 15 - PLUMBING									
1558	P1-11A TO P3-08			FCO - FLOOR CLEANOUT - CAST IRON CLEANOUT W/ GSKET SEAL & THREADED PLUG, ADJUSTABLE CAST IRON ROUND TOP W/ SECURING SCREW - JAY R. SMITH FIGURE 4220	5	EA							
1559				(2") HUB DRAIN W/ PRIMER CONNECTION	44	EA							
1560					44	EA							
1561				IM-1 - ICE MAKER OUTLET BOX: ABS, LEAD FREE W/ QUARTER TURN BALL VALVE & WATER HAMMER ARRESTOR - SIOUX CHIEF 696-G1010	44	EA							
1562				KS-1 - KITCHEN SINK - RESIDENTIAL	44	EA							
1563				LAV-1 - LAVATORY - RESIDENTIAL	98	EA							
1564				SH-1 - SHOWER - RESIDENTIAL W/ SHOWER HEAD	45	EA							
1565				SHUTT-OFF VALVE	44	EA							
1566				WATER SUBMETER	44	EA							
1567				WC-1 - WATER CLOSET - RESIDENTIAL	56	EA							
1568					32	EA							
1569				WH-2 - WATER HEATER - MODEL: ENLB-50 - 48 GAL, W/ T&P RELIEF VALVE, VACCUUM RELIEF VALVE & WATTS LFBVRV COMBINATION BALL & THERMAL RELIEF VALVE, A.O SMITH - PROLINE SERIES	12	EA							
1570				WM-1 - WASHING MACHINE OUTLET BOX, ABS, LEAD FREE W/ QUARTER TURN BALL VALVE, WATER HAMMER ARRESSTOR - SIOUX CHIEF 696-G1010 SERIES	44	EA							

[illegible]

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHrs/ Unit	S/Hour	(\$*er Unit)				
1708	A1-11A TO ID-7.3			Walking pad.	325	LF							
1709				Air/Moisture barrier.	16975	SF							
076000				SHEET METAL FLASHING AND TRIM									
1710	A1-11A TO ID-7.3			Downspout.	90	LF							
1711				Gutter	485	LF							
				Subtotal									
080000				DIVISION 08 - OPENING									
080152				WOOD WINDOWS									
1712	A1-11A TO ID-7.3			Type W 01, (2'-6" W x 6'-0" H) Single vinyl window.	8	EA							
1713				Type W 02, (3'-0" W x 6'-0" H) Single vinyl window.	4	EA							
1714				Type W 03, (5'-0" W x 6'-0" H) Single vinyl window.	14	EA							
1715				Type W 04, (6'-0" W x 6'-0" H) Single vinyl window.	74	EA							
081113				HOLLOW METAL DOORS, FRAMES AND HARDWARE									
1716	A1-11A TO ID-7.3			(HR 45 MIN) (3'-0" W x 7'-0" H) HM door & frame.	20	EA							
1717				(HR 90 MIN) (3'-0" W x 7'-0" H) HM door & frame.	5	EA							
082100				WOOD DOORS									
1718	A1-11A TO ID-7.3			(3'-0" W x 8'-0" H) Fiberglass door & frame.	2	EA							
1719				(3'-0" W x 8'-0" H) Fiberglass door & frame.	36	EA							
1720				(2'-10" W x 6'-8" H) Solid core wood door & frame.	203	EA							
1721				(2'-6" W x 6'-8" H) Solid core wood door & frame.	13	EA							
1722				(HR 20 MIN) (3'-0" W x 7'-0" H) Solid core wood door & frame.	38	EA							
1723				(3'-0" W x 6'-8" H) Solid core wood door & frame.	47	EA							
1724				(1'-6" W x 6'-8" H) Hollow core wood door & frame.	4	EA							
1725				(5'-0" W x 6'-8" H) Hollow core wood door & frame.	4	EA							
087100				FINISH HARDWARE									
1726	A1-11A TO ID-7.3			Door hardware (372 EA)	1	LS							
				Subtotal									
090000				DIVISION 09 - FINISHES									
1727	A1-11A TO ID-7.3			Exterior Type CP-1, Fiber cement panel (4"x10") W/ Battens-White Allura.	4910	SF							
1728				Exterior Type CP-2, Fiber cement panel (4"x10") W/ Battens-Dark gray.	5810	SF							
1729				Exterior Type CP-3,Fiber cement panel (4"x10") W/ Metal Reveals White.	500	SF							
1730				Exterior Type WP-1, Wall panel.	2435	SF							
1731				(1'2" H) Exterior Type CT-1.	6790	LF							
1732				(2'3" H) Exterior Type CT-1.	80	LF							
092600				GYPSON BOARD ASSEMBLIES									
1733	A1-11A TO ID-7.3			5/8" GWB ceiling.	37660	SF							
				INTERIOR WALLS									
1734	A1-11A TO ID-7.3			(1 HR) TYPE 1WB4, GWB UNIT WALL (4035 LF)									
1735				(2x4) Wood studs at 16" O.C	27314	LF							
1736				(5/8", 1-Layer) Type X, GYP. BD. both side	72630	SF							
				(2x4) Top and bottom track.	12105	LF							
1737	A1-11A TO ID-7.3			(1 HR) TYPE 1WB6, GWB UNIT WALL (4975 LF)									
1738				(2x6) Wood studs at 16" O.C	33674	LF							
1739				(5/8", 1-Layer) Type X, GYP. BD. both side	89550	SF							
				(2x6) Top and bottom track.	14925	LF							
1740	A1-11A TO ID-7.3			(1 HR) TYPE 1WC4, GWB WALL (375 LF)									
1741				(2x4) Wood studs at 16" O.C	2547	LF							
1742				(1/2") Resilient channel	2547	LF							
1743				(4") Batt insulation	3375	SF							
1744				(5/8", 1-Layer) Type X, GYP. BD. One side	3375	SF							
1745				(5/8", 1-Layer) Type X, Exterior grade GYP. BD. One side	3375	SF							
1746				(2x4) Top and bottom track.	1125	LF							
				(1/2") Top and bottom track.	750	LF							
1747	A1-11A TO ID-7.3			(1 HR) TYPE 1WC6, GWB WALL (1085 LF)									
1748				(2x6) Wood studs at 16" O.C	7351	LF							
1749				(1/2") Resilient channel	7351	LF							
1750				(6") Batt insulation	9765	SF							
1751				(5/8", 1-Layer) Type X, GYP. BD. One side	9765	SF							
1752				(5/8", 1-Layer) Type X, Exterior grade GYP. BD. One side	9765	SF							
1753				(2x6) Top and bottom track.	3255	LF							
				(1/2") Top and bottom track.	2170	LF							
1754	A1-11A TO ID-7.3			(1 HR) TYPE 1WD4, GWB UNIT SEP. WALL (1710 LF)									
1755				(2x4) Wood studs at 16" O.C	11590	LF							
1756				(4") Batt insulation	30780	SF							
1757				(5/8", 1-Layer) Type X, GYP. BD. both side	30780	SF							
				(2x4) Top and bottom track.	5130	LF							
1758	A1-11A TO ID-7.3			(1 HR) TYPE 1WD6, GWB UNIT SEP. WALL (350 LF)									
1759				(2x6) Wood studs at 16" O.C	2380	LF							
1760				(6") Batt insulation	6300	SF							
1761				(5/8", 1-Layer) Type X, GYP. BD. both side	6300	SF							
				(2x6) Top and bottom track.	1050	LF							
1762	A1-11A TO ID-7.3			(2 HR) TYPE 2WK4, GWB SHAFT WALL (825 LF)									
1763				(2x4) Wood studs at 16" O.C	11183	LF							
1764				(4") Batt insulation	14850	SF							
1765				(5/8", 1-Layer) Type X, GYP. BD. both side	14850	SF							
1766				(1", 1-Layer) Type X, GYP. Liner panel both side	14850	SF							
				(2x4) Top and bottom track.	4950	LF							
1767	A1-11A TO ID-7.3			(2 HR) TYPE 2WK6, GWB SHAFT WALL (112 LF)									
1768				(2x6) Wood studs at 16" O.C	1534	LF							
1769				(4") Batt insulation	2016	SF							
1770				(5/8", 1-Layer) Type X, GYP. BD. both side	2016	SF							
1771				(1", 1-Layer) Type X, GYP. Liner panel both side	2016	SF							
				(2x6) Top and bottom track.	672	LF							
1772	A1-11A TO ID-7.3			(1 HR) EXTERIOR WALL (1430 LF)									
1773				(2x6) Wood studs at 16" O.C	9686	LF							
1774				(R-20) Batt insulation.	16975	SF							
1775				(5/8", 1-Layer) Typ X, GYP. BD. One side.	16975	SF							
1776				(5/8", 1-Layer) Type X, Exterior Plywood sheathing one side.	16975	SF							
				(2x6) Top and bottom track.	4290	LF							
093100				CERAMIC /PORCELAIN TILING									
1777	A1-11A TO ID-7.3			porcelain wall tile.	2885	SF							
1778				Kitchen backsplash wall tile.	885	SF							
096000				FLOORING									
1779	A1-11A TO ID-7.3			Carpet floor.	8850	SF							
1780				Vinyl wood plank w/ sound mat floor.	20680	SF							
1781				Wood base painted.	11010	LF							
099100				PAINTING									
1782	A1-11A TO ID-7.3			GWB ceiling paint.	37660	SF							
1783				GWB wall paint.	244585	SF							
1784				Door paint. (372 EA)	16800	SF							
				Subtotal									

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHrs/ Unit	\$/Hour	(\$Per Unit)				
			100000	DIVISION 10 - SPECIALTIES									
			101510	TOILET COMPARTMENTS									
1785	A1-11A TO ID-7.3			Compartment wall. (6' H)	210	LF							
			102813	TOILET AND BATH ACCESSORIES									
1786	A1-11A TO ID-7.3			Mirror.	42	EA							
1787				Toilet paper holder.	42	EA							
1788				Towel bar.	42	EA							
1789				(36"x60") Tub	13	EA							
				Subtotal									
			110000	DIVISION 11 - EQUIPMENT									
1790	A1-11A TO ID-7.3			Dishwasher.	35	EA							
1791				Range & Microwave.	35	EA							
1792				Refrigerator	35	EA							
1793				Dryer	35	EA							
1794				Washer	35	EA							
				Subtotal									
			120000	DIVISION 12 - FURNISHING									
			123660	QUARTZ SURFACING COUNTERTOPS									
1795				QUARTZ COUNTER TOP - MSI SURFACES - MANHATTAN GRAY 3CM - POLISHED	2420	SF							
				Subtotal									
			150000	DIVISION 15 - HEATING, VENTILATING, AND AIR-CONDITIONING (HVAC)									
1796	M1-11A TO MP1-21			- FC 1-5-5 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 1-5-5, Manuf: CARRIER, FE4A/25HCE (800CFM)	1	EA							
1797				- RG2 - (20"x14") Return grille - Manuf: Titus, Model: 355RS, Steel	1	EA							
1798				FC 1-1-13 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 1-1-13, Manuf: CARRIER, FE4A/25HCE (800CFM)	1	EA							
1799				FC 1-2-5 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 1-2-5, Manuf: CARRIER, FE4A/25HCE (800CFM)	1	EA							
1800				FC 1-3-5 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 1-3-5, Manuf: CARRIER, FE4A/25HCE (800CFM)	1	EA							
1801				FC 1-4-5 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 1-4-5, Manuf: CARRIER, FE4A/25HCE (800CFM)	1	EA							
1802				Fire damper	4	EA							
1803				NFWH - NON-FREEZE EXTERIOR WALL HYDRANT, (3/4") CAST BRONZE HYDRANT, RECESSED W/ STAINLESS STEEL BOX, VACCUM BREAKER, NICKEL BRONZE - JAY R. SMITH FIGURE 5509-QT	2	EA							
1804				NON-FREEZE WALL HYDRANT, ROOF MOUNT PEDESTAL W/ MOUNTING FLANGE & SHROUD, MALE HOSE END OUTLET W/ DUAL CHECK BACKFLOW PREVENTER, (3/4") INLET W/ SELF DRAINING VENTURI - WOODFORD MODEL SRH-MS	1	EA							
1805				RG2 - (20"x18") Return grille - Manuf: Titus, Model: 355RS, Steel	4	EA							
1806				SG16 - (14x8) Supply grille - Manuf: Titus, Model: 301RS, Steel (200 CFM) w/ Radiation damper	19	EA							
1807				EF A - EXHAUST FAN - MANUF: BROAN, MODEL: 670, (50 CFM)	42	EA							
1808				FC A2 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP A2, Manuf: CARRIER, FFMA/25HCE (600CFM)	9	EA							
1809				FC A4 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP A4, Manuf: CARRIER, FFMA/25HCE (600CFM)	4	EA							
1810				FC A4-HC - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP A4-HC, Manuf: CARRIER, FFMA/25HCE (600CFM)	1	EA							
1811				FC A5 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP A5, Manuf: CARRIER, FFMA/25HCE (600CFM)	4	EA							
1812				FC A6 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP A6, Manuf: CARRIER, FFMA/25HCE (800CFM)	8	EA							
1813				FC A7 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP A7, Manuf: CARRIER, FFMA/25HCE (800CFM)	8	EA							
1814				FC C1 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP C1, Manuf: CARRIER, FFMA/25HCE (1200CFM)	4	EA							
1815				Radiation damper	236	EA							
1816				SG16 - (14x8) Supply grille - Manuf: Titus, Model: 301RS, Steel (200 CFM)	122	EA							
1817				SG16 - (8x6) Supply grille - Manuf: Titus, Model: 301RS, Steel	76	EA							
1818				RG2 - (16"x10") Return grille - Manuf: Titus, Model: 355RS	24	EA							
1819				RG2 - (36"x10") Return grille - Manuf: Titus, Model: 355RS	20	EA							
1820				RG2 - (36"x12") Return grille - Manuf: Titus, Model: 355RS	4	EA							
1821				RG3 - (16"x10") Return grille - Manuf: Titus, Model: 350RL	34	EA							
1822				RG3 - (36"x10") Return grille - Manuf: Titus, Model: 350RL	9	EA							
1823				RG3 - (36"x10") Return grille - Manuf: Titus, Model: 350RL	4	EA							
1824				RG3 - (36"x12") Return grille - Manuf: Titus, Model: 350RL	1	EA							
1825	M1-11A TO MP1-21			Galvanized sheet metal duct w/ Wrap equal to owens corning fiberglass w/ FRK vapor barrier. Insulation shall be R-6 except on roof shall be R-8.									
1826				(12X12) Metal duct	48	LF							
1827				(12X4) Metal duct	50	LF							
1827				(12X10) Metal duct	10	LF							
1828				(12X10) Metal duct	214	LF							
1829				(14X12) Metal duct	21	LF							
1830				ROUND DUCT									
1831				(8"Dia) Round Duct	130	LF							
1832				(6"Dia) Round duct	10	LF							
1832				(4"Dia) Round duct	2081	LF							
1833				FLEXIBLE ROUND DUCT									
1834				(8"Dia) Flexible Round Duct	710	LF							
1835				(4"Dia) Flexible Round duct	199	LF							
1836				(5"Dia) Flexible Round duct	371	LF							
1837				(7"Dia) Flexible Round duct	481	LF							
				(8"Dia) Flexible Round duct	2140	LF							
				Subtotal									
			150000	DIVISION 15 - PLUMBING									
1838				FCO - FLOOR CLEANOUT - CAST IRON CLEANOUT W/ GSKET SEAL & THREADED PLUG, ADJUSTABLE CAST IRON ROUND TOP W/ SECURING SCREW - JAY R. SMITH FIGURE 4220	6	EA							
1839				(2") HUB DRAIN W/ PRIMER CONNECTION	38	EA							
1840				AAV - AIR ADMITTANCE VALVE - STUDOR MINI-VENT, INTERNAL SCREENING, PREVENTS THE RELEASE OF FOUL AIR WHITE ABS	38	EA							

[illegible]

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHrs/ Unit	\$/Hour	(\$Per Unit)				
1906	E1-11A TO EPI-32			FIRE ALARM									
1907				FIRE ALARM DOOR HOLDER	4	EA							
1908				FIRE ALARM DOOR HOLDER	7	EA							
1909				FIRE ALARM HORN W/STROBE (CANDELAS)	5	EA							
1910				FIRE ALARM HORN W/STROBE (CANDELAS)	14	EA							
1911				FIRE ALARM PULL STATION	1	EA							
1912				FIRE ALARM PULL STATION	4	EA							
1913				SMOKE DETECTOR	4	EA							
1914				SMOKE DETECTOR	5	EA							
1915				SMOKE DETECTOR	6	EA							
1916				SPRINKLER FLOW SWITCH	4	EA							
1917				SPRINKLER VALVE TAMPER SWITCH	4	EA							
1918				120V, SELF CONTAINED AUDIBLE CARBON MONOXIDE SMOKE ALARM	42	EA							
1919				120V, SELF CONTAINED AUDIBLE SMOKE ALARM	46	EA							
1920				FIRE ALARM MINI HORN (CANDELAS)	78	EA							
				FIRE ALARM MINI HORN W/ STROBE (CANDELAS)	3	EA							
				Subtotal									
BUILDING 2000 A													
DIVISION 02 - EXISTING CONDITIONS													
			020000	EARTHWORK									
1921	S1-21A & S1-21B	S0-01, S3-01 & S3-02		Footing excavation.	35525	CF							
1922				Footing backfill.	20075	CF							
				Subtotal									
			030000	DIVISION 03 - CONCRETE									
			033000	CAST IN PLACE CONCRETE									
				(2'Wx1'8"H) CONCRETE FOOTING									
1923	S1-21A & S1-21B	S0-01, S3-01 & S3-02		Compaction of sub-grade.	4620	SF							
1924				Rebar's (Grade 60)	9850	LB							
1925				Concrete footing. (f'c = 3000 PSI)	6160	CF							
				(2'Wx2'2"H) CONCRETE FOOTING									
1926	S1-21A & S1-21B	S0-01, S3-01 & S3-02		Compaction of sub-grade.	1805	SF							
1927				Rebar's (Grade 60)	5000	LB							
1928				Concrete footing. (f'c = 3000 PSI)	3125	CF							
				(1'Wx8"H) CONCRETE FOOTING									
1929	S1-21A & S1-21B	S0-01, S3-01 & S3-02		Compaction of sub-grade.	560	SF							
1930				Rebar's (Grade 60)	5000	LB							
1931				Concrete footing. (f'c = 3000 PSI)	250	CF							
				(5'Wx1'2"H) RETAINING WALL CONCRETE FOOTING									
1932	S1-21A & S1-21B	S0-01, S3-01 & S3-02		Compaction of sub-grade.	1940	SF							
1933				Rebar's (Grade 60)	3285	LB							
1934				Concrete footing. (f'c = 3000 PSI)	2055	CF							
				RETAINING WALL									
1935	S1-21A & S1-21B	S0-01, S3-01 & S3-02		Rebar's (Grade 60)	3285	LB							
1936				(12" THK) Concrete wall. (f'c = 5000 PSI)	3880	CF							
				SLAB ON GRADE									
1937	S1-21A & S1-21B	S0-01, S3-01 & S3-02		Compaction of sub-grade.	17920	SF							
1938				(10 MIL) Vapor barrier.	17920	SF							
1939				(4" Thick) Reinforced concrete slab w/ post tensioning. (f'c = 3000 PSI)	17920	SF							
				SLAB ON GRADE									
1940	S1-21A & S1-21B	S0-01, S3-01 & S3-02		Compaction of sub-grade.	1240	SF							
1941				(10 MIL) Vapor barrier.	1240	SF							
1942				(4" Thick) Concrete slab w/ CIP 6x6 - 10/10 WWM. (f'c = 3000 PSI)	1240	SF							
1943	S1-21A to S1-24A			Metal pan concrete stair.	460	SF							
				Subtotal									
			040000	DIVISION 04 - MASONRY									
			042000	UNIT MASONRY									
1944	A1-11A TO ID-7.3			Exterior Type BR-1, Brick Veneer-Gray.	2860	SF							
				Subtotal									
			050000	DIVISION 05 - METAL									
			057000	ORNAMENTAL METAL									
1945	A1-11A TO ID-7.3			(42" H) Hand Rail.	180	LF							
1946				Type-MR-1, 42" Aluminum picket railing.	1240	LF							
				Subtotal									
			060000	DIVISION 06 - WOOD, PLASTIC AND COMPOSITES									
			061053	WOOD FRAMING									
1947	S1-22A to S1-25B			(2x8) Header beam.	1205	LF							
1948				(2x10) Header beam.	1605	LF							
1949				5.5x11.25 GL	485	LF							
1950				5.5x14 GL	105	LF							
1951				5.5x18 GL	380	LF							
1952				7x18 GL	210	LF							
1953				5.25x11.25 PSL	190	LF							
1954				Pre-Fabricated wood floor trusses	24660	LF							
1955				Pre-Engineered Roof Trusses	9070	LF							
1956				(2x12) Canopy SCAB	1095	LF							
1957				Joist hanger.	4516	EA							
			061000	ROUGH CARPENTRY									
1958	S1-22A to S1-25B			(3/4") T&G OSB or Plywood sheathing.	49030	SF							
1959				(5/8") Exterior grade OSB or Plywood sheathing.	18745	SF							
				SHEARWALL									
1960	A1-11A TO ID-7.3			(5/8", 1-Layer) Plywood sheathing.	20880	SF							
			064100	ARCHITECTURAL WOOD CASEWORK									
1961	A1-11A TO ID-7.3			(12" W) Road & Shelf.	2021	FT							
1962				(12'Lx2'Dx2'10"H) Wall cabinet.	8	EA							
1963				(8'8"Lx1Dx2'6"H) Wall cabinet.	10	EA							
1964				(11'Lx1Dx2'6"H) Wall cabinet.	4	EA							
1965				(13'Lx2'Dx2'10"H) Wall cabinet.	2	EA							
1966				(11'3"Lx1Dx2'6"H) Wall cabinet.	14	EA							
1967				(12'Lx1Dx2'6"H) Wall cabinet.	5	EA							
1968				(13'6"Lx1Dx2'6"H) Wall cabinet.	2	EA							
1969				(8'8"Lx2Dx2'10"H) Base cabinet.	14	EA							
1970				(12'Lx1Dx2'6"H) Base cabinet.	9	EA							
1971				(9'8"Lx2Dx2'10"H) Base cabinet.	4	EA							
1972				(11'9"Lx2Dx2'10"H) Base cabinet.	10	EA							
1973				(6'Lx2 Dx2'10"H) Base cabinet.	2881	EA							
1974				(11'Lx2'Dx2'10"H) Base cabinet.	23	EA							
1975				(14'Lx1Dx2'6"H) Base cabinet.	9	EA							
1976				(9'4"Lx2Dx2'10"H) Base cabinet.	4	EA							
1977				(6'8"Lx2Dx2'10"H) Base cabinet.	4	EA							

#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHrs/ Unit	\$/Hour	(\$Per Unit)				
1978				(4'6"Lx2Dx2'10"H) Base cabinet.	20	EA							
1979				(6'6"Lx2Dx2'10"H) Base cabinet.	10	EA							
1980				(9'Lx2Dx2'10"H) Base cabinet.	10	EA							
1981				(12'Lx2'Dx2'10"H) Base cabinet.	4	EA							
1982				Cabinet.	154	EA							
1983				16" Mud bench	80	EA							
				Subtotal									
			070000	DIVISION 07 - THERMAL AND MOISTURE PROTECTION									
				ROOFING									
1984	A2-10			(R-38) Roof insulation.	18745	SF							
1985				(60 MIL) TPO Roofing.	18745	SF							
1986	A1-11A TO ID-7.3			Walking pad.	750	LF							
1987				Air/Moisture barrier.	12215	SF							
			076000	SHEET METAL FLASHING AND TRIM									
1988	A1-11A TO ID-7.3			Downspout.	470	LF							
1989				Gutter.	785	LF							
				Subtotal									
			080000	DIVISION 08 - OPENING									
			080152	WOOD WINDOWS									
1990				Type S10, (9'-0" W x 8'-2" H) Single vinyl window.	1	EA							
1991				Type W 01, (2'-6" W x 6'-0" H) Single vinyl window.	58	EA							
1992	A1-11A TO ID-7.3			Type W 02, (3'-0" W x 6'-0" H) Single vinyl window.	36	EA							
1993				Type W 03, (5'-0" W x 6'-0" H) Single vinyl window.	32	EA							
1994				Type W 04, (6'-0" W x 6'-0" H) Single vinyl window.	334	EA							
1995				Type W 05, (9'-0" W x 7'-8" H) Single vinyl window.	9	EA							
			081113	HOLLOW METAL DOORS, FRAMES AND HARDWARE									
1996	A1-11A TO ID-7.3			(HR 45 MIN) (3'-0" W x 7'-0" H) HM door & frame.	20	EA							
1997				(HR 90 MIN) (3'-0" W x 7'-0" H) HM door & frame.	12	EA							
			082100	WOOD DOORS									
1998				(2'-10" W x 6'-8" H) Solid core wood door & frame.	369	EA							
1999				Unit A2F, (2'-6" W x 6'-8" H) Solid core wood door & frame.	26	EA							
2000				(HR 20 MIN) (3'-0" W x 7'-0" H) Solid core wood door & frame.	76	EA							
2001	A1-11A TO ID-7.3			(9'-0" W x 8'-0" H) Vinyl/ Glass door & frame.	9	EA							
2002				(3'-0" W x 8'-0" H) Fiberglass door & frame.	55	EA							
2003				(5'-0" W x 6'-8" H) Solid core wood door & frame.	36	EA							
2004				(3'-0" W x 6'-8" H) Solid core wood door & frame.	12	EA							
2005				(1'-6" W x 6'-8" H) Hollow core wood door & frame.	14	EA							
2006				(3'-0" W x 6'-8" H) Hollow core wood door & frame.	118	EA							
			087100	FINISH HARDWARE									
2007	A1-11A TO ID-7.3			Door hardware. (747 EA)	1	LS							
				Subtotal									
			090000	DIVISION 09 - FINISHES									
2008				Exterior Type CP-1, Fiber cement panel (4"x10") W/ Battens-White Allura.	5694	SF							
2009	A1-11A TO ID-7.3			Exterior Type CP-2, Fiber cement panel (4"x10") W/ Battens-Dark gray.	11452	SF							
2010				Exterior Type CP-3,Fiber cement panel (4"x10") W/ Metal Reveals White.	2420	SF							
2011				Exterior Type WP-1, Wall panel.	4815	SF							
2012				Exterior Type CT-1, (12" H)	702	LF							
2013				Exterior Type CT-1, (23" H)	251	LF							
			092600	GYPSPUM BOARD ASSEMBLIES									
2014	A1-11A TO ID-7.3			5/8" GWB ceiling.	68167	SF							
				INTERIOR WALLS									
				(1 HR) TYPE 1WB4, GWB UNIT WALL (7110 LF)									
2015	A1-11A TO ID-7.3			(2x4) Wood studs at 16" O.C	48122	LF							
2016				(5/8", 1-Layer) Type X, GYP. BD. both side	127980	SF							
2017				(2x4) Top and bottom track.	21330	LF							
				(1 HR) TYPE 1WB6, GWB UNIT WALL (910 LF)									
2018	A1-11A TO ID-7.3			(2x6) Wood studs at 16" O.C	6167	LF							
2019				(5/8", 1-Layer) Type X, GYP. BD. both side	16380	SF							
2020				(2x6) Top and bottom track.	2730	LF							
				(1 HR) TYPE 1WC4, GWB WALL (200 LF)									
2021				(2x4) Wood studs at 16" O.C	1362	LF							
2022				(1/2") Resilient channel	1362	LF							
2023	A1-11A TO ID-7.3			(4") Batt insulation	1800	SF							
2024				(5/8", 1-Layer) Type X, GYP. BD. One side	1800	SF							
2025				(5/8", 1-Layer) Type X, Exterior grade GYP. BD. One side	1800	SF							
2026				(2x4) Top and bottom track.	600	LF							
2027				(1/2") Top and bottom track.	400	LF							
				(1 HR) TYPE 1WC6, GWB WALL (2120 LF)									
2028				(2x6) Wood studs at 16" O.C	14355	LF							
2029				(1/2") Resilient channel	14355	LF							
2030	A1-11A TO ID-7.3			(6") Batt insulation	19080	SF							
2031				(5/8", 1-Layer) Type X, GYP. BD. One side	19080	SF							
2032				(5/8", 1-Layer) Type X, Exterior grade GYP. BD. One side	19080	SF							
2033				(2x6) Top and bottom track.	6360	LF							
2034				(1/2") Top and bottom track.	4240	LF							
				(1 HR) TYPE 1WD4, GWB UNIT SEP. WALL (2995 LF)									
2035	A1-11A TO ID-7.3			(2x4) Wood studs at 16" O.C	20280	LF							
2036				(4") Batt insulation	53910	SF							
2037				(5/8", 1-Layer) Type X, GYP. BD. both side	53910	SF							
2038				(2x4) Top and bottom track.	8985	LF							
				(1 HR) TYPE 1WD6, GWB UNIT SEP. WALL (885 LF)									
2039	A1-11A TO ID-7.3			(2x6) Wood studs at 16" O.C	6000	LF							
2040				(6") Batt insulation	15930	SF							
2041				(5/8", 1-Layer) Type X, GYP. BD. both side	15930	SF							
2042				(2x6) Top and bottom track.	2655	LF							
				(2 HR) TYPE 2WK4, GWB SHAFT WALL (685 LF)									
2043	A1-11A TO ID-7.3			(2x4) Wood studs at 16" O.C	9289	LF							
2044				(4") Batt insulation	12330	SF							
2045				(5/8", 1-Layer) Type X, GYP. BD. both side	12330	SF							
2046				(1", 1-Layer) Type X, GYP. Liner panel both side	12330	SF							
2047				(2x4) Top and bottom track.	4110	LF							
				(2 HR) TYPE 2WK6, GWB SHAFT WALL (140 LF)									
2048	A1-11A TO ID-7.3			(2x6) Wood studs at 16" O.C	1913	LF							
2049				(4") Batt insulation	2520	SF							
2050				(5/8", 1-Layer) Type X, GYP. BD. both side	2520	SF							
2051				(1", 1-Layer) Type X, GYP. Liner panel both side	2520	SF							
2052				(2x6) Top and bottom track.	840	LF							
				(1 HR) EXTERIOR WALL (8035 LF)									
2053	A1-11A TO ID-7.3			(2x6) Wood studs at 16" O.C	20547	LF							
2054				(R-20) Batt insulation.	12215	SF							
2055				(5/8", 1-Layer) Type X, GYP. BD. One side.	12215	SF							
2056				(5/8", 1-Layer) Type X, Exterior Plywood sheathing one side.	12215	SF							
2057				(2x6) Top and bottom track.	9105	LF							
			093100	CERAMIC / PORCELAIN TILING									

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL	EQUIPMENT	COMPOSITE	TOTAL	
							MHrs/ Unit	\$/Hour	(\$/Per Unit)	(\$Per Unit)	(\$Per Unit)	RATE/UNIT	COST	
2058	A1-11A TO			porcelain wall tile.	6050	SF								
2059	ID-7.3			Kitchen backsplash wall tile.	1435	SF								
					096000	FLOORING								
2060	A1-11A TO			Carpet floor.	19536	SF								
2061	ID-7.3			Vinyl wood plank w/ sound mat floor.	39141	SF								
2062				Wood base painted.	21097	LF								
					099100	PAINTING								
2063	A1-11A TO			GWB ceiling paint.	68170	SF								
2064	ID-7.3			GWB wall paint.	25915	SF								
2065				Door paint. (747 EA)	35310	SF								
						Subtotal								
					100000	DIVISION 10 - SPECIALTIES								
					101510	TOILET COMPARTMENTS								
2066	A1-11A TO			Compartment wall. (6' H)	415	LF								
					102813	TOILET AND BATH ACCESSORIES								
2067	A1-11A TO			Mirror.	104	EA								
2068	ID-7.3			Toilet paper holder.	104	EA								
2069				Tower bar.	104	EA								
2070				(36"x60") Tub	42	EA								
						Subtotal								
					110000	DIVISION 11 - EQUIPMENT								
2071	A1-11A TO			Dishwasher.	70	EA								
2072	ID-7.3			Range & Micro wave.	70	EA								
2073				Refrigerator	70	EA								
2074				Dryer	70	EA								
2075				Washer	70	EA								
						Subtotal								
					120000	DIVISION 12 - FURNISHING								
					123660	QUARTZ SURFACING COUNTERTOPS								
2076				QUARTZ COUNTER TOP - MSI SURFACES - MANHATTAN GRAY 3CM - POLISHED	4405	SF								
						Subtotal								
					150000	DIVISION 15 - HEATING, VENTILATING, AND AIR-CONDITIONING (HVAC)								
2077	M1-11A TO MP1-21			DS 2-1-1 - Ductless split system w/ Heat pump Outdoor unit DSHP 2-1-1, Manuf: MITSUBISHI ELECTRIC, MODEL: PKA/PUZ, (705 CFM)	1	EA								
2078				DS 2-2-1 - Ductless split system w/ Heat pump Outdoor unit DSHP 2-2-1, Manuf: MITSUBISHI ELECTRIC, MODEL: PKA/PUZ, (705 CFM)	1	EA								
2079				EH 2-1-1 - ELECTRIC HEATER, MANUF: MARLEY, MODEL NO: AWH (100 CFM)	1	EA								
2080				EH 2-1-2 - ELECTRIC HEATER, MANUF: MARLEY, MODEL NO: AWH (100 CFM)	1	EA								
2081				EH 2-2-1 - ELECTRIC HEATER, MANUF: MARLEY, MODEL NO: AWH (100 CFM)	1	EA								
2082				FC 2-1-1 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 2-1-1, Manuf: CARRIER, FE4A/25HCE (800CFM)	1	EA								
2083				FC 2-2-1 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 2-2-1, Manuf: CARRIER, FE4A/25HCE (800CFM)	1	EA								
2084				FC 2-3-1 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 2-3-1, Manuf: CARRIER, FE4A/25HCE (800CFM)	1	EA								
2085				FC 2-4-1 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP 2-4-1, Manuf: CARRIER, FE4A/25HCE (800CFM)	2	EA								
2086				Fire damper	5	EA								
2087				RG2 - (14"x14") Return grille - Manuf: Titus, Model: 355RS, Steel	4	EA								
2088				RG2 - (18"x18") Return grille - Manuf: Titus, Model: 355RS, Steel	5	EA								
2089				SG16 - (14x8) Supply grille - Manuf: Titus, Model: 301RS, Steel (200 CFM) w/ Radiation damper	20	EA								
2090				(BLDG 2000A) ESP-1 - PUMP - MODEL: STANCO OIL MINDER SYSTEM W/ ALARM & REMOTE MONITORING CIRCUIT	1	EA								
2091				(BLDG 2000A) NFVH - NON-FREEZE EXTERIOR WALL HYDRANT, (3/4") CAST BRONZE HYDRANT, RECESSED W/ STAINLESS STEEL BOX, VACCUM BREAKER, NICKEL BRONZE - JAY R. SMITH FIGURE 5509-QT	1	EA								
2092				(BLDG 2000A) NON-FREEZE WALL HYDRANT, ROOF MOUNT PEDESTAL W/ MOUNTING FLANGE & SHROUD, MALE HOSE END OUTLET W/ DUAL CHECK BACKFLOW PREVENTER, (3/4") INLET W/ SELF DRAINING VENTURI - WOODFORD MODEL SRH-MS	2	EA								
2093				EF A - EXHAUST FAN - MANUF: BROAN, MODEL: 670, (50 CFM)	93	EA								
2094				FC A2 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP A2, Manuf: CARRIER, FFMA/25HCE (600CFM)	4	EA								
2095				FC A3 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP A3, Manuf: CARRIER, FFMA/25HCE (600CFM)	2	EA								
2096				FC A4 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP A4, Manuf: CARRIER, FFMA/25HCE (600CFM)	14	EA								
2097				FC A5 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP A5, Manuf: CARRIER, FFMA/25HCE (600CFM)	4	EA								
2098				FC A6 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP A6, Manuf: CARRIER, FFMA/25HCE (800CFM)	5	EA								
2099				FC A7 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP A7, Manuf: CARRIER, FFMA/25HCE (800CFM)	5	EA								
2100				FC B2 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP B2, Manuf: CARRIER, FFMA/25HCE (800CFM)	10	EA								
2101				FC B2E - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP B2, Manuf: CARRIER, FFMA/25HCE (800CFM)	9	EA								
2102				FC B2-HC - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP B2-HC, Manuf: CARRIER, FFMA/25HCE (800CFM)	1	EA								
2103				FC B3 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP B3, Manuf: CARRIER, FFMA/25HCE (1000CFM)	4	EA								
2104				FC C1 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP C1, Manuf: CARRIER, FFMA/25HCE (1200CFM)	10	EA								
2105				Radiation damper	483	EA								
2106				RG2 - (16"x10") Return grille - Manuf: Titus, Model: 355RS	38	EA								
2107				RG2 - (36"x10") Return grille - Manuf: Titus, Model: 355RS	14	EA								
2108				RG2 - (36"x12") Return grille - Manuf: Titus, Model: 355RS	34	EA								
2109				RG3 - (16"x10") Return grille - Manuf: Titus, Model: 350RL	90	EA								
2110				RG3 - (36"x10") Return grille - Manuf: Titus, Model: 350RL	20	EA								
2111				SG16 - (14x8) Supply grille - Manuf: Titus, Model: 301RS, Steel	248	EA								
2112				SG16 - (8x6) Supply grille - Manuf: Titus, Model: 301RS, Steel	167	EA								

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHrs/ Unit	\$/Hour	(\$Per Unit)				
				Galvanized sheet metal duct w/ Wrap equal to owens coming fiberglass w/ FRK vapor barrier. Insulation shall be R-6 except on roof shall be R-8.									
2113				(10X10) Metal duct	125	LF							
2114				(12X12) Metal duct	60	LF							
2115				(12X10) Metal duct	225	LF							
2116				(14X10) Metal duct	112	LF							
2117				(14X12) Metal duct	72	LF							
				ROUND DUCT									
2118				(8"Dia) Round duct	110	LF							
2119				(4"Dia) Round duct	2868	LF							
				FLEXIBLE ROUND DUCT									
2120				(10"Dia) Flexible round duct	1135	LF							
2121				(8"Dia) Flexible round duct	235	LF							
2122				(4"Dia) Flexible Round duct	570	LF							
2123				(5"Dia) Flexible Round duct	594	LF							
2124				(7"Dia) Flexible Round duct	1523	LF							
2125				(8"Dia) Flexible Round duct	3960	LF							
				Subtotal									
			150000	DIVISION 15 - PLUMBING									
2126				(BLDG 2000A) FCO - FLOOR CLEANOUT - CAST IRON CLEANOUT W/ GSKET SEAL & THREADED PLUG, ADJUSTABLE CAST IRON ROUND TOP W/ SECURING SCREW - JAY R. SMITH FIGURE 4220	6	EA							
2127				(BLDG 2000A) FD-2 - (4") FLOOR DRAIN - CAST IRON (12"Dia) DRAIN W/ SEDIMENT BUCKET, Cast IRON GRATE, Speedi set OUTLET, & TRAP PRIMER - JAY R. SMITH FIGURE 2142-M	1	EA							
2128				(2") HUB DRAIN W/ PRIMER CONNECTION	68	EA							
2129				AAV - AIR ADMITTANCE VALVE - STUDOR MINI-VENT, INTERNAL SCREENING, PREVENTS THE RELEASE OF FOUL AIR WHITE ABS	68	EA							
2130					68	EA							
2131				KS-1 - KITCHEN SINK - RESIDENTIAL	68	EA							
2132				LAV-1 - LAVATORY - RESIDENTIAL	186	EA							
2133				SH-1 - SHOWER - RESIDENTIAL W/ SHOWER HEAD	68	EA							
2134				SHUTT-OFF VALVE	68	EA							
2135				WATER SUBMETER	68	EA							
2136				WC-1 - WATER CLOSET - RESIDENTIAL	102	EA							
2137				WH-1 - WATER HEATER - MODEL: ENLB-40 - 38 GAL, W/ T&P RELEIF VALVE, VACCUM RELIEF VALVE & WATTS LFBRV COMBINATION BALL & THERMAL RELIEF VALVE, A.O SMITH - PROLINE SERIES	34	EA							
2138				WH-2 - WATER HEATER - MODEL: ENLB-50 - 48 GAL, W/ T&P RELEIF VALVE, VACCUM RELIEF VALVE & WATTS LFBRV COMBINATION BALL & THERMAL RELIEF VALVE, A.O SMITH - PROLINE SERIES	34	EA							
2139				WM-1 - WASHING MACHINE OUTLET BOX, ABS, LEAD FREE W/ QUARTER TURN BALL VALVE, WATER HAMMER ARRESSTOR - SIOUX CHIEF 696-G1010 SERIES	68	EA							
2140				DOMESTIC WATER PIPING									
2141				(BLDG 2000A) (1-1/2") COLD WATER PIPE	275	LF							
2142				(BLDG 2000A) (4") COLD WATER PIPE	592	LF							
2143				(BLDG 2000A) (8") FIRE SERVICE LINE	15	LF							
2144				(1/2") COLD WATER PIPE	3453	LF							
2145				(1/2") HOT WATER PIPE	2630	LF							
2146				(1-1/4") COLD WATER PIPE	313	LF							
2147				(3/4") COLD WATER PIPE	2689	LF							
				(3/4") HOT WATER PIPE	2289	LF							
				SANITARY PIPING									
2148				(BLDG 2000A) (4") SANITARY PIPE	141	LF							
2149				(BLDG 2000A) (8") SANITARY PIPE	460	LF							
2150				(2") SANITARY PIPE	2965	LF							
2151				(2") VENT PIPE	1217	LF							
2152				(3") SANITARY PIPE	3247	LF							
2153				(3") VENT PIPE	966	LF							
				Subtotal									
			160000	DIVISION 16 - ELECTRICAL									
				LIGHT FIXTURE									
2154				A1 - 6" SURFACE MOUNT LED DOWNLIGHT - MANUF: HALO, MODEL: SLD 1200 SERIES / SLD612B35WH/80 CRI/3500K/WHITE	92	EA							
2155				B1 - UNIT ENTRY SCONE - MANUF: SAVOY HOUSE, MODEL: 9-0901-1-89/GLENN 1-LIGHT WALL SCONE / 7"WX12"HX9"D/E26 8W 120V LED BULB (1 PER FIXTURE) / MATTE BLACK FINISH	68	EA							
2156				EM - EMERGENCY FIXTURE LIGHT - SEALED NICKEL CADMIUM BATTERY, CIRCULAR HEAD, DAMP LOCATION LISTED, W/ BATTERY CAPACITY TO POWER REMOTE HEAD, MANUF: SURE LITES SEL50 SERIES LITHONIA	25	EA							
2157				EMR1 - REMOTE HEAD, PAIRED W/ EMERGENCY FIXTURE OR EXIT SIGN, SINGLE HEAD, MANUF: SURE LITES SRP SERIES	1	EA							
2158				S1 - 4' LED STRIP LIGHT - METALUX SNLED SERIES, LITHONIA	41	EA							
2159				S1E - 4' LED STRIP LIGHT - METALUX SNLED SERIES, LITHONIA W/ 1600 LUMENS BATTERY	15	EA							
2160				S2E - 4' LED VAPORTIGHT STRIP, IMPACT RESISTANT POLYCARBONATE HOUSING, IMPACT RESISTANT FROASTED POLYCARBONATE LENS, LED LAMP, WIDE DISTRIBUTION, MANUF: LITHONIA VAP LED SERIES, PHILIPS W/ 1600 LUMEN BATTERY	4	EA							
2161				S3 - 4' SURFACE/WALL MOUNTED LED FIXTURE, INTEGRAL OCCUPANCY SENSOR W/ 0-10V DIMMING, STEP DIMMING, HIGH LUMEN OUTPUT, INTEGRAL 14W BATTERY PACK, MANUF: METALUX SWLED SERIES LITHONIA	30	EA							
2162				X1 - EXIT SIGN, LED LAMP, POLYCARBONATE HOUSING, SELF CONTAINED BATTERY, MODEL: SURE LITES LPX SERIES LITHONIA	43	EA							
2163				D - 7" SURFACE MOUNTED LED FIXTURE - MANUF: SATCO - S29331 / 7" FLUSH MOUNT LED FIXTURE - ROUND /120V	556	EA							
2164				F - 50" CEILING FAN W/ LED LIGHT KIT - MANUF: CASK INDUSTRIES - CF104/4-BLADE/50"WX19.5"H	180	EA							
2165				P - ISLAND PENDANT - MANUF: KUZCO LIGHTING - MODEL: VANDERBILT 493210-WH/GD/10"DIA X 12"H / 120" MAX CORD LENGTH	170	EA							
2166				VA - VANITY SCOSCE - MANUF: QUORUM INTERNATIONAL - MODEL: 507-3-6980/EPsy 3-LIGHT VANITY / 9.25"H X23.5"W X 7"D / 100W MAX WATTAGE	186	EA							

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHrs/ Unit	\$/Hour	(\$Per Unit)				
2239	A1-11A TO ID-7.3			(42" H) Hand Rail.	110	LF							
2240				Type-MR-1, 42" Aluminum picket railing.	1140	LF							
				Subtotal									
			060000	DIVISION 06 - WOOD, PLASTIC AND COMPOSITES									
			061053	WOOD FRAMING									
2241	S1-22B to S1-25D			(2x8) Header beam.	1315	LF							
2242				(2x10) Header beam.	1325	LF							
2243				5.5x11.25 GL	320	LF							
2244				5.5x14 GL	50	LF							
2245				5.5x18 GL	240	LF							
2246				7x18 GL	130	LF							
2247				5.25x11.25 PSL	165	LF							
2248				Pre-Fabricated wood floor trusses	25015	LF							
2249				Pre-Engineered Roof Trusses	9290	LF							
2250				(2x12) Canopy SCAB	1280	LF							
2251				Joist hanger.	4566	EA							
			061000	ROUGH CARPENTRY									
2252	S1-22B to S1-25D			(3/4") T&G OSB or Plywood sheathing.	49785	SF							
2253				(5/8") Exterior grade OSB or Plywood sheathing.	19260	SF							
	A1-11A TO ID-7.3			SHEARWALL									
2254				(5/8", 1-Layer) Plywood sheathing.	23265	SF							
			064100	ARCHITECTURAL WOOD CASEWORK									
2255	A1-11A TO ID-7.3			(12" W) Road & Shelf.	1979	LF							
2256				(12'Lx1'Dx2'6"H) Wall cabinet.	8	EA							
2257				(12'Lx1'Dx2'6"H) Wall cabinet.	4	EA							
2258				(13'6"Lx1'Dx2'6"H) Wall cabinet.	7	EA							
2259				(11'Lx1'Dx2'6"H) Wall cabinet.	9	EA							
2260				(8'8"Lx1'Dx2'6"H) Wall cabinet.	10	EA							
2261				(13'Lx2'Dx2'10"H) Wall cabinet.	2	EA							
2262				(14'Lx1'Dx2'10"H) Wall cabinet.	16	EA							
2263				(11'2"Lx1'Dx2'6"H) Wall cabinet.	10	EA							
2264				(11'3"Lx1'Dx2'6"H) Wall cabinet.	26	EA							
2265				(6'Lx2'Dx2'10"H) Base cabinet.	153	EA							
2266				(11'Lx2'Dx2'10"H) Base cabinet.	25	EA							
2267				(8'8"Lx2'Dx2'10"H) Base cabinet.	26	EA							
2268				(12'Lx2'Dx2'10"H) Base cabinet.	17	EA							
2269				(11'9"Lx2'Dx2'10"H) Base cabinet.	8	EA							
2270				(6'8"Lx2'Dx2'10"H) Base cabinet.	9	EA							
2271				(4'Lx2'Dx2'10"H) Base cabinet.	10	EA							
2272				(8'Lx2'Dx2'10"H) Base cabinet.	10	EA							
2273				(9'4"Lx2'Dx2'10"H) Base cabinet.	9	EA							
2274				Cabinet.	169	EA							
2275				16" Mud bench	70	EA							
				Subtotal									
			070000	DIVISION 07 - THERMAL AND MOISTURE PROTECTION									
2276	A2-10			ROOFING									
2277				(R-38) Roof insulation.	19260	SF							
2278				(60 MIL) TPO Roofing.	19260	SF							
2279	A1-11A TO ID-7.3			Walking pad.	835	LF							
				Air/Moisture barrier.	12000	SF							
			076000	SHEET METAL FLASHING AND TRIM									
2280	A1-11A TO ID-7.3			Downspout.	360	LF							
2281				Gutter.	755	LF							
				Subtotal									
			080000	DIVISION 08 - OPENING									
			080152	WOOD WINDOWS									
2282	A1-11A TO ID-7.3			Type S10, (9'-0" W x 8'-2" H) Single vinyl window.	1	EA							
2283				Type W 01, (2'-6" W x 6'-0" H) Single vinyl window.	35	EA							
2284				Type W 02, (3'-0" W x 6'-0" H) Single vinyl window.	22	EA							
2285				Type W 03, (5'-0" W x 6'-0" H) Single vinyl window.	83	EA							
2286				Type W 04, (6'-0" W x 6'-0" H) Single vinyl window.	290	EA							
2287				Type W 05, (9'-0" W x 7'-8" H) Single vinyl window.	9	EA							
			081113	HOLLOW METAL DOORS, FRAMES AND HARDWARE									
2288	A1-11A TO ID-7.3			(3'-0" W x 8'-0" H) HM door & frame.	4	EA							
			082100	WOOD DOORS									
2289	A1-11A TO ID-7.3			(HR 90 MIN) (3'-0" W x 7'-0" H) HM door & frame.	4	EA							
2290				(HR 45 MIN) (3'-0" W x 7'-0" H) HM door & frame.	13	EA							
2291				(HR 20 MIN) (3'-0" W x 7'-0" H) Solid core wood door & frame.	79	EA							
2292				(2'-10" W x 6'-8" H) Solid core wood door & frame.	459	EA							
2293				(2'-6" W x 6'-8" H) Solid core wood door & frame.	13	EA							
2294				(3'-0" W x 8'-0" H) Fiberglass door & frame.	71	EA							
2295				(6'-0" W x 7'-0" H) Vinyl/ Glass door & frame.	15	EA							
2296				(9'-0" W x 8'-0" H) Vinyl/ Glass door & frame.	10	EA							
2297				(5'-0" W x 6'-8" H) Solid core wood door & frame.	26	EA							
2298				(1'-6" W x 6'-8" H) Hollow core wood door & frame.	9	EA							
2299				(3'-0" W x 6'-8" H) Hollow core wood door & frame.	73	EA							
			087100	FINISH HARDWARE									
2300	A1-11A TO ID-7.3			Door hardware. (776 EA)	1	LS							
				Subtotal									
			090000	DIVISION 09 - FINISHES									
2301	A1-11A TO ID-7.3			Exterior Type CP-1, Fiber cement panel (4"x10") W/ Battsens-White Allura.	6420	SF							
2302				Exterior Type CP-2, Fiber cement panel (4"x10") W/ Battsens-Dark gray.	8855	SF							
2303				Exterior Type CP-3, Fiber cement panel (4"x10") W/ Metal Reveals White.	2330	SF							
2304				Exterior Type WP-1, Wall panel.	7130	SF							
2305				Exterior Type CT-1, (12" H)	880	LF							
2306				Exterior Type CT-1, (23" H)	215	LF							
			092600	GYPSUM BOARD ASSEMBLIES									
2307	A1-11A TO ID-7.3			5/8" GWB ceiling.	74865	SF							
				INTERIOR WALLS									
				(1 HR) TYPE 1WB4, GWB UNIT WALL (6590 LF)									
2308	A1-11A TO ID-7.3			(2x4) Wood studs at 16" O.C	44600	LF							
2309				(5/8", 1-Layer) Type X, GYP. BD. both side	118620	SF							
2310				(2x4) Top and bottom track.	19770	LF							
				(1 HR) TYPE 1WB6, GWB UNIT WALL (3035 LF)									
2311	A1-11A TO ID-7.3			(2x6) Wood studs at 16" O.C	20550	LF							
2312				(5/8", 1-Layer) Type X, GYP. BD. both side	54630	SF							
2313				(2x6) Top and bottom track.	9105	LF							
				(1 HR) TYPE 1WC4, GWB WALL (150 LF)									
2314				(2x4) Wood studs at 16" O.C	1025	LF							
2315				(1/2") Resilient channel	1025	LF							

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHrs/ Unit	\$/Hour	(\$Per Unit)				
2383	M1-11A TO MP1-21			FC A2 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP A2, Manuf: CARRIER, FFMA/25HCE (600CFM)	4	EA							
2384				FC A3 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP A3, Manuf: CARRIER, FFMA/25HCE (600CFM)	2	EA							
2385				FC A4 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP A4, Manuf: CARRIER, FFMA/25HCE (600CFM)	26	EA							
2386				FC A4-HC - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP A4-HC, Manuf: CARRIER, FFMA/25HCE (600CFM)	2	EA							
2387				FC A6 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP A6, Manuf: CARRIER, FFMA/25HCE (800CFM)	4	EA							
2388				FC A7 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP A7, Manuf: CARRIER, FFMA/25HCE (800CFM)	4	EA							
2389				FC B1 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP B1, Manuf: CARRIER, FFMA/25HCE (600CFM)	10	EA							
2390				FC B2 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP B2, Manuf: CARRIER, FFMA/25HCE (800CFM)	7	EA							
2391				FC B2E - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP B2, Manuf: CARRIER, FFMA/25HCE (800CFM)	9	EA							
2392				FC B3 - DX SPLIT SYSTEM HEAT PUMP W/ OUTDOOR HP B3, Manuf: CARRIER, FFMA/25HCE (1000CFM)	9	EA							
2393				Radiation damper	540	EA							
2394				RG2 - (16"X10") Return grille - Manuf: Titus, Model: 355RS	26	EA							
2395				RG2 - (36"X10") Return grille - Manuf: Titus, Model: 355RS	18	EA							
2396				RG2 - (36"X12") Return grille - Manuf: Titus, Model: 355RS	25	EA							
2397				RG3 - (16"X10") Return grille - Manuf: Titus, Model: 350RL	120	EA							
2398				RG3 - (36"X10") Return grille - Manuf: Titus, Model: 350RL	6	EA							
2399				RG3 - (36"X10") Return grille - Manuf: Titus, Model: 350RL	28	EA							
2400				RG3 - (36"X12") Return grille - Manuf: Titus, Model: 350RL	2	EA							
2401				SG16 - (14x8) Supply grille - Manuf: Titus, Model: 301RS, Steel	266	EA							
2402				SG16 - (8x6) Supply grille - Manuf: Titus, Model: 301RS, Steel	197	EA							
	M1-11A TO MP1-21			Galvanized sheet metal duct w/ Wrap equal to ownes corning fiberglass w/ FRK vapor barrier. Insulation shall be R-6 except on roof shall be R-8.									
2403				(10X10) Metal duct	40	LF							
2404				(10X10) Metal duct	50	LF							
2405				(14X14) Metal duct	50	LF							
2406				(12X10) Metal duct	280	LF							
2407				(14X10) Metal duct	142	LF							
2408				(14X12) Metal duct	45	LF							
				ROUND DUCT									
2409				(8"Dia) Round duct	130	LF							
2410				(8"Dia) Round duct	20	LF							
2411				(4"Dia) Round duct	4309	LF							
				FLEXIBLE ROUND DUCT									
2412				(10"Dia) Flexible round duct	715	LF							
2413				(10"Dia) Flexible round duct	530	LF							
2414				(8"Dia) Flexible round duct	470	LF							
2415				(4"Dia) Flexible Round duct	631	LF							
2416				(5"Dia) Flexible Round duct	698	LF							
2417				(7"Dia) Flexible Round duct	1793	LF							
2418				(8"Dia) Flexible Round duct	4041	LF							
				Subtotal									
				DIVISION 15 - PLUMBING									
2419	P1-11A TO P3-08			(BLDG 2000B) FCO - FLOOR CLEANOUT - CAST IRON CLEANOUT W/ GSKET SEAL & THREADED PLUG, ADJUSTABLE CAST IRON ROUND TOP W/ SECURING SCREW - JAY R. SMITH FIGURE 4220	6	EA							
2420				(2") HUB DRAIN W/ PRIMER CONNECTION	67	EA							
2421				AAV - AIR ADMITTANCE VALVE - STUDOR MINI-VENT, INTERNAL SCREENING, PREVENTS THE RELEASE OF FOUL AIR WHITE ABS	67	EA							
2422				IM-1 - ICE MAKER OUTLET BOX: ABS, LEAD FREE W/ QUARTER TURN BALL VALVE & WATER HAMMER ARRESTOR - SIOUX CHIEF 696-G1010	67	EA							
2423				KS-1 - KITCHEN SINK - RESIDENTIAL	67	EA							
2424				LAV-1 - LAVATORY - RESIDENTIAL	171	EA							
2425				SH-1 - SHOWER - RESIDENTIAL W/ SHOWER HEAD	67	EA							
2426				SHUTT-OFF VALVE	67	EA							
2427				WATER SUBMETER	67	EA							
2428				WC-1 - WATER CLOSET - RESIDENTIAL	92	EA							
2429	P1-11A TO P3-08			WH-1 - WATER HEATER - MODEL: ENLB-40 - 38 GAL, W/ T&P RELEIF VALVE, VACCUM RELIEF VALVE & WATTS LFBRV COMBINATION BALL & THERMAL RELIEF VALVE, A.O SMITH - PROLINE SERIES	42	EA							
2430				WH-2 - WATER HEATER - MODEL: ENLB-50 - 48 GAL, W/ T&P RELEIF VALVE, VACCUM RELIEF VALVE & WATTS LFBRV COMBINATION BALL & THERMAL RELIEF VALVE, A.O SMITH - PROLINE SERIES	25	EA							
2431	P1-11A TO P3-08			WM-1 - WASHING MACHINE OUTLET BOX, ABS, LEAD FREE W/ QUARTER TURN BALL VALVE, WATER HAMMER ARRESSTOR - SIOUX CHIEF 696-G1010 SERIES	67	EA							
2432				DOMESTIC WATER PIPING									
2433				(BLDG 2000B) (1-1/2") COLD WATER PIPE	255	LF							
2434				(BLDG 2000B) (2") COLD WATER PIPE	60	LF							
2435				(BLDG 2000B) (2-1/2") COLD WATER PIPE	115	LF							
2436				(BLDG 2000B) (3") COLD WATER PIPE	96	LF							
2437				(BLDG 2000B) (4") COLD WATER PIPE	125	LF							
2438				(1/2") COLD WATER PIPE	3258	LF							
2439				(1/2") HOT WATER PIPE	2510	LF							
2440				(1-1/4") COLD WATER PIPE	310	LF							
2441				(3/4") COLD WATER PIPE	2241	LF							
				(3/4") HOT WATER PIPE	2053	LF							
2442				SANITARY PIPING									
2443				(BLDG 2000B) (4") SANITARY PIPE	165	LF							
2444				(BLDG 2000B) (6") SANITARY PIPE	430	LF							
2445				(BLDG 2000B) (8") SANITARY PIPE	170	LF							
2446				(2") SANITARY PIPE	2630	LF							
2447				(2") VENT PIPE	1192	LF							
2448				(3") SANITARY PIPE	3046	LF							
				(3") VENT PIPE	919	LF							
				Subtotal									
				DIVISION 16 - ELECTRICAL									
2449				LIGHT FIXTURE									
				A1 - 6" SURFACE MOUNT LED DOWNLIGHT - MANUF: HALO, MODEL: SLD 1200 SERIES / SLD612835WH/80 CRI/3500K/WHITE	97	EA							
2450				B1 - UNIT ENTRY SCONE - MANUF: SAVOY HOUSE, MODEL: 9- 0901-1-89/GLENN 1-LIGHT WALL SCONE / 7"X12"HX9"D/E26 8W 120V LED BULB (1 PER FIXTURE) / MATTE BLACK FINISH	77	EA							

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHrs/ Unit	\$/Hour	(\$*Per Unit)				
2451	E1-11A TO EP1-32			EMR1 - REMOTE HEAD, PAIRED W/ EMERGENCY FIXTURE OR EXIT SIGN, SINGLE HEAD, MANUF: SURE LITES SRP SERIES	1	EA							
2452				S1 - 4' LED STRIP LIGHT - METALUX SNLED SERIES, LITHONIA	31	EA							
2453				S1E - 4' LED STRIP LIGHT - METALUX SNLED SERIES, LITHONIA W/ 1600 LUMENS BATTERY	5	EA							
2454				S2E - 4' LED VAPORTIGHT STRIP, IMPACT RESISTANT POLYCARBONATE HOUSING, IMPACT RESISTANT FROASTED POLYCARBONATE LENS, LED LAMP, WIDE DISTRIBUTION, MANUF: LITHONIA VAP LED SERIES, PHILIPS W/ 1600 LUMEN BATTERY	4	EA							
2455				S3 - 4' SURFACE/WALL MOUNTED LED FIXTURE, INTEGRAL OCCUPANCY SENSOR W/ 0-10V DIMMING, STEP DIMMING, HIGH LUMEN OUTPUT, INTEGRAL 14W BATTERY PACK, MANUF: METALUX SWLED SERIES LITHONIA	15	EA							
2456				X1 - EXIT SIGN, LED LAMP, POLYCARBONATE HOUSING, SELF CONTAINED BATTERY, MODEL: SURE LITES LPX SERIES LITHONIA	41	EA							
2457				D - 7" SURFACE MOUNTED LED FIXTURE - MANUF: SATCO - S29331 / 7" FLUSH MOUNT LED FIXTURE - ROUND /120V	578	EA							
2458				F - 50" CEILING FAN W/ LED LIGHT KIT - MANUF: CASK INDUSTRIES - CF104/4-BLADE/50"WX19.5"H	189	EA							
2459				P - ISLAND PENDANT - MANUF: KUZCO LIGHTING - MODEL: VANDERBILT 493210-WH/GD/10"DIA X 12"H / 120" MAX CORD LENGTH	189	EA							
2460				VA - VANITY SCONCE - MANUF: QUORUM INTERNATIONAL - MODEL: 507-3-6980/EPsy 3-LIGHT VANITY / 9.25"H X23.5"W X 7"D / 100W MAX WATTAGE	201	EA							
2461	W - EXTERIOR SCONE - MANUF: QUORUM INTERNATIONAL - MODEL: 730-69/TORREY SM LANTERN - NR/13.75"H X 7.5"W X 14.75"D / 100W MAX	77	EA										
2462	E1-11A TO EP1-32			LIGHTING CONTROLS									
				OCCUPANCY SENSOR	1	EA							
2463				OCCUPANCY SENSOR SWITCH	10	EA							
2464				SINGLE POLE SWITCH	1017	EA							
2465				3-WAY SWITCH	354	EA							
				RECEPTACLES & SWITCHES									
2466				DUPLEX RECEPTACLE	1141	EA							
2467				QUAD RECEPTACLE	10	EA							
2468				GFI DUPLEX RECEPTACLE	759	EA							
2469				GFI RECEPTACLE WEATHER PROOF	4	EA							
2470				GFI RECEPTACLE WEATHER PROOF	80	EA							
2471				TWO WAY COMMUNICATION CALL BOX	5	EA							
2472				240 VOLT RECEPTACLE	154	EA							
2473				COMBINATION DATA/ TELE OUTLET	378	EA							
2474				JUNCTION BOX	154	EA							
2475				SPLIT DUPLEX RECEPTACLE	77	EA							
2476	TELEVISION OUTLET	189	EA										
2477	USB DUPLEX RECEPTACLE	219	EA										
2478	USB GFI DUPLEX RECEPTACLE	73	EA										
2479	E1-11A TO EP1-32			DISCONNECT SWITCHES									
				DISCONENCT SWITCH	2	EA							
				LOW VOLTAGE & OTHER ELECTRICAL DEVICES									
2480				METERCENTER ELBOW	5	EA							
2481				(METER STACK	8	EA							
2482				(METERCENTER MAIN	3	EA							
2483				ELECTRIC WIRING	1	LS							
				ELECTRIC BREAKER									
2484				ELECTRIC BREAKER - 1P 20A	1098	EA							
2485				ELECTRIC BREAKER - 2P 30A	150	EA							
2486				ELECTRIC BREAKER - 2P 50A	75	EA							
				ELECTRIC PANEL									
2487	LOAD CENTER - 125A MLO 1PHASE 3W	79	EA										
2488	ELECTRIC PANEL "2B2" - 200A MLO 3PHASE 4W	1	EA										
2489	ELECTRIC PANEL "2B4" - 200A MLO 3PHASE 4W	1	EA										
2490	E1-11A TO EP1-32			FIRE ALARM									
				FIRE ALARM DOOR HOLDER	12	EA							
2491				FIRE ALARM HORN W/STROBE (CANDELAS)	27	EA							
2492				FIRE ALARM PULL STATION	6	EA							
2493				HEAT DETECTOR	1	EA							
2494				HEAT DETECTOR	1	EA							
2495				SPRINKLER FLOW SWITCH	2	EA							
2496				SPRINKLER VALVE TAMPER SWITCH	2	EA							
2497				SMOKE DETECTOR	34	EA							
2498				120V, SELF CONTAINED AUDIBLE CARBON MONOXIDE SMOKE ALARM	119	EA							
2499	120V, SELF CONTAINED AUDIBLE SMOKE ALARM	112	EA										
2500	FIRE ALARM MINI HORN (CANDELAS)	176	EA										
2501	FIRE ALARM MINI HORN W/ STROBE (CANDELAS)	6	EA										
				Subtotal									
				PARKING DECK 01									
			020000	DIVISION 02 - EXISTING CONDITIONS									
			022000	EARTHWORK									
2502	SG-11	S3-02 & AP7-01		Footing excavation.	66410	CF							
2503				Footing backfill.	52490	CF							
				Subtotal									
				DIVISION 03 - CONCRETE									
			030000	CAST IN PLACE CONCRETE									
			033000	(3'8"Wx1'H) CONCRETE FOOTING									
2504	SG-11	S3-02 & AP7-01		Compaction of sub-grade.	335	SF							
2505				Rebar's (Grade 60)	472	LB							
2506				Concrete footing. (fc = 3000 PSI)	295	CF							
				(5'Wx1'H) CONCRETE FOOTING									
2507	SG-11	S3-02 & AP7-01		Compaction of sub-grade.	795	SF							
2508				Rebar's (Grade 60)	1155	LB							
2509				Concrete footing. (fc = 3000 PSI)	725	CF							
				(10'Wx1'H) CONCRETE FOOTING PAD (7 EA)									
2510	SG-11	S3-02 & AP7-01		Compaction of sub-grade.	775	SF							
2511				Rebar's (Grade 60)	1120	LB							
2512				Concrete footing. (fc = 3000 PSI)	700	CF							
				(10'Wx20'Lx1'H) CONCRETE FOOTING PAD (2 EA)									
2513	SG-11	S3-02 & AP7-01		Compaction of sub-grade.	435	SF							
2514				Rebar's (Grade 60)	640	LB							
2515				Concrete footing. (fc = 3000 PSI)	400	CF							
				(11'Wx12"H) RETAINING WALL CONCRETE FOOTING									
2516	SG-11	S3-02 & AP7-01		Compaction of sub-grade.	5215	SF							
2517				Rebar's (Grade 60)	13085	LB							

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHrs/ Unit	\$/Hour	(\$Per Unit)				
2518				Concrete footing. (f'c = 3000 PSI)	5815	CF							
2519	SG-11	S3-02 & AP7-01		RETAINING WALL									
2520				Rebar's (Grade 60) (12" THK) Concrete wall. (f'c = 5000 PSI)	7745	LB							
2521	SG-11	S3-02 & AP7-01		CONCRETE WALL									
2522				Rebar's (Grade 60) (8" THK) Concrete wall. (f'c = 5000 PSI)	500	LB							
2523	SG-11	S3-02 & AP7-01		SLAB ON GRADE									
2524				Compaction of sub-grade.	29760	SF							
2525				Rebar's (Grade 60) (5" Thick) Concrete slab. (f'c = 3000 PSI)	25300	LB							
2526	SG-11	S3-02 & AP7-01		STAIR	29760	SF							
2527				Rebar's (Grade 60) (8" Thick) Concrete stair slab & steps. (f'c = 3000 PSI)	805	LB							
2528	SG-11			(12" THK) Pre-cast spandrel wall.	230	SF							
				Subtotal	4900	SF							
			040000	DIVISION 04 - MASONRY									
			042000	UNIT MASONRY									
				CMU WALL									
2529	SG-11	AP7-01		Rebar's (Grade 60)	820	LB							
2530				(8" THK) CMU wall.	565	SF							
				Subtotal									
			050000	DIVISION 05 - METAL									
			057000	ORNAMENTAL METAL									
2531	A1-11A TO ID-7.3			42" Guard rail.	20	LF							
2532				34" hand rail.	20	LF							
				Subtotal									
			080000	DIVISION 08 - OPENING									
			081113	HOLLOW METAL DOORS, FRAMES AND HARDWARE									
2533	A1-11A TO ID-7.3			(3'-0" W x 7'-0" H) HM door & frame.	5	EA							
2534				(10'-0" W x 7'-0" H) HM door & frame.	1	EA							
			087100	FINISH HARDWARE									
2535	A1-11A TO ID-7.3			Door hardware. (6 EA)	1	LS							
				Subtotal									
			090000	DIVISION 09 - FINISHES									
			092600	GYPSUM BOARD ASSEMBLIES									
2536	A1-11A TO ID-7.3			(1 HR) TYPE 1WB4, GWB UNIT WALL (16 LF)									
2537				(2x4) Wood studs at 16" O.C	120	LF							
2538				(5/8", 1-Layer) Type X, GYP. BD. both side	290	SF							
				(2x4) Top and bottom track.	50	LF							
			093100	CERAMIC / PORCELAIN TILING									
2539	A1-11A TO ID-7.3			Porcelain wall tile.	60	SF							
			096000	FLOORING									
2540	A1-11A TO ID-7.3			Sealed concrete	300	SF							
			099100	PAINTING									
2541	A1-11A TO ID-7.3			GWB wall paint.	300	SF							
				Subtotal									
			150000	DIVISION 15 - HEATING, VENTILATING, AND AIR- CONDITIONING (HVAC)									
2542	M1-11A TO MP1-21			DS P1-1 - Ductless split system w/ Heat pump Outdoor unit DSHP P1-1, Manuf: MITSUBISHI ELECTRIC, MODEL: PKA/PUZ, (705 CFM)	1	EA							
2543				EF P1-1 - EXHAUST FAN - MANUF: BROAN, MODEL: AE80, (80 CFM)	1	EA							
2544				EF P1-2 - EXHAUST FAN - MANUF: BROAN, MODEL: L200, (200 CFM)	1	EA							
				Subtotal									
			150000	DIVISION 15 - PLUMBING									
2545				BACKFLOW PREVENTER W/ SHUTT OFF VALVE	1	EA							
2546				EH P1-1 - ELECTRIC HEATER, MANUF: MARLEY, MODEL NO: AWH (100 CFM)	1	EA							
2547				FCO - FLOOR CLEANOUT - CAST IRON CLEANOUT W/ GSKET SEAL & THREADED PLUG, ADJUSTABLE CAST IRON ROUND TOP W/ SECURING SCREW - JAY R. SMITH FIGURE 4220	2	EA							
2548				FD-1 - (2") FLOOR DRAIN - CAST IRON FLOOR DRAIN W/ (6") SQUARE NICKEL BRONZE STRAINER, SPEEDI-SET OUTLET, & TRAP PRIMER - JAY R SMITH FIGURE 2005-B6	1	EA							
2549				FD-2 - (4") FLOOR DRAIN - CAST IRON (12"Dia) DRAIN W/ SEDIMENT BUCKET, Cast IRON GRATE, Speedi set OUTLET, & TRAP PRIMER - JAY R. SMITH FIGURE 2142-M	1	EA							
2550				LV-3A - LAVATORY - WALL HUNG	1	EA							
2551				DOMESTIC WATER PIPING									
				(2") DOMESTIC SERVICE LINE	15	LF							
2552				SANITARY PIPING									
2553				(10") SANITARY PIPING	265	LF							
2554				(12") SANITARY PIPING	50	LF							
				(4") SANITARY PIPE	15	LF							
				Subtotal									
			160000	DIVISION 16 - ELECTRICAL									
				LIGHT FIXTURE									
2555				02 - LED AREA LIGHT, TWIN-HEADS, FULL CUTOFF, TYPE 4 MEDIUM DISTRIBUTION, W/ ALUMINUM POLE, MANUF: LITHONIA DSX1 SERIES	4	EA							
2556				S1 - 4' LED STRIP LIGHT - METALUX SNLED SERIES, LITHONIA	5	EA							
2557				S2 - 4' LED VAPORTIGHT STRIP, IMPACT RESISTANT POLYCARBONATE HOUSING, IMPACT RESISTANT FROASTED POLYCARBONATE LENS, LED LAMP, WIDE DISTRIBUTION, MANUF: LITHONIA VAP LED SERIES, PHILIPS	26	EA							

#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHrs/ Unit	\$/Hour	(\$Per Unit)				
2558	E1-11A TO EPI-32			S2E - 4' LED VAPORTIGHT STRIP, IMPACT RESISTANT POLYCARBONATE HOUSING, IMPACT RESISTANT FROASTED POLYCARBONATE LENS, LED LAMP, WIDE DISTRIBUTION, MANUF: LITHONIA VAP LED SERIES, PHILIPS W/ 1600 LUMEN BATTERY	33	EA							
2559				S3 - 4' SURFACE/WALL MOUNTED LED FIXTURE, INTEGRAL OCCUPANCY SENSOR W/ 0-10V DIMMING, STEP DIMMING, HIGH LUMEN OUTPUT, INTEGRAL 14W BATTERY PACK, MANUF: METALUX SWLED SERIES LITHONIA	3	EA							
2560				S3 - 4' SURFACE/WALL MOUNTED LED FIXTURE, INTEGRAL OCCUPANCY SENSOR W/ 0-10V DIMMING, STEP DIMMING, HIGH LUMEN OUTPUT, INTEGRAL 14W BATTERY PACK, MANUF: METALUX SWLED SERIES LITHONIA	1	EA							
2561				X1 - EXIT SIGN, LED LAMP, POLYCARBONATE HOUSING, SELF CONTAINED BATTERY, MODEL: SURE LITES LPX SERIES LITHONIA WEATHER PROOF	7	EA							
2562	E1-11A TO EPI-32			LIGHTING CONTROLS OCCUPANCY SENSOR SWITCH	3	EA							
2563				RECEPTACLES & SWITCHES GFI DUPLEX RECEPTACLE	2	EA							
2564				GFI DUPLEX RECEPTACLE WEATHER PROOF	2	EA							
2565				JUNCTIN BOX	1	EA							
2566				ELECTRIC PANEL "P" - 200A MCB 3PHASE 4W	1	EA							
2567				ELECTRIC PANEL "1G1" - 400A MCB 3PHASE 4W	1	EA							
2568				ELECTRIC BREAKER 1P 20A	10	EA							
2569				ELECTRIC WIRING	1	LS							
				Subtotal									
			100000	DIVISION 10 - SPECIALTIES									
			102813	TOILET AND BATH ACCESSORIES									
2570	A1-11A TO ID-7.3			Mirror.	1	EA							
2571				Toilet paper holder.	1	EA							
2572				Tower bar.	1	EA							
				Subtotal									
				PARKING DECK 02									
			020000	DIVISION 02 - EXISTING CONDITIONS									
			022000	EARTHWORK									
2573	SG-12	S3-02 & AP7-02		Footing excavation.	2980	CF							
2574					Footing backfill.	575	CF						
				Subtotal									
			030000	DIVISION 03 - CONCRETE									
			033000	CAST IN PLACE CONCRETE									
2575	SG-12	S3-02 & AP7-02		(3'8"Wx1'H) CONCRETE FOOTING Compaction of sub-grade.	265	SF							
2576					Rebar's (Grade 60)	375	LB						
2577					Concrete footing. (fc = 3000 PSI)	235	CF						
2578	SG-12	S3-02 & AP7-02		(5'Wx1'H) CONCRETE FOOTING Compaction of sub-grade.	655	SF							
2579					Rebar's (Grade 60)	950	LB						
2580					Concrete footing. (fc = 3000 PSI)	595	CF						
2581	SG-12	S3-02 & AP7-02		(10'Wx1'H) CONCRETE FOOTING PAD (10 EA) Compaction of sub-grade.	1105	SF							
2582					Rebar's (Grade 60)	1600	LB						
2583					Concrete footing. (fc = 3000 PSI)	1000	CF						
2584	SG-12	S3-02 & AP7-02		(10'Wx20'Lx1'H) CONCRETE FOOTING PAD (2 EA) Compaction of sub-grade.	435	SF							
2585					Rebar's (Grade 60)	640	LB						
2586					Concrete footing. (fc = 3000 PSI)	400	CF						
2587	SG-12	S3-02 & AP7-02		CONCRETE WALL Rebar's (Grade 60)	1120	LB							
2588					(8" THK) Concrete wall. (fc = 5000 PSI)	700	CF						
2589	SG-12	S3-02 & AP7-02		SLAB ON GRADE Compaction of sub-grade.	26455	SF							
2590					Rebar's (Grade 60)	22485	LB						
2591					(5" Thick) Concrete slab. (fc = 3000 PSI)	26455	SF						
2592	SG-12	S3-02 & AP7-02		STAIR Rebar's (Grade 60)	2100	LB							
2593					(8" Thick) Concrete stair slab & steps. (fc = 3000 PSI)	600	SF						
2594	SG-12			(12" THK) Pre-cast spandrel wall.	9260	SF							
				Subtotal									
			040000	DIVISION 04 - MASONRY									
			042000	UNIT MASONRY									
2595	SG-12	AP7-02		CMU WALL Rebar's (Grade 60)	240	LB							
2596					(8" THK) CMU wall.	165	SF						
				Subtotal									
			050000	DIVISION 05 - METAL									
			057000	ORNAMENTAL METAL									
2597	A1-11A TO ID-7.3			42" Guard rail.	56	LF							
2598				34" hand rail.	35	LF							
				Subtotal									
			080000	DIVISION 08 - OPENING									
			081113	HOLLOW METAL DOORS, FRAMES AND HARDWARE									
2599	A1-11A TO ID-7.3			(3'-0" W x 7'-0" H) HM door & frame.	5	EA							
			087100	FINISH HARDWARE									
2600	A1-11A TO ID-7.3			Door hardware. (5 EA)	1	LS							
				Subtotal									
			090000	DIVISION 09 - FINISHES									
			096000	FLOORING									
2601	A1-11A TO ID-7.3			Sealed concrete	50	SF							
				Subtotal									
			150000	PARKING DECK 02									
				DIVISION 15 - PLUMBING									

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHrs/ Unit	\$/Hour	(\$Per Unit)				
2602				EH P2-1 - ELECTRIC HEATER, MANUF: MARLEY, MODEL NO: AWH (100 CFM)	1	EA							
2603				EH P2-2 - ELECTRIC HEATER, MANUF: MARLEY, MODEL NO: AWH (100 CFM)	1	EA							
2604				FCO - FLOOR CLEANOUT - CAST IRON CLEANOUT W/ GSKET SEAL & THREADED PLUG, ADJUSTABLE CAST IRON ROUND TOP W/ SECURING SCREW - JAY R. SMITH FIGURE 4220	2	EA							
2605				SANITARY PIPING									
2606				(10") SANITARY PIPING	235	LF							
				(12") SANITARY PIPING	55	LF							
				Subtotal									
			160000	DIVISION 16 - ELECTRICAL									
				LIGHT FIXTURE									
2607				02 - LED AREA LIGHT, TWIN-HEADS, FULL CUTOFF, TYPE 4 MEDIUM DISTRIBUTION, W/ ALUMINUM POLE, MANUF: LITHONIA DSX1 SERIES	4	EA							
2608				EMR1 - REMOTE HEAD, PAIRED W/ EMERGENCY FIXTURE OR EXIT SIGN, SINGLE HEAD, MANUF: SURE LITES SRP SERIES	2	EA							
2609				S1 - 4' LED STRIP LIGHT - METALUX SNLED SERIES, LITHONIA	1	EA							
2610				S2 - 4' LED VAPORTIGHT STRIP, IMPACT RESISTANT POLYCARBONATE HOUSING, IMPACT RESISTANT FROASTED POLYCARBONATE LENS, LED LAMP, WIDE DISTRIBUTION, MANUF: LITHONIA VAP LED SERIES, PHILIPS	24	EA							
2611				S2E - 4' LED VAPORTIGHT STRIP, IMPACT RESISTANT POLYCARBONATE HOUSING, IMPACT RESISTANT FROASTED POLYCARBONATE LENS, LED LAMP, WIDE DISTRIBUTION, MANUF: LITHONIA VAP LED SERIES, PHILIPS W/ 1600 LUMEN BATTERY	34	EA							
2612				S3 - 4' SURFACE/WALL MOUNTED LED FIXTURE, INTEGRAL OCCUPANCY SENSOR W/ 0-10V DIMMING, STEP DIMMING, HIGH LUMEN OUTPUT, INTEGRAL 14W BATTERY PACK, MANUF: METALUX SWLED SERIES LITHONIA	8	EA							
2613				X1 - EXIT SIGN, LED LAMP, POLYCARBONATE HOUSING, SELF CONTAINED BATTERY, MODEL: SURE LITES LPX SERIES LITHONIA WEATHER PROOF	11	EA							
2614				LIGHTING CONTROLS									
				OCCUPANCY SENSOR SWITCH	1	EA							
2615				RECEPTACLES & SWITCHES									
2616				GFI DUPLEX RECEPTACLE WEATHER PROOF	6	EA							
2617				JUNCTION BOX	1	EA							
2618				ELECTRIC PANEL "2G1" - 400A MCB 3PHASE 4W	1	EA							
2619				ELECTRIC BREAKER 1P 20A	12	EA							
				ELECTRIC WIRING	1	LS							
2620				FIRE ALARM									
				SPRINKLER FLOW SWITCH	4	EA							
2621				SPRINKLER VALVE TAMPER SWITCH	4	EA							
				Subtotal									
				PARKING DECK 03									
			020000	DIVISION 02 - EXISTING CONDITIONS									
			022000	EARTHWORK									
2622	SG-13	S3-02 & AP7-03		Footing excavation.	4050	CF							
2623				Footing backfill.	575	CF							
				Subtotal									
			030000	DIVISION 03 - CONCRETE									
			033000	CAST IN PLACE CONCRETE									
2624	SG-13	S3-02 & AP7-03		(3'8"Wx1'H) CONCRETE FOOTING									
2625				Compaction of sub-grade.	355	SF							
2626				Rebar's (Grade 60)	495	LB							
				Concrete footing. (f'c = 3000 PSI)	310	CF							
2627	SG-13	S3-02 & AP7-03		(5'Wx1'H) CONCRETE FOOTING									
2628				Compaction of sub-grade.	1290	SF							
2629				Rebar's (Grade 60)	1880	LB							
				Concrete footing. (f'c = 3000 PSI)	1175	CF							
2630	SG-13	S3-02 & AP7-03		(10'Wx1'H) CONCRETE FOOTING PAD (14 EA)									
2631				Compaction of sub-grade.	1545	SF							
2632				Rebar's (Grade 60)	2240	LB							
				Concrete footing. (f'c = 3000 PSI)	1400	CF							
2633	SG-13	S3-02 & AP7-03		(10'Wx20'Lx1'H) CONCRETE FOOTING PAD (4 EA)									
2634				Compaction of sub-grade.	865	SF							
2635				Rebar's (Grade 60)	1280	LB							
				Concrete footing. (f'c = 3000 PSI)	800	CF							
2636	SG-13	S3-02 & AP7-03		CONCRETE WALL									
2637				Rebar's (Grade 60)	1490	LB							
				(8" THK) Concrete wall. (f'c = 5000 PSI)	930	CF							
2638	SG-13	S3-02 & AP7-03		SLAB ON GRADE									
2639				Compaction of sub-grade.	40355	SF							
2640				Rebar's (Grade 60)	34300	LB							
				(5" Thick) Concrete slab. (f'c = 3000 PSI)	40355	SF							
2641	SG-13	S3-02 & AP7-03		STAIR									
2642				Rebar's (Grade 60)	2415	LB							
2643				(8" Thick) Concrete stair slab & steps. (f'c = 3000 PSI)	690	SF							
				(12" THK) Pre-cast spandrel wall.	12085	SF							
				Subtotal									
			040000	DIVISION 04 - MASONRY									
			042000	UNIT MASONRY									
2644	SG-13	AP7-03		CMU WALL									
2645				Rebar's (Grade 60)	240	LB							
				(8" THK) CMU wall.	165	SF							
				Subtotal									
			050000	DIVISION 05 - METAL									
			057000	ORNAMENTAL METAL									
2646	A1-11A TO ID-7.3			42" Guard rail.	60	LF							
2647				34" hand rail.	35	LF							
				Subtotal									
			080000	DIVISION 08 - OPENING									
			081113	HOLLOW METAL DOORS, FRAMES AND HARDWARE									
2648	A1-11A TO ID-7.3			(3'-0" W x 7'-0" H) HM door & frame.	7	EA							

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHrs/ Unit	\$/Hour	(\$Per Unit)				
			087100	FINISH HARDWARE									
2649	A1-11A TO ID-7.3			Door hardware. (7 EA)	1	LS							
				Subtotal									
			090000	DIVISION 09 - FINISHES									
			096000	FLOORING									
2650	A1-11A TO ID-7.3			Sealed concrete	50	SF							
				Subtotal									
				PARKING DECK 03									
			150000	DIVISION 15 - PLUMBING									
2651				EH P3-1 - ELECTRIC HEATER, MANUF: MARLEY, MODEL NO: AWH (100 CFM)	1	EA							
2652				EH P3-2 - ELECTRIC HEATER, MANUF: MARLEY, MODEL NO: AWH (100 CFM)	1	EA							
2653				EH P3-3 - ELECTRIC HEATER, MANUF: MARLEY, MODEL NO: AWH (100 CFM)	1	EA							
2654				FCO - FLOOR CLEANOUT - CAST IRON CLEANOUT W/ GSKET SEAL & THREADED PLUG, ADJUSTABLE CAST IRON ROUND TOP W/ SECURING SCREW - JAY R. SMITH FIGURE 4220	4	EA							
2655				SANITARY PIPING									
2656				(10") SANITARY PIPE	140	LF							
2657				(12") SANITARY PIPE	30	LF							
2658				(15") SANITARY PIPE	70	LF							
				(8") SANITARY PIPE	190	LF							
				Subtotal									



99 ESTIMATORS

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHrs/ Unit	\$/Hour	(\$Per Unit)				
			160000	DIVISION 16 - ELECTRICAL									
				LIGHT FIXTURE									
2659				S1 - 4' LED STRIP LIGHT - METALUX SNLED SERIES, LITHONIA	1	EA							
2660				S2 - 4' LED VAPORTIGHT STRIP, IMPACT RESISTANT POLYCARBONATE HOUSING, IMPACT RESISTANT FROASTED POLYCARBONATE LENS, LED LAMP, WIDE DISTRIBUTION, MANUF: LITHONIA VAP LED SERIES, PHILIPS	38	EA							
2661				S2E - 4' LED VAPORTIGHT STRIP, IMPACT RESISTANT POLYCARBONATE HOUSING, IMPACT RESISTANT FROASTED POLYCARBONATE LENS, LED LAMP, WIDE DISTRIBUTION, MANUF: LITHONIA VAP LED SERIES, PHILIPS W/ 1600 LUMEN BATTERY	50	EA							
2662				S3 - 4' SURFACE/WALL MOUNTED LED FIXTURE, INTEGRAL OCCUPANCY SENSOR W/ 0-10V DIMMING, STEP DIMMING, HIGH LUMEN OUTPUT, INTEGRAL 14W BATTERY PACK, MANUF: METALUX SWLED SERIES LITHONIA	12	EA							
2663				X1 - EXIT SIGN, LED LAMP, POLYCARBONATE HOUSING, SELF CONTAINED BATTERY, MODEL: SURE LITES LPX SERIES LITHONIA WEATHER PROOF	16	EA							
2664				02 - LED AREA LIGHT, TWIN-HEADS, FULL CUTOFF, TYPE 4 MEDIUM DISTRIBUTION, W/ ALUMINUM POLE, MANUF: LITHONIA DSX1 SERIES	8	EA							
2665				EMR1 - REMOTE HEAD, PAIRED W/ EMERGENCY FIXTURE OR EXIT SIGN, SINGLE HEAD, MANUF: SURE LITES SRP SERIES	2	EA							
				RECEPTACLES & SWITCHES									
2666				OCCUPANCY SENSOR SWITCH	1	EA							
2667				GFI DUPLEX RECEPTACLE WEATHER PROOF	7	EA							
2668				JUNCTION BOX	1	EA							
2669				ELECTRIC PANEL "3G1" - 400A MCB 3PHASE 4W	1	EA							
2670				ELECTRIC BREAKER 1P 20A	20	EA							
2671				ELECTRIC WIRING	1	LS							
				FIRE ALARM									
2672				SPRINKLER FLOW SWITCH	5	EA							
2673				SPRINKLER VALVE TAMPER SWITCH	5	EA							
				Subtotal									
				Total									
				Add wastage of materials									
				Add Contractor's overhead & profit @ 15%									
				G.Total									



99 ESTIMATORS